

AD-A149 773 LITTLE RIVER INLET NAVIGATION PROJECT BRUNSWICK COUNTY 1/2  
NORTH CAROLINA AND. (U) CORPS OF ENGINEERS CHARLESTON  
SC CHARLESTON DISTRICT JUN 77


AD-A149 773 LITTLE RIVER INLET NAVIGATION PROJECT BRUNSWICK COUNTY 1/2  
NORTH CAROLINA AND. (U) CORPS OF ENGINEERS CHARLESTON  
SC CHARLESTON DISTRICT JUN 77

AD-A149 773 LITTLE RIVER INLET NAVIGATION PROJECT BRUNSWICK COUNTY 1/2  
NORTH CAROLINA AND. (U) CORPS OF ENGINEERS CHARLESTON  
SC CHARLESTON DISTRICT JUN 77

UNCLASSIFIED F/G 13/2 NL

UNCLASSIFIED F/G 13/2 NL

UNCLASSIFIED F/G 13/2 NL



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS 1963 A

AD-A149 773


REVISED

FINAL

ENVIRONMENTAL IMPACT STATEMENT

Copy available to DTIC and not  
permit fully legible reproduction

LITTLE RIVER INLET  
NAVIGATION PROJECT  
BRUNSWICK COUNTY, NORTH CAROLINA  
AND Horry County, SOUTH CAROLINA



Approved for Public Release: Estimated Release

FILE

Prepared by  
U. S. ARMY ENGINEER DISTRICT, CHARLESTON, SOUTH CAROLINA

June 1977

85 01 14 129

(1)

JAN 9 1971

SUMMARY

Little River Inlet Navigation Project, Brunswick County, North Carolina  
and Horry County, South Carolina

( ) Draft

(X) Final Environmental Statement

Responsible Office: U. S. Army Engineer District  
P. O. Box 919  
Charleston, South Carolina 29402  
Telephone: 803-577-4171, Ext. 229

1. Name of Action: (X) Administrative ( ) Legislative
2. Description of Action: The recommended plan of improvement consists of the following: dredging an entrance channel, 300 feet wide and 12 feet deep through the offshore bar, a distance of approximately 5,160 feet; providing an inner channel, 90 feet wide and 10 feet deep from the entrance channel to the Atlantic Intracoastal Waterway, a distance of 11,000 feet; dredging the lower 5,200 feet of the inner channel; dredging an upcoast deposition basin adjacent to the weir section of the north jetty to a depth of -20 feet to provide a capacity of 400,000 cubic yards; dredging a downcoast deposition basin adjacent to the weir section of the south jetty to a depth of -10 feet to provide a capacity of 200,000 cubic yards; constructing a north jetty 3,835 feet long with a low weir section for sand bypassing; constructing a south jetty 3,570 feet long with a low weir section for sand bypassing; constructing sand dikes on both sides of the inlet to tie the jetties to the existing dune line; and possibly constructing a fishing walkway on top of the south jetty.
3. a. Environmental Impacts: Short-term increase in turbidity; alteration of existing vegetation during construction of south sand dike; temporary frightening of birds and mammals in the area; destruction of some benthic organisms by dredge cutterhead; smothering of invertebrates under jetty stone and in beach disposal areas; improvement of navigation with associated benefits to local economy, charter and commercial fishing industries, and recreational boaters; and increase in recreational opportunities.  
  
b. Adverse Environmental Effects: Temporary increase in turbidity; alteration of existing vegetation during construction of south sand dike; temporary disturbance of birds and mammals in the area; destruction of some benthic organisms by dredge cutterhead; smothering of invertebrates under jetty stone and in beach disposal area; and possible displacement of wildlife species.
4. Alternatives. Alternatives to the proposed action include no action; channel improvement without structural control; modified structural controls; and alternate channel depths.

This document is to be approved  
for public release and, if its  
distribution is authorized.

Original contains color  
plates. All DTIC reproductions  
will be in black and  
white.

5. Comments received from:


U. S. Environmental Protection Agency  
U. S. Department of Interior  
U. S. Department of Commerce  
Forest Service, USDA  
Soil Conservation Service, USDA  
Department of Health, Education, and Welfare  
Department of Housing and Urban Development  
Federal Highway Administration, USDT  
North Carolina Office of Marine Affairs  
North Carolina Department of Human Resources  
North Carolina Department of Natural and Economic Resources  
South Carolina Wildlife and Marine Resources Department  
South Carolina Department of Health and Environmental Control  
South Carolina Department of Archives and History  
South Carolina Water Resources Commission  
Cape Fear Council of Governments  
Waccamaw Regional Planning and Development Council

6. Draft Statement to CEQ 20 January 1972.

Final Statement to CEQ 19 September 1972.

Revised Draft Statement to CEQ 30 September 1976.

Revised Final Statement to CEQ 27 May 1977.



# Table of Contents

	<u>Para. No.</u>	<u>Page No.</u>
PROJECT DESCRIPTION	1.0	1
Project authorization	1.01	1
Project purpose	1.02	1
Description of proposed plan of improvement	1.03	1
Upcoast jetty	1.04	1
Downcoast jetty	1.05	1
Sand dikes	1.06	2
Deposition basins	1.07	2
Entrance channel	1.08	2
Inner channel	1.09	3
Recreation facilities	1.10	3
Fishing walkway	1.12	3
Comfort station	1.13	3
Power supply	1.14	3
Water supply	1.15	4
Sewage disposal	1.16	4
Parking	1.17	4
Proposed dredged materials quantities and placement plan	1.18	4
Entrance channel	1.19	4
Inner channel	1.20	4
Deposition basins	1.21	4
Operation and maintenance	1.22	5
Channels	1.23	5
Jetties	1.24	5
Recreational facilities	1.25	5
Special studies	1.26	5
Environmental studies	1.27	5
Model study	1.28	6
Monitoring of project effects	1.30	7
ENVIRONMENTAL SETTING WITHOUT THE PROJECT	2.0	7a
General	2.01	7a
History of Little River Inlet shoaling problem	2.02	7a
Other Federal projects	2.03	8
Regional physiography and geology	2.05	9
Soils	2.09	10
Capers Association	2.10	10
Wando-coastal beach association	2.11	10
Little River Inlet sediments	2.13	10
Littoral drift	2.14	11
Ground water	2.15	11
Surface water	2.16	12
Tides	2.18	12
Water quality	2.19	12
Climatology	2.20	13
Biological resources	2.21	13
General	2.22	13

	Para. No.	Page No.
Beach	2.24	14
Dune	2.30	15
Maritime shrub/thicket	2.32	16
Pine forest	2.35	17
Oak-pine forest	2.37	18
Open water	2.38	19
Nekton	2.40	19
Benthos	2.41	19
Benthic macroinvertebrate studies	2.45	20
Entrance channel	2.46	21
Inner channel	2.47	21
Adjacent waterways	2.49	22
Oyster reefs	2.50	22
Clam resources	2.51	22
Other animals in the open water community	2.52	22
Tidal marsh	2.53	24
Sand and/or mud flats	2.60	26
Disposal areas	2.62	27
Sport and commercial fisheries	2.63	27
Recreation	2.65	27
Historical sites	2.67	28
Archaeology	2.70	28
Economic indicators	2.73	29
Population	2.74	29
Employment	2.75	29
Income	2.77	30
Commercial recreation	2.79	30
Amusement and recreation services	2.80	30
Transportation	2.82	31
Nature environmental setting without the project	2.83	31
RELATIONSHIP OF THE PROPOSED ACTION TO LAND		
USE PLANS	3.0	32
THE PROBABLE IMPACT OF THE PROPOSED ACTION ON		
THE ENVIRONMENT	4.0	32
Water quality	4.01	32
Fishes	4.02	33
Biological resources	4.03	33
Open water community	4.04	33
Benthic invertebrates	4.05	33
Fish	4.10	34
Commercial fisheries	4.14	36
Beach community	4.15	36
Oysters	4.16	36
Clams	4.17	36
Marsh	4.18	36
Pine forest	4.19	37
Endangered species	4.20	37

	<u>Para. No.</u>	<u>Page No.</u>
Mosquitoes	4.21	37
Archaeological and historical sites	4.22	37
Recreation	4.23	37
Aesthetics	4.24	38
Noise and air quality	4.25	38
Economic impact	4.26	38
Maintenance dredging	4.28	38
Sand bypassing	4.29	39
ANY PROBABLE ADVERSE EFFECTS WHICH CANNOT BE AVOIDED	5.0	39
ALTERNATIVES TO THE PROPOSED ACTION	6.0	39
General	6.01	39
Non-structural alternatives	6.02	39
Structural alternatives	6.07	40
Alternative depths	6.09	41
No action	6.11	42
Disposal alternatives	6.14	42
THE RELATIONSHIP BETWEEN LOCAL SHORT-TERM USES OF MAN'S ENVIRONMENT AND THE MAINTENANCE AND ENHANCEMENT OF LONG-TERM PRODUCTIVITY	7.0	42
ANY IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES WHICH WOULD BE INVOLVED IN THE PROPOSED ACTION SHOULD IT BE IMPLEMENTED	8.0	43
COORDINATION AND COMMENT AND RESPONSE	9.0	43
List of references		50
Glossary		54

#### List of Plates

	<u>Page No.</u>
1 Navigation project - General plan	59
2 Jetty and entrance channel plan	60
3 Upcoast jetty profile and jetty sections	61
4 Downcoast jetty profile	62
5 Recreation plan	63
6 Quarternary formations and terraces of a portion of the South Carolina coastal plain	64
7 Location of S. C. Wildlife and Marine Resources Department benthic sampling stations	65
8 Geomorphic changes at Little River Inlet, N.C. and S.C.	66
9 Intertidal oyster surveys	67
10 Clam survey	68
11 Biotic communities of Little River Inlet	69



## List of Tables

	<u>Page No.</u>
Test results - Little River Inlet	70
Chemical analysis of sediment samples from the Little River Inlet area	71
Macroinvertebrates collected during benthic studies in Little River Inlet	72
Species of macroinvertebrates collected on Waties Island and Bird Island beaches and their esti- mated densities in numbers $m^2$	73
Species of macroinvertebrates collected in the entrance channel and their estimated densities in numbers $m^2$	74
Benthic invertebrates from dredge collections at nine stations in the entrance channel	77
Species of macroinvertebrates collected in the inner channel and their estimated den- sities in numbers $m^2$	78
Benthic invertebrates from oyster dredge collections at nine stations in the inner channel	81
Species of macroinvertebrates collected in adjacent waterways and their estimated densities in numbers $m^2$	84
Benthic invertebrates from oyster dredge collections at eight stations in adjacent waterways	87
List of observed marsh and marsh bordering plants in the Little River Inlet study area	90
Results of MRD field observations of 19 marsh locations in Little River Inlet study area	91
Commercial fishery landings	92
Confidence levels of improvement for navigation facil- ities	93

## List of Appendices

Appendix A	
Chemical analysis	
Appendix B	
Consent	
Appendix C	
Consent List for Section 404 Evaluation	

Revised  
Final  
Environmental Statement  
Little River Inlet Navigation Project  
Brunswick County, North Carolina and  
Horry County, South Carolina

1.0 Project Description

1.01 Project authorization. The Little River Inlet Navigation Project (Plate 1) was authorized by the Congress of the United States on 12 October 1972 under Section 201 of Public Law 298, 89th Congress (House Document 92-362, 92nd Congress, 1st Session).

1.02 Project purpose. The purpose of this project is to provide a stabilized channel from the 12-foot contour in the open ocean to the Atlantic Intracoastal Waterway (AIWW) of sufficient depth and width for regular use by commercial and recreational vessels. The benefit-to-cost ratio (navigation facilities only) of the proposed project is 1.2:1. A summary of project economic data is presented in Appendix A.

1.03 Description of the proposed plan of improvement. The proposed plan provides for the construction of an upcoast jetty with a low weir section, a downcoast jetty with a low weir section, sand dikes (downcoast with protective berm), two deposition basins, entrance channel and inner channel. The two jetties, sand dikes, deposition basins, entrance channel and that portion of the inner channel requiring dredging are shown on Plate 2. Plate 1 shows the extension of the inner channel to the AIWW.

1.04 Upcoast jetty. The jetty would be composed of a low weir section, trunk section, and a head section. The low weir section would have a length of 1,275 feet and an elevation of 2.3 feet, which elevation would allow the passage of littoral drift moving between the shoreline and -4 foot mean low water (mlw). The low weir section would be connected to a sand dike described in Section 1.06 by a jetty section 200 feet in length, 114.5 feet at elevation 8 feet msl sloping to an elevation of 2.3 feet mlw at the juncture with the low weir section. The trunk section would extend a distance of 2,085 feet seaward of the low weir section and would have an elevation of 8 feet mlw and a crest width of 15 feet. The head section would extend a distance of 150 feet seaward from the trunk section and would be constructed to the same elevation as the trunk section. It would however be wider and would have an additional armor layer. The total length of this jetty would be 3,710 feet.

1.05 Downcoast jetty. This jetty would be similar to the upcoast jetty but differs in the following features. The length of the low weir section would be 1,310 feet and the length of the trunk

section would be 1,830 feet, giving a total length of 3,490 feet. Although the elevation of the low weir section in both jetties is the same, littoral drift patterns and shoreline configurations indicate that the low weir section in the downcoast jetty will allow the passage of littoral drift moving between the shoreline and -2 feet mlw.

1.06 Sand dikes. Sand dikes would be constructed from the shoreward end of the weirs to the existing dune line at 10 feet mlw. The upcoast sand dike would consist of strengthening (widening) an existing sand dune and extending it to the mean low water line. The length of upcoast sand dike would be about 2,330 feet. The downcoast sand dike would extend from the shoreward end of the downcoast weir to the existing high ground at elevation 10 feet mlw, a length of about 4,970 feet. The dike would have a crest width of 100 feet and side slopes of 1 vertical on 25 horizontal. The downcoast sand dike would have a berm on the bayward side at elevation 8 feet mlw between the east tip of Waties Island and the downcoast deposition basin. The berm would provide protection to the sand dike and downcoast deposition basin from high ebb tide velocities and would confine flow within the channels. The dikes would be constructed of hydraulic, granular fill dredged from the channels and deposition basins. Upon completion of construction, the sand dikes will be planted with sea oats, panic grass, beach grass, or other salt-tolerant plant species to aid in erosion control. Profiles and typical sections of the jetties and sand dikes are shown on Plate 4.

1.07 Deposition basins. Following construction of the jetties, deposition basins would be dredged between the weirs and the entrance channel with a pipeline dredge to trap littoral material moving in either the upcoast or downcoast direction over the weirs. The upcoast basin would be dredged to a depth of -20.0 feet mlw and would have a capacity of 400,000 cubic yards and the downcoast basin would have a depth of -10.0 feet mlw with 200,000 cubic yards capacity. The sides of the basins (bottom dimensions) adjacent to the weirs will be 1,125 and 1,160 feet for the upcoast and downcoast weirs, respectively; the other dimensions of the basins will be commensurate with the aforementioned basin capacities. The capacity of the deposition basins will be sufficient to contain an estimated two-year accumulation of littoral drift material.

1.08 Entrance channel. The entrance channel would extend from the -12-foot ocean contour to the inner channel, a length of about 5,160 feet. The entrance channel will be 300 feet wide and 12 feet deep. An allowable overdepth of 2 feet will be permitted to compensate for dredging inaccuracies. Side slopes of 1 vertical on 4 horizontal are expected initially after the box-cut dredging of the channel. Due to the wave action in the entrance channel, the ultimate side slope will probably be 1 vertical on 10 horizontal. The distance between the edge of the channel and the jetty toe are sufficient to allow for this ultimate side slope.

1.09 Inner channel. The inner channel would extend from the entrance channel up Little River to the AIWW, a length of 11,000 feet. Only the lower 5,200 feet of the channel will require dredging. The inner channel will be 90 feet wide and 10 feet deep. An allowable overdepth of two feet will be permitted to compensate for dredging inaccuracies. Side slopes of 1 vertical on 4 horizontal are expected after the box-cut dredging of the channel. Since there is little or no wave action in the inner channel, it is believed that this slope would be stable.

1.10 Recreation facilities. At the time of the project document, a fishing walkway was not economically justified because of the lack of access to Waties and Bird Islands which are privately owned. In addition to the foregoing, there was no expression of interest (on the part of legally responsible and financially capable state or local agencies) in participating in the construction of a jetty fishing walkway. Recently, however, the South Carolina Department of Parks, Recreation and Tourism has shown an interest in purchasing Waties Island for development as a park and would be interested in participating in a jetty fishing walkway if a state park is subsequently developed. The proposed Waties Island State Park borders on the west side of Little River Inlet. Should the South Carolina Department of Parks, Recreation and Tourism purchase the island, a fishing walkway, comfort station, and access trail could be justified. As shown in Appendix A, apportionment of first costs for recreational development would be 50% Federal and 50% State.

1.11 The recommended plan of improvement (Plate 5) would provide for a 6-foot wide bridge over the weir section and an 8-foot wide fishing walkway constructed on the downcoast jetty along its entire length; a paved access trail from the parking area to the walkway area, a parking area for the walkway and the other activities in this segment of the park area; and a toilet facility located in the general vicinity of the picnic area, as shown on Plate 5. All facilities would be designed in accordance with the latest criteria for design of facilities for handicapped persons.

1.12 Fishing walkway. The timber portion of the walkway bridging the weir would have a deck at elevation 15 feet mhw which corresponds to the 10-year frequency storm wave level. The deck would be 6 feet wide with handrails on both sides for safety. The asphalt portion of the walkway would be 8 feet wide and would extend the entire length of the downcoast rubble mound section. The downcoast jetty would be raised 1 foot for the safety of fishermen and sightseers and to make the jetty usable during spring tides.

1.13 Comfort station. The comfort station would be designed in accordance with a standard plan of the South Carolina State Department of Parks, Recreation and Tourism. This building would be compatible with the picnic shelters and other facilities of the proposed park.

1.14 Power supply. The Department of Parks, Recreation and Tourism would provide power at the transport and recreation area which could be extended to the well pump and comfort station. Power will only be needed for lighting in the comfort station and for the water and sewage pumps.

1.15 Water supply. It is estimated that about 350 persons would use the comfort station during peak weekends requiring about 10 gallons of water per person. This would amount to 2.4 gallons per minute; however, since this demand would be over an eight-hour period at least 7 gallons per minute should be provided. To meet peak demands, the system would be sized to supply at least 35 gpm for short periods of time. It is proposed to provide water with a 4-inch well located near the comfort station. The water system would consist of a well pump, a high pressure supply main to a 1,000 gallon pressure tank, a pressure switch on the pump and an air compressor and relief valve or other acceptable means for maintaining the correct air-water ratio in the pressure tank.

1.16 Sewage disposal. Domestic sewage would require about 2,400 gallons per day which is two-thirds of the total water requirement. The Department of Parks, Recreation and Tourism would be responsible for the extension the county sewer system to the transport and recreational area. It is proposed to provide a pump station (80 gallon per minute pumps) and a 4-inch diameter PVC force main to connect with the park's sewer system.

1.17 Parking. Parking would be provided for 200 cars. Based on recommended stall and aisle sizes for 90° parking (9' x 18' stalls, 27' center aisle) the lot would be 189' x 350' including the 25' end aisles. This new parking area would be adjacent to the proposed parking area and about 2 miles from the jetty. Access to the walkway would be provided by state operated vehicles or by walking to the jetty along the beach or along the trail through the forest.

1.18 Proposed dredged material quantities and placement plan. The initial amount of material to be dredged from the various reaches is as follows:

Entrance channel	440,000 cubic yards
Inner channel	170,000
Deposition basins	
Upcoast	450,000
Downcoast	230,000
Total	1,290,000

1.19 Entrance channel. Initial dredging quantities for the entrance channel are estimated to be about 440,000 cubic yards. This material is of a sandy nature and would be used for sand dike construction, beach nourishment, or both.

1.20 Inner channel. Dredging required for construction of the inner channel is estimated to be 170,000 cubic yards. This material is also of a sandy nature and would be used for sand dike construction, beach nourishment, or both.

1.21 Deposition basins. Deposition basins would be dredged between the weirs and the navigation channel to intercept and hold

material crossing the weirs. Initial construction would require the removal of 450,000 cubic yards for the upcoast basin and 230,000 cubic yards for the downcoast basin. This material is mostly sand and would be used for sand-like construction and beach nourishment.

#### 1.23 Operation and maintenance.

1.23.1 Channels. The most significant aspect of operation and maintenance of this project is maintenance dredging which would be required about every two to three years. Such dredging would require about 309,000 cubic yards of material annually at a cost of about \$400,000 including the cost for mobilization and demobilization. The annual quantity includes sand bypassing of 200,000 cubic yards from the eastern deposition basin, 100,000 cubic yards from the western deposition basin and inner channel maintenance dredging of 9,000 cubic yards. Because of the flow restriction created by the jetties, the entrance channel would have sufficient tidal currents to be self-maintained and, therefore, no maintenance dredging would be needed for that channel. Material removed from the inner channel and littoral drift that has passed over the jetty-weirs and into the deposition basins could be used to stabilize adjacent shorelines. Dredging would be accomplished by pipeline dredge.

1.24 Jetties. Included under this project feature are the two jetties and sand dikes. No major rehabilitation of these structures would be required since toe protection would be provided for the jetties where scour is most likely to occur. As scour occurs, this armor of toe protection stone would drape the sand slope thereby holding foundation sands in place, preventing settlement of the rubble structure. It is estimated that the average annual cost of jetty maintenance would be \$78,000. Sand dike maintenance costs are included in channel costs discussed above.

1.25 Recreational facilities. Maintenance is expected to be high since the portion of the walkway over the weir section is expected to need replacement every 15 years and the portion of the walkway over the rubble mound section would have to be replaced every 25 years. Large waves breaking on the jetty may cause shifting of the stones under the walkway, causing cracking of the pavement. Large waves can also be expected to damage the wooden deck of the walkway over the weir section. No annual maintenance is expected for the comfort station, access trail or parking lot. The South Carolina Department of Parks, Recreation and Tourism would be responsible for maintaining all recreational facilities including the walkway, comfort station, access trail, and parking lot.

1.26 Special studies. Under the aforementioned authorization, the following studies were conducted:

1.26.1 Environmental studies: Environmental studies were accomplished under a contract with the South Carolina Wildlife and Marine Resources Department. The study was designed to:

a. Provide an estimate of the biological productivity of the area with a view to preventing or minimizing any adverse project effects on biological systems.

b. Provide a basis for an assessment of changes in biological communities during and following construction of this and other similar projects.

1.28 Model study. A fixed bed model of the Little River Inlet system was constructed at the Waterways Experiment Station (WES) in Vicksburg, Mississippi to examine the effects of currents and wave conditions on different arrangements of project appurtenances under simulated prototype conditions. WES presented ten jetty alignments for preliminary testing. A brief description of these plans and the results of this testing is as follows:

a. Plan 1A. Similar to the project plan, but normal to the shoreline. This plan crosses the shallow ocean bar on the downcoast side of the inlet. Flow lines are generally good, however, ebb velocities in the entrance channel and along the upcoast sand dike and basin area are rather high. Peak ebb velocities between the jetties varied from 4.0 to 5.0 feet per second (fps). Flood velocities varied from 3.5 to 4.5 fps.

b. Plan 1B. Same as 1A with weir in the upcoast jetty. Ebb velocities in the area of the upcoast weir are still rather high. Early flood flow is similar to Plan 1A. Once the tide is above the top of the weir, there is flow over the deposition basin. Maximum flood flows are 4.0 to 3.5 fps. Maximum ebb velocities range from 4.2 to 5.3 fps between the jetties.

c. Plan 1C. Same as 1A with weir in the downcoast jetty. Flow is similar to 1A, however, velocities along the upcoast weir are slightly less. During early ebb, flow is over the weir section, but once the water level is below the weir crest, it is confined to the channels.

d. Plan 1D. Same as 1A with weirs in both jetties. Flow is similar to 1A, however, velocities along the upcoast weir are slightly less.

e. Plan 2A. The jetties are moved upcoast with respect to Plan 1A still normal to the shoreline but now follow the existing channel through the ocean bar. Ebb velocities in the channel are slightly slower than Plan 1, but now the downcoast sand dike and jetty is subjected to high velocities.

f. Plan 2B. Same as 2A with a weir in the upcoast jetty. Flow is similar to 2A except that some flood flow is deflected towards the downcoast sand dike.

g. Plan 2C. Same as 2A with a weir in downcoast jetty. Flow is similar to 2A including high velocities along the downcoast sand dike.

h. Plan 2D. Same as 2A with a weir in both jetties. Flow is similar to 1A but during the early ebb, flows attack the bend in the upcoast rubble mound jetty.

i. Plan 2D1. Same as 2D but with shortened jetties and berm on downcoast sand dike. Flow is similar to Plan 2D.

j. Plan 3. This is the same as the project plan presented in the survey report. Flow patterns are fairly good between the jetties.

1.29 A review of the photographs shows that Plans 2D and 2D1 were better than the other plans. The problem of any high velocities along the downcoast sand dike would be alleviated by filling the area adjacent to the downcoast basin to a level above the high water mark with excess excavated material from the basins and channels. Plan 2D and 2D1 are also less costly than Plans 1 or 3. For Plans 1 and 3 ebb and flood velocity direction are reversed bayward of the upcoast sand dike compared to the base plan. For Plan 2, bay circulation remains closer to the natural condition. Wave tests indicate that wave heights are lower in the entrance channel for Plan 2 than for Plans 1 and 3. The wave tests consist of seven second waves with wave heights of 4.8 feet generated from the east and southeast. Shoaling tests also have been performed and indicate that the weir and deposition basins will operate very efficiently. The complete results of the model tests are not available in report form. However, Plan 2D1 is the selected plan based on the detailed model testing.

1.30 Monitoring of project effects. Constructing jetties at Little River Inlet would likely have some effect on adjacent beaches. In order to identify changes which might be attributed to project construction, a monitoring program would be undertaken at an annual cost of \$14,000 as part of the project. This program would cover a minimum 10-year period after project completion and would monitor both existing and future geographical features in addition to project features and structures. A summary of the project monitoring plan follows.



# SUMMARY OF LITTLE RIVER INLET PROJECT MONITORING PLAN

Item	Extent	Frequency
<u>HYDROGRAPHIC SURVEYS:</u>		
Deposition Basin	Whole Basin	Annual
Entrance Channel	Entire channel	Annual
Interior Channel	Entire channel	Biennial
Outer Bar	2000 feet on each side of jetties 1000' seaward	Once during the 1st 5 years
<u>LAND SURVEYS:</u>		
Sand Fillet & Profiles	Parallel & 500' from jetties to MLW line	Semi-annual for 1st 3 years; then annual
Beach Profiles	7 along east beach 7 along west beach	Annual
Jetty, levels	Both jetties	Biennial
<u>PHOTOGRAPHS:</u>		
Aerial	Little River Inlet) Mad Inlet ) Tubbs Inlet ) Hog Inlet ) Shallotte Inlet )	Annual Continuous (include intervening area)
Jetty	Both jetties	Annual
<u>SAND SAMPLING:</u>		
Deposition Basin	10 surface samples	Annual
Entrance Channel	5 surface samples	Annual
Interior Channel	10 surface samples	Annual
Outer Bar	10 surface samples	Annual
Beach Nourishment Areas	10 surface samples for each area	Only when sand is being placed, near end of the nourishment
Sand Fillets at Jetties	6 surface samples	Semi-annual for 1st 3 years; then annual
Beach Profiles	112 surface samples	Annual

## 2.0 Environmental Setting Without the Project

2.01 General. Little River Inlet is a shallow coastal inlet located in Brunswick County, North Carolina and Horry County, South Carolina (see Plate 1). Little River originates in Little River swamp and flows generally eastward, entering the Atlantic Ocean at Little River Inlet between Waties Island and Bird Island. The inlet provides an ocean entrance to the AIWW and to several tidal streams in the Little River, South Carolina - Calabash, North Carolina estuarine area. The Little River Inlet estuarine system is characterized by high energy ocean beaches, sand and mud flats, intertidal shellfish beds, and expanses of salt and brackish water marshes intersected by numerous tidal streams. The inlet is constantly shifting due to ocean currents and wave action resulting in a situation which is hazardous to navigation.

2.02 History of Little River Inlet shoaling problem. Principle difficulties attending navigation result from inadequate depths across the ocean and inner bars and continual shifting of the bar

channel. Channel alignment shifts so rapidly and so often that it is difficult for the Coast Guard to maintain channel markers in proper positions. During periods of low tide or of high seas or swell, the bars are extremely hazardous if not impassable. This condition has created an unstable channel without adequate depths to permit unrestricted navigation through the inlet and offshore bar. To help alleviate this condition, emergency dredging under the River and Harbor Act of 1945 was performed at Little River Inlet in August 1967 when an 8 x 100-foot cut was made through the inner bar for a distance of 1,200 feet. During November of 1968, emergency dredging was performed at the entrance (ocean bar) to provide a channel 10 x 100 feet for a distance of 2,600 feet. These dimensions were not actually achieved and the channel soon deteriorated further.

2.03 In 1974, Congress included in P.L. 93-251 a provision which directed the Corps of Engineers to perform emergency dredging operations needed to maintain channel depths sufficient to permit free and safe movement of vessels as an interim measure until the authorized project is constructed. Emergency dredging under this authority has been accomplished as follows:

a. The inner channel was dredged by pipeline dredge to a bottom depth of 8 feet mlw and a bottom width of 100 feet between 29 May 1974 and 9 June 1974.

b. The outer bar was dredged by the Corps-owned side-caster dredge MERRITT to a depth of 10 feet mlw and a bottom width of 100 feet between 31 March 1974 and 30 April 1974.

c. During the period 28 April 1975 and 15 May 1975 the Corps-owned sidecaster dredge MERRITT attempted to dredge an 8 x 100-foot channel through the outer bar for a distance of 1,500 feet.

d. The most recent dredging occurred in March and April, 1976. During this period the Corps-owned sidecaster dredge FRY attempted to dredge a 3,400 by 8 by 100-foot channel through the outer bar and a contractor owned pipeline dredge removed 107,836 cubic yards of material from a 4,000-foot section of the 6 by 100-foot inner channel.

2.04 Emergency dredging of the outer bar is accomplished by the only practicable equipment capable of working in such shallow inlets without damage to itself - Corps-owned sidecaster dredges. However, this equipment is inefficient in obtaining desirable depths, and complaints of inadequate depth are received within a week or two of its departure. In short, the emergency dredging of the channel is considered to be an inadequate alternative to stabilizing the inlet channel by jetties.

2.05 Other Federal projects. The Cape Fear River, about 32 miles upcoast, is the nearest Federally improved inlet to the north. The nearest Federally improved harbor on the downcoast is Georgetown

Harbor, South Carolina, about 56 miles away. Murrells Inlet, South Carolina is about 35 miles from Little River Inlet. This inlet has a severe shoaling problem with a normal controlling depth of about 3 feet, mean low water. The Murrells Inlet Navigation Project (similar to the Little River Inlet Project) is in the final stages of preconstruction planning. The Federally maintained Atlantic Intracoastal Waterway is located at the upper end of the proposed project.

2.06 Regional physiography and geology. The project lies along the eastern edge of the Atlantic Coastal Plain Physiographic Province. This province is underlain by sediments of Cretaceous to Recent Age which become thicker in a southeastern direction from the Fall Line. Little River Inlet lies along the central axis of a north-west trending structural high known as the Cape Fear Arch (originally known as the Great Carolina Ridge). This arch is thought to have begun flexure in Late Eocene time and to have continued to rise until late Miocene. Sediments younger than Miocene are essentially flat lying whereas older sediments dip slightly away from the axis of the arch. In the central part of the arch, erosion has removed most of the Tertiary sediments exposing Paleocene to Upper Cretaceous formations below a thin cover of late Tertiary to Recent sediments (see Plate 6).

2.07 The barrier islands, such as Bird and Waties Islands, are geologically very young, having been formed during Pleistocene to Recent time. Bird Island, located upcoast of the inlet is somewhat less typical of barrier islands than Waties Island, which is located down-coast of the inlet. Bird Island has an average width of 1,000 feet and is low topographically, with very low, arcuate, northeast trending dune ridges being the dominant feature. Waties Island is larger and wider and has a more well developed typical geomorphic expression, with beach environment, hummocky dune ridges with scrub vegetation, and a backdune flat.

2.08 Shallow borings taken in the inlet all found similar sands down to a depth of 25.5 feet where they were terminated. The sands were generally gray, fine to coarse grained, with varying amounts (up to 30%) of shell fragments, occasional minor clay beds, and areas containing minor (less than 5%) heavy minerals. The sands contained occasional wood fragments, and were generally quite uniform in grain size, color and texture. The sands were dense to very dense with average blow counts (standard penetration test) above 30 and with blows above 50 being common in the lower depths. The blows tended to increase with depth in the shallow borings. Two deeper borings found a lessening of density (decrease in blow count) and an increase in shell content at a depth of about 35 feet. This was about four feet above the contact with the underlying siltstone and shale. The siltstone-shale was found to be relatively soft in the first deep boring (low blows  $N=27$ ) while this same interval in the second had very high core losses. The 39-foot depth appears to be the depth of scour of the present inlet.

The material above this depth is reworked sediments. The limestone and silty sand probably represent the Black Mingo Formation of Paleocene age. The limestones encountered were approximately 1 foot or less in thickness, silty and generally hard. They were generally fine grained and not highly fossiliferous. Thin limestone beds were found at the point of refusal in both deep borings. As noted above, the 39-foot depth appears to be the limit of recent scour; nearly all material above this refusal point consisted of similar gray sands. Shoreline change studies indicate that the inlet has occupied the area in which these borings were taken during shifts in the very recent past. All the sands above the 39-foot depth are of Pleistocene to Recent Age, most of them being of Recent Age.

2.09 Soils. The materials forming the beaches in the project area consist chiefly of silica sand, but locally, shell fragments are abundant. On most beaches a thin bed of peaty clay or sand crops out near mean sea level. This layer is commonly covered except immediately after storms and is more resistant to erosion than the beach sands. Lignina is exposed at several places along the beach. Soils in the Little River Inlet area belong to the Capers and Wando-coastal beach associations (Craddock and Ellerbee).

2.10 Capers association. Capers soils are deep, poorly drained, nearly level soils on tidal flats and are flooded almost daily by salt-water tides. These soils have very dark grayish-brown to dark gray silt loam to clay surface layers and gray to greenish-gray silt clay loam to clay subsoils. Soils in this association contain a high percentage of organic material and are not suitable for dry land agriculture.

2.11 Wando-coastal beach association. This association contains deep, excessively to well-drained, gently sloping to nearly level soils which have developed in thin beds of sands. These soils occur as a broad, nearly level area between the Waccamaw River and the ocean and on sand dunes and beaches bordering the ocean. Wando soils and coastal beach make up 55 and 35 percent of this association, respectively. The remaining 10 percent is made up of Lakeland, Rutledge, and Capers soils.

2.12 Wando soils are excessively drained and occupy a long narrow strip of land paralleling the coast just behind the sand dunes and the beaches. They have dark grayish-brown fine sand surface layers and strong brown fine sand subsoils. Coastal beach consists of sand and sand dunes occupying a narrow strip of land bordering the Atlantic Ocean.

2.13 Little River Inlet sediments. Table I, which is a resume of the soil test results, shows that the greater portion of the subsurface materials encountered at Little River Inlet are poorly graded fine silty sands. With the exception of the more plastic soils found at depths greater than 36 feet in borings No. LR-1 and No. LR-13 (see Plate 1), the grain-size breakdown of all the soils tested is as follows:

Station LRI-1	4.8
Station LRI-2	91.2
Station LRI-3	3.2
Station LRI-4	6.4
Station LRI-5	0.4

These data indicate that, in most cases, a sediment sample was reached within the first foot of water. There is the expected general increase in depth. In a more recent study, sediment was collected with a modified Petersen dredge at the inlet and in Little River (see Plate 7). Sediment samples taken in the entrance channel and stations LRI-1 through LRI-9 were mostly gray or light gray poorly sorted sediment. At stations LRI-5, LRI-7, and LRI-9 further up the river, the sediment is composed of gravel-size shell fragments and sand. Grain size analysis data are presented in Appendix 1. Analyses of these sediment samples did not reveal quantities or amounts that would adversely affect water quality during the disposal operation (see Table 2).

**Littoral drift.** When waves approaching the shoreline at an angle are not completely refracted, the breaking waves create a longshore littoral current. This current is more apparent in the surf zone than farther out. It carries the beach sand, which is moved into suspension by the turbulence of the breaking waves along the shore parallel to the beach. The sand, which is moved both ways, is known as littoral drift. The term "net littoral drift" refers to the difference between the volume of sand moving in one direction along the beach and that moving in the opposite direction. At Little River, the predominant direction of littoral drift is in the down-drift or easterly direction. Based on the latest available data, the annual littoral drift rates for the Little River inlet are as follows:

Net littoral drift	300,000 cubic yards
Coastal and marine material	200,000 cubic yards
Non-coastal and non-marine material	100,000 cubic yards
Net littoral drift	100,000 cubic yards

Groundwater in the vicinity of Little River from 1873 to 1968 are shown in Figure 1.

**Geologic Formations.** There are three geologic formations in the area of concern: ground water aquifers, the Tuscaloosa, Black Creek, and Peedee (see p. 36). Most of the well water along the Grand Strand comes from the Black Creek and Peedee formations. The Black Creek formation is chiefly of dark-gray laminated clay and sand. Water drawn from this formation is soft, highly mineralized, and contains calcium and magnesium bicarbonate. Many flowing wells in Georgetown and Beaufort draw their water from this formation. The Peedee formation is composed of gray sandy earth interbedded with thin ledges of

stone. Waters in this formation are soft and contain considerable bicarbonate. The Tuscaloosa formation contains a great deal of sand through which water can circulate freely and as a result is one of the most productive water bearing formations in the Coastal Plain. Water derived from the Tuscaloosa formation is soft and only moderately mineralized.

2.15 Surface water. The Little River Inlet system conforms with Pritchard's (1955) definition of an estuary as "a semi-enclosed coastal body of water having a free connection with the open sea and within which the seawater is measurably diluted with fresh water runoff." Low salinity water enters the inlet area via AIWW and despite mixing processes, some stratification occurs. As can be seen in Table 2, stratification was observed at station LRI-9 (see Plate 7) during an April 1976 study by the South Carolina Marine Resources Center. It should be noted, however, that this study was conducted during a rather extensive drought and salinities may have been somewhat higher than normal.

2.16 The Marine Resources Center found pronounced oscillations in salinity over a tidal cycle in Little River Inlet and as a result, the estuary is regarded as poikilohaline. During high tide, relatively clear, greenish ocean water is present throughout the lower portion of the inlet. In contrast, the entire estuary is occupied by turbid, brownish-colored water of substantially lower salinity at low tide. The Marine Resources Center found that bottom salinity samples taken hourly from low to high tide at station LRA-3 on 22 April 1976 varied from a minimum of 23.95 parts per thousand (o/oo) to a maximum of 32.97 o/oo. Such highly variable conditions of salinity have a pronounced effect on the species composition of benthic communities in estuaries (Kneib, 1954; Dahl, 1956; Boesch, 1976; Calder, 1976).

2.17 Tides. The AIWW enters Little River about 2.4 miles from the mouth of Little River Inlet. At a point one mile above the mouth, the mean tide range is 4.5 to 4.7 feet and the spring range is 5.2 to 5.4 feet (the spring tide is the tide which rises highest and falls lowest when the earth, sun and moon are aligned). At the mouth of Little River, the mean tide range is 4.4 feet and the spring range is 5.0 feet. Some of the highest observed storm tides in the area were produced by hurricane Hazel on 15 October 1954. At Cherry Beach, roughly on the ocean fronting the town of Little River, a storm highwater mark of nearly 17.0 feet above mean sea level was observed; at the town of Little River a tide level of about 16.5 feet above mean sea level is estimated to have occurred.

2.18 Water quality. Water quality in the study area is considered to be fair to good. Recent water quality data collected and analyzed by the S. C. Marine Resources Center as part of a contract with the U. S. Army Corps of Engineers is presented in Table 3. The lowest oxygen value observed was 6.5 mg/l in a bottom water sample from station

LRI-1. Since there is no industrial pollution in the area, pollution problems are mainly related to bacterial contamination from improperly treated domestic wastes. As a result of this problem most of the area has been closed to shellfishing. In South Carolina, the Department of Health and Environmental Control has closed the area starting at Little River Inlet and including all of Little River as far as shellfish may grow, including the AIWW to the North Carolina State line and including parts of Dunn Sound to a point southwest of the bridge to Waties Island. In North Carolina, the Department of Natural and Economic Resources has closed the Calabash Creek area and the AIWW and contiguous waters upstream to just above the Sunset Beach bridge.

2.20            Climatology. The climate of the area is temperate and is moderated by the nearness of the ocean and the Gulf Stream. Although summers are warm and humid, temperatures of 100°F or higher occur on the average of less than once a year. The mean annual temperature is about 64°F. The frostfree growing season averages about 231 days. The first freeze generally occurs around the first part of November and the last freeze near the end of March. Precipitation is well distributed throughout the year with an average of about 50 inches. Percentage of precipitation by seasons is as follows: 18% winter; 20% spring; 41% summer; and 21% fall. Low pressure areas moving northeast along the coast bring heavy amounts of rain but rarely snow during the winter months. During the late summer or fall months, hurricanes occasionally reach the South Carolina coast. Available records indicate that over 70 storms and/or hurricanes have struck the coast. Heavy precipitation usually occurs with these storms, i.e., more than eight inches of rainfall associated with the hurricanes of September 1924 and October 1964 were recorded at the Georgetown weather station located about 56 miles south of the project.

2.21            Biological resources.

2.22            General. For the purpose of this report, biological resources will be separated into distinct assemblages of plants and animals called biotic communities. In general, biotic communities may be identified on the basis of their dominant vegetation or, in the absence of dominant vegetation, by physiography. Nine major biotic communities have been determined as being present within one or two miles of the project. These are:

- Coastal fringe communities
  - Beach
  - Dune
  - Pine forest
  - Maritime shrub thicket
- Coastal plain communities
  - Oak-pine forest
- Estuarine Communities
  - Open water
  - Tidal marshes
  - Sand and/or mud flats
  - Dredged material islands

Each of the biotic communities described in the following sections contains a description and/or list of characteristic plants and animals. References used to compile these are as follows:

Plants - Radford et al. 1968; S. C. Wildlife and Marine Resources Department 1976; Teal and Teal 1969.

Birds - Robins et al. 1966; Pough 1951.

Mammals - Burt and Grossenheider 1964; Palmer 1954.

Reptiles and Amphibians - Conant 1958; Carr and Goin 1955.

Fish - Breder 1948; Carr and Goin 1955; American Fisheries Society 1970; Cupka, 1972.

Invertebrates - Morris 1951; Gosner 1971; Miner 1950; S. C. Wildlife and Marine Resources Department 1976.

**Beach.** Beach communities in the area are found along Bird Island northeast of the inlet and Waties Island to the southwest. The beach community is comprised of a dry berm zone located beyond the high tide line, an intertidal zone that is alternately covered and uncovered by tidal action, and a subtidal zone that occurs below the low tide line and extends seaward, merging with the ocean surf. Beaches, in general, are gently-sloping communities that serve as transitional areas between open water and upland terrestrial communities.

The beach community is a harsh environment characterized by rapid changes in most of its physical environmental parameters. This is particularly true of the upper surface layers. Vascular plants are virtually absent from these communities primarily because of instability of the substrata, high salinity, and extreme fluctuation of moisture. Shells, and seeds of Caribbean and European plants carried by the Gulf Stream are sometimes tossed up on the beach following the passage of storms. Sediments on the beach are stratified by wind and wave energy and according to particle size and are composed of coarse to fine grained quartz sands and shells and shell fragments.

Marine invertebrates are the predominant faunal organisms inhabiting the beach region and most live beneath the sand surface where moisture and temperature are most constant. Organisms in these areas are continually subjected to strong wave and current action, the rise and fall of tides, shifting sediments, heavy predation, and wide fluctuations in temperature and salinity. Under such rigorous environmental conditions, the fauna is specialized and highly adapted for survival. A small percentage of these organisms are filter or deposit feeders which are concentrated largely in the intertidal zones where there is a constant flow of water and organic matter brought in by the tides or waves. The abundance and condition of animals on the beach



2.27 Relatively few species inhabit sandy beaches, but those present frequently occur in large numbers. Consequently, high energy beaches are far from being biological deserts, and together with the associated fauna they act as extensive food-filtering systems (Riedl and McMahon, 1974). Typical beach inhabitants are beach fleas and ghost crabs in the beach berm; Florida conquinas, mole crabs and various burrowing worms in the beach intertidal zone and blue crabs, horseshoe crab, sand dollars and numerous clams and gastropod mollusks in the beach subtidal areas. In addition, several species of fish are commonly observed in the surf zone along the beach, many of which are of importance to the sport and commercial fisheries of the state. The Atlantic silverside, bay anchovy, Florida pompano, Gulf Kingfish, striped mullet, rough silverside, striped killifish, striped anchovy, permit, bluefish, red drum, and planehead filefish are the most common. These species are also considered to be part of the open water community discussed in Section 2.38.

2.28 The beach zone is also utilized by many species of shorebirds for nesting and feeding. Species commonly observed are the American oystercatcher, plovers, willet, sandpipers, lesser and greater yellowlegs, gulls, and terns. Atlantic loggerhead sea turtles utilize South Carolina beaches for nesting purposes during the summer months.

2.29 In April 1976, the S. C. Wildlife and Marine Resources Department (SCWMRD) under a contract with the U. S. Army, Corps of Engineers, conducted studies of the macroinvertebrate communities in the project vicinity, including those in the intertidal beach zone. Samples of the intertidal macrofauna on Waties Island and Bird Island adjacent to the inlet were collected at stations located at high tide, mid-tide and low tide levels along a transect (Plate 7) on each of the two beaches. Analysis of these samples by SCWMRD showed that the existing communities are typical of those found along high energy beaches. Both species richness and diversity of benthic invertebrates were low. As shown in Table 4, haustoriid amphipods and the coquina clam, Donax variabilis, accounted for 98.4% of the macrofauna observed on Waties Island beach, and 85.8% on Bird Island beach. In each case, substantially fewer individuals and species were found at high tide than at mid or low tide.

2.30 Dune. Dunes are located landward and run parallel to beach communities. They are composed of drifting sand and their height and direction of movement is determined by wind direction and intensity. Few species of plants are capable of tolerating the harsh environment of the dune community. As a result, vegetative cover is usually sparse and consists predominantly of salt-tolerant perennial grasses. Typical species include Russian thistle, seabeach orach, bitter panic grass, salt-marsh cordgrass, sea oats, and broomsedges. All of these plants depend on the constant influx of nutrients because leaching in the dune community is very rapid. Likewise, all of the above species derive nutrients from particulate matter attached to the sands and precipitation. As they accumulate sand at their base, the plants increase the

Black-necked stilts, sandpipers, and an insufficient food supply are the primary limiting factors in this habitat. Ghost crabs, shorebirds, and shorebirds, including sparrows, are the primary predators, while glass lizards and Eastern bluebirds are the primary terrestrial animal inhabitants. Black-necked stilts occasionally utilize the dune communities during the spring and summer.

As the center of the island shifts northward, the maritime shrub thickets are being shifted to the beach zone because erosion is occurring. The maritime shrub thickets are gradually being shifted to the beach zone as the breaking waves continue to shift the center of the island. At the same time, the maritime shrub thickets are being shifted to the beach zone.

Putnam, 1983b; 1. Towhee  
2. Song Sparrow Blackbird  
3. Red-tailed Grackle

Birds (continued)

Brown Thrasher  
Gray Catbird  
Common Yellowthroat  
White-throated Sparrow

Fish Crow  
Indigo Bunting  
Seaside Sparrow

Mammals

Eastern Cottontail  
Raccoon  
Reptiles and Amphibians

Cotton Mouse  
White-tailed deer

Northern Black Racer  
Six-lined Racerunner

South Toad  
Fowler's Toad

2.35 Pine forest. The pine forest community occurs landward of the maritime shrub community on Waties Island. The pine forest differs dramatically from the dunes in both physical conditions and living organisms. The relatively cooler, moist, organic soils support plants which prefer mesic conditions. The dominant species, slash pine, was first introduced to the island in 1950 after hurricane Hazel had destroyed the then dominant loblolly pines. Other trees found in the pine forest are red maple, red cedar, sweet gum, red bay, sugarberry, swamp willow, and black cherry. Common vines include sand bamboo, saw greenbrier, yellow jessamine, dewberry, catbrier and poison ivy. There are also several open areas in the pine forest on the northern portion of the island where sand dunes up to 15 feet in height are found. These dunes support vegetation similar to that found along the beach and were formed when cover vegetation was removed from the island after hurricane Hazel. Before the slash pine became sufficiently established to provide cover, shifting sand from the beach and the open dunes along the oceanfront was swept inland toward the marsh where it accumulated to form the dunes.

2.36 Birds are the most conspicuous faunal inhabitants of the pine forest. This is particularly true during the spring and fall when numerous migratory species are present. Representative vertebrate species found in these communities in the project area are as follows:

Birds

Red-tailed hawk  
Red-shouldered hawk  
Mourning dove  
Yellow-bellied sapsucker  
Red-bellied woodpecker  
Pileated woodpecker  
Blue jay  
Carolina wren  
Mockingbird  
Gray catbird

Flicker  
Yellow-throated vireo  
Red-eyed vireo  
Parula warbler  
Myrtle warbler  
Yellowthroat  
Red-winged blackbird  
Boat-tailed grackle  
Cardinal  
Indigo bunting

Birds (continued)

Brown thrasher  
Robin  
Cedar waxwing

Rufus-sided towhee  
White-throated sparrow

Mammals

Virginia opossum  
Gray fox  
Gray squirrel  
Raccoon

Cotton rat  
White-tailed deer  
Marsh rabbit  
Rice rat

Reptiles and Amphibians

Green anole  
Eastern glass lizard  
Southern five-lined skink  
Eastern coachwhip  
Rough green snake  
Scarlet kingsnake  
Southern copperhead

Scarlet snake  
Yellow rat snake  
Southern toad  
Oak toad  
Green treefrog  
Squirrel treefrog

2.37 Oak-pine forest. The oak-pine forest communities occupy the higher sites and are generally found a short distance inland of the Inlet. Soils in these areas are excessively well drained and are subject to severe leaching. A thin layer of leaves and pine needles and cones is often intermittently present on the ground surface. Live oak, water oak, and loblolly pine are the dominant tree species in these communities. The short tree or shrub region generally is a mixture of turkey oak, overcup oak, scrubby post oak, blackjack oak, and wax myrtle. Other trees present in this association are dogwood, magnolia, black willow, mockernut hickory, yellow poplar, and sweetgum. The understory includes such species as wild black cherry, sassafras, persimmon, various blueberries, laurel cherry, and herbs such as wiregrass, sparrowgrass, goldenrod, aster, partridge berry, Spanish moss, mistletoe, poison ivy, and catbrier. Animal species found in this association include:

Birds

Cooper's hawk  
Red-tailed hawk  
Turkey vulture  
Black vulture  
Bobwhite  
Mourning dove  
Screech owl  
Chuck-will's widow  
Common flicker  
Red-headed woodpecker  
Eastern kingbird  
Eastern phoebe

Blue jay  
Common crow  
Fish crow  
Carolina chickadee  
Brown-headed nuthatch  
Mockingbird  
Eastern bluebird  
Loggerhead shrike  
Pine warbler  
Yellow-throated warbler  
Summer tanager  
Rufus-sided towhee

### Mammals

Virginia opossum	Eastern gray squirrel
Least shrew	Eastern fox squirrel
Eastern mole	Gray fox
Eastern cottontail	Striped skunk
Southern flying squirrel	White-tailed deer
Raccoon	

### Reptiles and Amphibians

Northern fence lizard	Southern crowned snake
Six-lined racerunner	Eastern diamondback rattlesnake
Southeastern five-lined skink	Southern toad
Eastern slender glass lizard	Oak toad
Eastern hognose snake	Pine woods treefrog
Eastern coachwhip	Barking treefrog
	Carolina gopher frog

2.38            Open water. The open water community, as defined here, includes all marine and estuarine waters together with all underlying bottoms below the intertidal zone. The open water biota includes the plankton and nekton inhabiting the water column and the benthos living on or in the substrata.

2.39            The plankton is mainly composed of unicellular algae, larval stages of many fish and invertebrates and the adult stages of several microscopic invertebrates. Adult stages of several macroinvertebrates such as jellyfish (Chrysaora, Cyanea, Stomolophus, Rhopilema,) and comb-jellies (Mnemiopsis) which are carried by current and tides are also an important part of the plankton community.

2.40            Nekton. Fish are the principal nektonic species although some crustaceans such as portunid crabs, penaeid shrimp, and some mollusks, such as the squid spend at least a portion of their life as nekton. A number of the fish species including many of importance to the sport and commercial fishery are considered to be estuarine dependent and utilize the coastal estuaries for at least a portion of their life cycle.

2.41            Benthos. The benthic environment includes a number of communities correlated largely with substratum type. Multicellular green, red, and brown algae, and unicellular algae (especially diatoms), are the primary producers within the photic zone of the benthic environment.

2.42            The benthic fauna is divided into two groups: epifauna, living on the substratum; and infauna, living within the substratum. Infaunal communities are dominated by a great diversity of burrowing and tube dwelling crustaceans (e.g. amphipods), polychaete worms, and by

burrowing bivalve mollusks. Some infaunal invertebrates, especially among the crustaceans, are capable of a high degree of lateral mobility, but the majority are essentially sedentary. The infauna is, with rare exception, comprised of filter and detritus feeding invertebrates.

2.43 The epifauna contains a diversity of animal groups associated with a diverse flora. Hard substrata, such as rocks, shell and gravel surfaces, and artificial surfaces, such as pilings, wrecks, and weirs support a rich assortment of attached plants and invertebrates. Typically, these communities contain red, green, and brown algae, barnacles, attached bivalves, anemones, corals, sea fans, bryozoans, tunicates, sponges, and foraminiferans. The communities formed by these attached organisms host a number of both transient and permanent fish species, and motile invertebrates, including gastropod mollusks, starfish, sea urchins, crabs, and shrimp. Attached epifaunal invertebrates are principally filter and detritus feeders, but some of the more motile organisms are carnivores.

2.44 The epifauna and flora of muddy and sandy bottoms tend to be much lower in diversity, and most inhabitants are microscopic. These surfaces are unsuitable for attachment by sessile invertebrates. In addition, sand bottoms such as those found in the inlet are depositional and the continual rain of sediment quickly buries attached animals. Thus, these substrata support diatoms, other unicellular algae, protists, and attached multicellular algae. Invertebrates primarily include motile deposit feeders, such as polychaete worms, sea cucumbers, and sand dollars. Some fish and crabs also graze on the bottom. Attached organisms are restricted largely to the occasional bit of shell or small rock lying on the surface. The development of oyster reefs on muddy intertidal bottoms, for example, is dependent on the presence of bits of shell or rock for initial larval attachment.

2.45 Benthic macroinvertebrate studies. The most extensive study of the benthic macroinvertebrate communities in the project area was recently completed by the South Carolina Wildlife and Marine Resources Department under the previously discussed contract with the Corps of Engineers. Field samples for this study were collected at 20 stations within the Little River system (Plate 2) during the period 19-22 April 1976. Sampling equipment utilized included a modified Petersen grab sampler and a modified oyster dredge. Station depths are shown in the following text table. A discussion of the findings of this study is presented in the following paragraphs.

<u>Station</u>	<u>Depth (Feet)</u>	<u>Station</u>	<u>Depth (Feet)</u>
LRI-1	14.8	LRE-2	11.5
LRI-2	9.8	LRE-3	9.8
LRI-3	14.8	LRA-1	16.4
LRI-4	13.1	LRA-2	8.2
LRI-5	16.4	LRA-3	4.9
LRI-6	21.3	LRA-4	4.9
LRI-7	18.1	LRA-5	13.1
LRI-8	11.5	LRA-6	14.8
LRI-9	13.1	LRA-7	11.5
LRE-1	19.7	LRA-8	6.6

inner channel. The bottom at inner channel stations 1-4 was mostly fine sand, with relatively little shell. The bottom at the channel end at station LRE-3, with large numbers of small, unidentified amphipods. Neohaustorius schnitzii, Parahaustorius sp. and Lepidactylus dytiscus accounted for 93.5% of the fauna collected at all four stations. Ephemeroptera was sparse at all four stations. Crustaceans and insect larvae were collected at all in two three minute samples.

100

and Eudendrium carneum and Sertularia stookeyi (hydroids). Short-term variations in salinity are known to have a greater impact on the epifauna than on the infauna (Sanders, Mangelsdorf, and Hampson, 1965). They demonstrated that salinity in a poikilohaline estuary is much more stable in the sediments than in the overlying water column, and that the epifauna is therefore subjected to greater physiological stress than the infauna.

2.49            Adjacent waterways. In addition to the nine stations in the inner channel, eight others were occupied in adjacent waterways of Little River Inlet. Polychaetes were the dominant infaunal animals at all of these stations (Table 9). A large number of live oysters, along with typical brackish water oyster associates, were collected at station LRA-1 in the intracoastal waterway. The epifauna was substantially better represented at stations LRA-7 and LRA-8 in Bonaparte Creek than anywhere else in the inlet (Table 10). A number of Euryhaline Marine I species (those tolerating salinities from above 30 o/oo to a minimum of 10 o/oo) were present, suggesting that this creek has polyhaline salinities and probably less-pronounced oscillations in salinity compared with other areas studied in the inlet. Live oysters were common at these two stations, but shells in the creek were heavily infested with boring sponges, and several predatory gastropods were collected. The fewest species in samples from stations in adjacent waterways were obtained at stations LRA-3, LRA-5, and LRA-6; bottom type at each of these stations was predominantly sandy with little shell or other firm substrate.

2.50            Oyster reefs. Intertidal oyster reefs within 0.5 miles of the centerline of the proposed channel were surveyed and charted during the S. C. Wildlife and Marine Resources Department study (see Plate 9). This included shoreline reefs along tidal creeks and isolated reefs located in shoal and flat areas. The total acreage of intertidal reefs within the area surveyed was limited, amounting to about 2.48 acres. Approximately 1.84 acres of the total were shoreline reefs, including 0.904 acres having heavy coverage, 0.742 acres of medium coverage, and 0.193 acres of light coverage by living oysters. Individual reefs (beds) totaled only 0.638 acres, including 0.586 acres of heavy coverage, 0.025 acres of medium coverage, and 0.267 acres of light coverage. No significant reefs of subtidal oysters were found in the Little River Inlet study area.

2.51            Clam resources. Approximately 37 acres of bottoms containing hard clams were located during the Marine Resources study (see Plate 10). These were found in both intertidal and subtidal areas within Little River and its tributary creeks. Bottoms containing hard clams totaled 12 acres in Dunn Sound Creek, 7.4 acres in Horse Ford Creek, 9 acres in Sheephead Creek, and 8.21 acres in Little River.

2.52            Other animals in the open water community. The open water community is also utilized by waterfowl and shorebirds, particularly during the winter months. Many waterfowl are surface feeders and



dabblers, and are commonly found along the shallow water zones where they feed on submerged or emergent vegetation. Other vertebrates (i.e. mammals, reptiles, and amphibians) are poorly represented in the open water community. Many of these are semi-aquatic and, thus, are temporary residents of the community. The following is a list of typical floral and faunal inhabitants, with the exception of benthic macroinvertebrates which are listed in Tables 5 through 10, of communities associated with open water habitats:

#### Plankton

Diatoms	Comb-jellies
Dinoflagellates	Cryptophytes
Chlorophytes	Xanthophytes
Jelly fish	Copepods
Arrow worms	

#### Animals with Planktonic Larval Stages

Fish	Echinoderms
Crabs	Jelly fish
Barnacles	Comb jellies
Mollusks	Copepods
Polychaete worms	

#### Nekton

Amphipods	Silver perch
Isopods	Star drum
Portunid crabs	Spot
Squid	Atlantic croaker
Alewife	Bluefish
Atlantic menhaden	Spotted seatrout
Gizzard shad	Weakfish
Bay anchovy	Red drum
Mummichog	Striped mullet
Striped killifish	Summer flounder
Rainwater killifish	Tidewater silverside
Sheepshead	Atlantic silverside
Little tunny	Pinfish
Spadefish	Atlantic needlefish
Toadfish	Naked goby
Whiffs	Crevalle jack
Pigfish	Spanish mackerel
Tonguefish	Black drum
Shrimps	Striped bass

#### Birds

Common loon	Ring-billed gull
Brown pelican	Herring gull
Double-crested cormorant	Black skimmer

Birds (continued)

Osprey	Royal tern
Merganser	Least tern
Laughing gull	Belted kingfisher
Mallard	Ruddy duck

Mammals

Bottle-nosed dolphin

Reptiles and Amphibians

Atlantic loggerhead turtle  
Diamondback terrapin

153. Tidal marsh. The tidal marshes of the Little River Inlet marine system are classified as salt marshes since their plant composition generally reflects the strong marine influence on this region. In a 1970 study, the S. C. Wildlife and Marine Resources Department under contract to the U. S. Army, Corps of Engineers inventoried the upland vegetation of the Little River Inlet area (see Plate 11). A discussion of the pertinent aspects of this study is presented in the following paragraphs.

154. For the purposes of this study, the salt marshes of Little River Inlet were separated into two major zones based on tidal elevation and vegetative composition: (1) low marsh and (2) high marsh. The regularly flooded low marsh extends from a point slightly above the mean low water mark to the approximate mean high water level, while the high marsh occurs above this zone in an area which is flooded only at irregular intervals by higher than average tides, i.e., spring and storm tides. This difference in tidal elevation and related physical conditions (i.e., submergence and exposure, soil salinity, etc.) is evidenced by an obvious change in plant community composition between these two marsh zones. A list of plant species observed during the Marine Resources Division's study is presented in Table 11. Table 12 outlines the plant composition, dominant vegetation, and approximate elevation at the tidal marsh stations surveyed during the study. Station locations are shown on Plate 11.

The Little River Inlet system contains about 1,050 acres of tidal marshland. Of this amount, about 900 acres or 85 percent of the total is low marsh acreage dominated by a single plant species, *Spartina cordgrass*. Lacking formidable competitors, this plant dominates the low tidal marsh where it attains heights of six feet or more along the margins.

155. High marsh covers about 150 acres or 15 percent of the tidal marshland acreage. In contrast to the monotypic low marsh, plant life of the high marsh is more varied, with several halophytes

plants are found in abundance: glasswort, sea lavender, salt marsh aster, salt grass, and salt marsh bulrush, as well as a large amount of smooth cordgrass. As the high marsh approaches the water, several other marsh plants enter the community: salt marsh cordgrass, seaside goldenrod, black needlerush, high tide bush, sea purslane, salt grape, wax myrtle, and broomsedge. This upper high marsh community is dominated by marsh-hay cordgrass and saltgrass, while sea purslane, high tide bush and salt marsh bulrush are also quite abundant. Cordgrass and threesquare are locally abundant in the marshes near the lake, especially associated with freshwater inflow of Little River.

Marsh communities have been well documented in terms of productivity, animal diversity, and importance to the marine system (and to man). The basis of the importance of these marsh communities includes the high productivity of the marsh itself and its function as a sink for nutrients. The detritus deposited each year when the marsh plants die and decomposes provides a food base upon which the estuarine animals thrive. The dense plant growth in the marsh provides a refuge for many species of birds, aquatic and semi-aquatic mammals, reptiles, and amphibians. Substrates in these communities are composed of a variety of foraminiferans, nematodes, annelids, arthropods, mollusks, such as the salt marsh snail, marsh periwinkle, ribbed muscle, and eastern oyster, and crustaceans such as the penaeid shrimps, sand fiddler, and white and blue crabs. The marsh community provides a nursery ground for the principal commercial marine organisms of the state; white and brown shrimp and blue crabs. Marsh creeks also serve as spawning and nursery grounds for many commercial and sport fishes and shellfishes, in addition to being prime shellfish growing areas.

Throughout these marsh communities numerous shorebirds, waterfowl, gulls, herons, and egrets will be found. Birds such as cormorants, stilts, and sandpipers thrive on the benthic invertebrate population around the shoreline and on open flats. In the open water areas of these communities, waterfowl will be found feeding on vegetation and small marine fishes and free swimming invertebrates. Another bird commonly found is the clapper rail, a permanent resident of these marshes. The herons and egrets feed on fish, invertebrates, reptiles, amphibians, and small mammals in the marsh. They also are found nesting in the marsh during the summer months. Many gulls will be found the marshes, utilizing these communities for resting and scavenging. Other birds such as the red-winged blackbird, common and boat-tailed grackles, sparrows, and warblers will be found nesting and feeding on marsh plants and grains. Birds of prey such as the osprey and marsh hawk also will be found utilizing these communities to some degree.

Mammals of the marshes typically include the raccoon, muskrat, coon, otter, opossum and marsh rabbit. The raccoon and opossum are opportunistic animals and opportunistic feeders. The otter thrives on aquatic plants and fish while the rice rat and marsh rabbit are herbivores. Other mammals such as the bobcat and fox will visit these marshes.

the Little River. The tidal flats occupy a large area of the delta by the Little River Inlet and extend inland. They lie below the mean high water mark and are exposed by wind-driven or wave-driven currents. They are free of vascular plants but are free of algae, diatoms, bacteria, oysters, and other organisms. They are usually fringed with stands of cordgrass, smooth cordgrass and open water. In the delta of the inlet, the flats are usually above the mean high water mark and are exposed only in these instances, the flats are fringed with cordgrass, smooth cordgrass,

and other organisms. A constant influx of particulate material from the river provides a rich nutrient supply for the organisms. When the tidal flats are covered by water, the nutrients constitute an important food source for many species. When the flats are exposed, the organisms are consumed by birds and shorebirds. A list of the birds follows:

Long-billed dowitcher	Long-billed dowitcher
Dunlin	Dunlin
Semipalmated sandpiper	Semipalmated sandpiper
Herring gull	Herring gull
Ring-billed gull	Ring-billed gull
Laughing gull	Laughing gull
Least tern	Least tern
Royal tern	Royal tern
Gull-billed tern	Gull-billed tern
Short-billed dowitcher	Short-billed dowitcher
Caspian tern	Caspian tern
Black skimmer	Black skimmer
Lesser yellowlegs	Lesser yellowlegs

#### Wading birds

Black tern

Sunray venus	Sunray venus
Crisp-barred venus	Crisp-barred venus
Goldeneye	Goldeneye
Red-tailed olive	Red-tailed olive

2.62 Disposal areas. Disposal areas used for deposition of material removed during maintenance of the AIWW and emergency dredging in the Little River Inlet channel comprise about 57 acres. The original plant communities that were present on these sites prior to disposal have been obliterated. Upon revegetation, these areas usually contain natural biotic communities that are similar in appearance and composition to those which naturally occur in the surrounding environment. Other potential disposal areas in the Little River Inlet system are currently vegetated with smooth cordgrass, glasswort, sea lavender, sea purslane, sea ox-eye, marsh elder, wax myrtle, coastal cedar, and sea myrtle. Wildlife species commonly observed in these areas include black skimmers, American oystercatchers, terns, gulls, herons, egrets, several species of ducks, raccoon, and rodents.

2.63 Sport and commercial fisheries. The Little River Inlet system is a significant contributor to the economy of the adjacent counties in North and South Carolina in terms of recreational and commercial fisheries. There are eight marinas and numerous private docks located in the vicinity of Little River Inlet. Personal pleasure craft harbored at the inlet include about 310 outboards, 230 inboards, 100 cruisers, and 30 sailboats. In addition, there are many transient boats hauled into the area for day use. These boats are used for fishing, crabbing, shrimping, oystering, water skiing, and pleasure riding. There were 16 party and charter fishing boats utilizing the inlet in March 1976. Fourteen of these boats work out of the village of Little River and two work out of Calabash, North Carolina. Common salt water game fish caught in inshore waters by the small boat and surf fishermen include such species as spot, seatrout, black and red drum, flounder, kingfish, pompano, black sea bass, croaker and Spanish mackerel.

2.64 Commercial fishing vessels operating out of Little River Inlet as of March 1976 include three boats based at Seaside Landing, four at Bonaparte Landing, thirteen at Calabash, North Carolina, and five at the Hurricane Marina in Little River, South Carolina. Available data on annual commercial fishery landings are presented in Table 13. Data presented in this table were compiled from the records of licensed fish dealers by the Department of Commerce in cooperation with the S. C. Wildlife and Marine Resources Department and N. C. Department of Natural and Economic Resources. As shown in Table 13, the major commercial species landed in the area are mullet, spot, sea bass, thread herring, whiting, shrimp, and oysters.

2.65 Recreation. Little River Inlet is located on the northern end of what is known as the Grand Strand, South Carolina's most popular vacation area. The "Strand", famous for its gently sloping-fine white sand beaches, is a 50-mile seashore vacation land and recreational area. In addition to its famous beaches, the Strand offers abundant hotel, motel, and camping areas, 13 ocean fishing piers, numerous championship golf courses, miniature golf courses, amusement parks, and two state parks, Huntington Beach State Park and Myrtle Beach State Park.

As a result, the lake is bordered by private lands on both sides. The hunting and trapping hunters enjoy a number of advantages, such as the ability to buy and sell, and a skill in hunting and trapping. The hunting and trapping hunters are also able to hunt and trap in the lake area.

the United States, the National Health and Medical Research Council (NH&MRC) has been instrumental in the development of a national research agenda for the prevention of violence. Since 1990, NH&MRC has funded a number of research projects in the area of violence prevention, including the following:

There is a small creek, called the Inlet, which flows into the Calabash River in the area. The river is characterized by many small encampments. The mouth of the Inlet, at the Calabash River, was the birthplace of John Martin, older brother of the famous John Martin, who died in the 1770's. The Inlet was explored by General Francis Nash and his troops during the March from Wilmington, North Carolina. The Inlet River disappeared prior to the 1900's. There is a marker on the right bank of the Inlet, at the mouth of the Calabash River.

at the site of the earthwork, was located at the site of the earthwork. The earthwork is the

of the Little River Inlet. The transitional nature of the inlet channel precludes permanent human habitation, and no physical remains exist in any form of construction. It also appears likely that a village had existed in the inlet channel at the time of the emergency flooding. The site of the village lay between 1.04 through 2.04, however, all of the evidence of construction and which have not been excavated. The evidence of construction so that the site of the village can be located. The most likely site of the habitation can be located by the use of the evidence of the University of the Pacific, 1964, p. 121-124.

the 1990s, the Willamette and Bull Run properties were sold to a private owner. The sale of the land to a private owner represents a threat to the Willamette and Bull Run properties, threatening the Willamette and Bull Run properties with a loss of the historic and scenic resources.

2.72 Several mounds were also found on the island with one site being selected for excavation by Dr. Engelmayr. The site appeared to be a large shell midden about 46 meters long, 15 meters wide, and 3 meters high. The mound was covered with a layer of shell up to 40 centimeters in depth. Small fireplaces consisting of fine ashes and charcoal were found in a portion of the mound. A few long bones and jaws of white-tail deer, raccoon, turtle, and alligator were found around the edges of the fireplaces. Artifacts consisting of potsherds, lithic material, bone tools, and worked shells were concentrated in the lower five centimeters of the shell layer. The archeological material excavated at the site places it in the cultural period of late Wilmington complex and Savannah I phase and an approximate date of 500-1000 A.D.

2.73 Economic indicators. The standard indicators and others found to be related to the Little River Inlet area are keyed to the State of North Carolina, State of South Carolina, and U. S. Department of Commerce, Bureau of Economic Analysis (BEA) Economic Area Numbers 24 and 30. These economic areas have been delineated by the BEA and the Economic Research Service (ERS), Department of Agriculture, who have made national and area economic projections to 2020 for the Water Resources Council. The Series E projections dated April, 1974 have been adopted as the current appraisal of the long-range national trends for planning purposes. These projections are designated as "OBERS Projections." BEA Area 024 consists of eleven North Carolina counties: Brunswick, Columbus, New Hanover, Pender, Duplin, Onslow, Jones, Lenoir, Craven, Carteret, and Pamlico. BEA Area 030 consists of nine South Carolina counties: Georgetown, Horry, Marion, Williamsburg, Dillon, Florence, Darlington, Chesterfield, and Marlboro. Projections for progressively smaller areas were made with regard to their expected performance relative to the larger areas of which they are a part. Projections have been made to the year 2020.

2.74 Population. According to the 1970 U. S. Census of Population, the 1970 population of the State of South Carolina was 2,590,516, an increase of 8.7 percent over its 1960 population and a decrease from the 12.5 percent increase registered during the 1950-1960 decade. The 1970 population of North Carolina was 5,082,059, an increase of 11.5 percent over its 1960 population and a decrease from the 12.2 percent increase registered during the period 1950-1960. Horry County had a 1970 population of 69,992, an increase of 2.6 percent over a 1960 population of 68,247. Brunswick County had a 1970 population of 24,223, an increase of 19.5 percent over the 1960 population of 20,278.

2.75 Employment. The average annual employment in South Carolina totaled 1,053,000 in 1973 with about 4.1 percent of the labor force unemployed. (S. C. Employment Security Commission, 1975). About 375,200 persons or 36 percent were employed in manufacturing; 171,700 or 16 in Government; 171,500 or 16 in wholesale and retail trade; 110,200 or 11 in services; and 7 in contract construction. The remainder were either self-employed or in agriculture, forestry, and fisheries; mining; transportation, communication, and public utilities; and finance, insurance, and real estate. Average annual employment in Horry County in

10/1/51

10/1/51

10/1/51

10/1/51

10/1/51

10/1/51



amusement and recreation services is found throughout the smaller economic areas. After 1980 annual growth rates are expected to decline with all economic areas showing less than one percent growth for each 10-year period.

2.81 While employment growth in amusement and recreation services is expected to be minor in the years to come, the growth of earnings from these services is expected to have a brighter future. These earnings in the United States are projected at an annual growth rate of about three percent while employment for the same area was projected at less than one percent. The difference in the rates in BEA Areas 024 and 030 is three percent for earnings and 0.2 percent for employment.

2.82 Transportation. The area has a fair transportation system. Good highways make it accessible from all directions. U. S. Highway 17, which parallels the ocean front along the entire area, connects all northern and southern points. U. S. Highways 378, 501 and 521 and S. C. Highway 9 provide connections to west, mid-west, southwest and northern localities. A multi-lane expressway from Florence to Myrtle Beach was recently opened. It is served, for freight service only, by the Seaboard Coast Line Railroad. The AIWW, with a 12-foot depth, traverses the Atlantic coast and is traveled by many pleasure boats as well as by freight barges. The AIWW and Little River provide the only public access to the inlet. There is a Myrtle Beach - North Myrtle Beach municipal airport, with a 6,000-foot runway but no tower facilities, served by Piedmont Airlines. Smaller fields are those serving Loris and Tabor City (jointly), and the Horry County airport at Conway. Bus service is provided by Trailways and Greyhound.

2.83 Future environmental setting without the project. Population centers are expected to expand to accommodate a growing population and new industries. This expansion will be achieved at the expense of undeveloped lands. Acreage currently devoted to cropland and forestry will continue to decrease as lands of this type yield to the pressures of urban development. The population in BEA Economic Areas 024 and 030 in 1970 was 884,488 or about 11% of the total population of the States of North and South Carolina. This represents a 4% increase in population over 1960 for the two BEA Economic Areas and a 13% increase for the two states as compared to a 13% increase for the United States as a whole. Projections indicate that state populations will increase at an average annual rate of about 1% as compared to about 0.5% for the two BEA Economic Areas through the year 2020. The labor force for BEA Areas 024 and 030 was about 38% of its population in 1970, compared to 40% for the two states. These ratios are expected to continue through 2020. The annual growth rate for personal per capita income from BEA

and 25 percent of the population is under 18 and will increase from 21 percent in 1980 to 25 percent of the total population. Average per capita income in 2020. Development in the area is expected to continue to concentrate and intensify along the Atlantic coastline in Barry and Brunswick Counties with or without the proposed project.

#### 4. Relationship of the Proposed Action to Land Use Plans

The proposed project is not anticipated to conflict with existing or proposed land use plans in the Little River Inlet area. The proposed jetties and possible future fishing walkway would be compatible with the state park proposed for development on Watie's Island. The project has been and will continue to be coordinated with state and local planning agencies.

#### 4.1 The Probable Impact of the Proposed Action on the Environment

The proposed plan of improvement includes the construction of jetties and sand dikes and the dredging of entrance and inner channels and two reposition basins. The project will require the removal of about 1,400,000 cubic yards of material by hydraulic pipeline dredge. This material is mostly sand and will be used for construction of sand dikes and beach nourishment. The major adverse effects of this project relate to effects on water quality and on the ecosystems in the disposal areas, channel areas, and other areas within the inlet which will be disturbed by construction activities. Beneficial effects relate to the provision of a navigation channel for the safe operation of charter, recreational, and commercial fishing boats.

4.1.1 Water quality. The proposed project is not expected to create any long-term or large scale adverse impacts or detrimental effects on the water quality of the Little River Inlet system. As is characteristic of any hydraulic dredging operation, water turbidity in the vicinity of the dredge will increase as a result of the mechanical action of the dredge cutterhead. Turbidities will also increase adjacent to beach disposal areas. However, since all materials to be dredged during project construction are of a sandy nature with a rapid settling rate, any increases in turbidity are expected to be insignificant and of short-term duration and will not affect the long-term productivity of the Little River Inlet estuarine system. As discussed in Section 4.1.2, the sediment analysis of Little River Inlet sediments did not reveal the presence of any substances in amounts that would adversely affect water quality during the dredging and disposal operation (see Table 4.1). Water quality impacts resulting from periodic maintenance dredging of the Little River Inlet and the inner channel will be similar to that resulting from construction. If the fishing walkway is constructed, sanitary water from the bottom of the walkway could be pumped inland to the existing sewerage treatment facility.

...the results of the  
...indicate that  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...

...the ...  
...the ...  
...the ...  
...the ...  
...the ...

...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...

...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...  
...the ...

...the ...

...the ...

...the ...

the jetties would provide substrate for epifaunal assemblages and benthic algae, both of which are very limited in the entrance channel area at the present time.

4.08 The lower half of the inner channel is currently dominated by sand-dwelling haustoriid amphipods. If the area remains sandy after completion of the navigation project, these animals should rapidly recolonize the area and community structure should remain essentially the same. If conditions are altered so that the substrate becomes shelly or muddy, it is likely that benthic assemblages would become dominated by polychaetes. The upper half of the inner channel and all of the stations sampled in adjacent waterways were dominated by polychaetes. With the exception of LRA-3, LRA-5, and LRA-7 (see Plate 7), the bottom at these stations was shelly. No dredging appears necessary at any of these locations and little if any impact on the benthos is anticipated.

4.09 As a result of the findings of the above study, it is expected that the disruption or destruction of benthic invertebrates would be a short-term impact as recolonization by organisms disturbed by the cutterhead and recruitment from adjacent areas would begin almost immediately after dredging is completed. The suitability of newly dredged areas for recolonization would of course, be dependent on the interaction of factors such as bottom topography, bottom substrates and habitats, water velocity and current patterns, and future sediment distribution patterns. However, since the composition of bottom sediments is not expected to change appreciably as a result of the proposed dredging it is expected that the populations which eventually become established would be similar to those presently found in deeper channel areas. Due to the continual movement of sand into the deposition basins, numbers and species of benthic organisms inhabiting these areas after construction is completed would probably be low.

4.10 Fish. Available data indicate that fish populations, unlike benthic invertebrates which are relatively immobile and may undergo population reductions that may be locally severe, are less likely to be adversely affected by dredging operations. For example, Stickney (1973) in his study of the Atlantic Intracoastal Waterway in Georgia found no indication of fishes being killed during dredging operations. In some areas, dredging could be considered to be beneficial to certain species of fish, especially those which prey on the larger benthic organisms. As a dredge works its way along a channel, benthic animals which would normally be buried in the sediments are dislodged and become susceptible to predation. This sudden availability of food quite often results in higher than normal concentrations of fishes near the dredge. A similar situation would occur in beach disposal areas. As organisms are dislodged from sandy sediments being deposited on the beach, they become subject to predation by fishes inhabiting the surf zone.

4.11 Although it would appear that fish are relatively unaffected by dredging, there has been some concern recently over the possible effects of increased turbidities and siltation generally associated with dredging. As a dredge moves along the channel, it invariably creates some type of turbidity plume, the size of which will vary considerably depending on the type of sediment being dredged, strength of currents and other factors. The magnitude of the impact of these suspended particles on fishes will, in most cases, be dependent on the concentration, composition, absorbed minerals or toxins and the tolerance of particular species. In general, bottom-dwelling species are the most tolerant of suspended solids, filter feeders are most sensitive and juvenile forms are more sensitive than adults. Under normal circumstances, fish can generally avoid turbid waters and have the ability to clear gill membranes of accumulated silt upon entering undisturbed water (Sherk and Cronin, 1970). However, not all species are equally susceptible to suspended solids and different suspended solids vary in their effect. As a general rule, it has been found that fish can tolerate high turbidities except when they are accompanied by low levels of dissolved oxygen, acids, alkalies, or other substances which interfere with respiration, injure gills or prevent their normal function, and they are quite capable of leaving the immediate dredging area.

4.12 Due to the sandy nature of the substrate in areas to be dredged, turbidity plumes created by the dredge cutterhead would primarily be restricted to the immediate dredging area. Fish species which would have the highest probability of being affected are the filter feeders (primarily menhaden, herring, and shad) and juvenile forms. Estimates of the relative abundance of these species in the area at any given time varies so that it is not practical to attempt a quantitative determination of the impact on these species. In addition, some larval fishes may be destroyed as a result of the mechanical action of the dredge cutterhead. However, based on research which has been accomplished in other areas and available information on the effects of current dredging practices in the area, it is felt that any impact resulting from the proposed dredging would be of a short-term, localized nature and would not significantly affect the fish stocks in the Little River Inlet system. Similar temporary adverse and beneficial impacts would occur during periodic maintenance dredging but would be of a lessened nature due to the lesser amounts of material involved.

4.13 The construction of the jetties would provide substrate for new epifaunal communities of invertebrates and provide habitat for numerous fish species. The combination of a deepened channel flanked by two jetties will concentrate fish food organisms and thereby attract large numbers of marine sport fishes. A jetty related sport fishery would develop shortly after the project is completed and the fishing walkway on the south jetty, if constructed, would provide access to this newly developed fishery by land-based fishermen. Fish species which would be available to anglers on the jetty during various times of the year are sheepshead, black drum, red drum, flounder, bluefish, seatrout, croaker, spot, and whiting.

4.14 Commercial fisheries. The project offers little potential for adversely affecting the areas valuable commercial fisheries industry. As is discussed in Section 4.26 and shown in Appendix A, the commercial fishing industry would benefit from the project.

4.15 Beach community. As discussed in Section 1.0, all material removed during initial dredging operations would be used for beach nourishment and construction of sand dikes. Organisms inhabiting this beach fill zone would be covered as material is pumped onto the beach. When considered in terms of numbers of organisms which may be potentially destroyed, the short-term adverse impact would be significant. However, because animals from high energy beaches are motile and adapted to shifting sediments, rapid recovery of the fauna on these beach areas following the deposition of dredged materials is likely. This is particularly true if the dredged material is similar to that of the original beach in grain size and other characteristics (Thompson, 1973). The intertidal areas of Waties Island and Bird Island were populated by only a few species, all of which are typical of sandy beaches. Haustoriid amphipods and the bivalve Donax variabilis were abundant at both locations. These organisms continually undergo rapid population turnovers and have high resiliency following disturbance.

4.16 Oysters. Intertidal oyster reefs in the study area were small and widely scattered, totaling about 2.5 acres. No dredging or disposal operations are planned within the immediate vicinity of these reefs. Therefore, no extensive sand transport from the inlet channel dredging is expected and no physical damage to intertidal oyster communities is foreseen.

4.17 Clams. An estimated 37 acres of intertidal and subtidal bottoms containing hard clams were located during the State study. According to the Marine Resources Department, hard clams represent the most potentially valuable molluscan resource in the Little River estuary. In spite of the present closure of the area to shellfishing, hard clams could be removed by commercial operators and replanted in clean waters elsewhere for depuration prior to marketing. Hard clam bottoms were primarily located near the inner shorelines of Little River and in tributary creeks, and none were found within the proposed Inlet channel area. Immediate physical effects of the proposed dredging on these resources should be minimal.

4.18 Marsh. Construction of the south sand dike may require the filling of approximately three acres of upper high marsh and less than one acre of high marsh at the north end of Waties Island. The proposed project would not affect any of the area's valuable low marsh acreage. Loss of the high marsh acreage would slightly reduce the areas productivity. Vertebrate animals displaced or disturbed by construction could move into adjacent areas which have similar habitat and could temporarily stress resident populations in those areas as they compete for available food and cover. Macroinvertebrates would be buried during sand-like construction. Native plant species would be planted on the spoil piles after construction is completed. As these plants become established, the sand dikes would be utilized by species generally associated with a dune type habitat.

food and cover. Native plant species would be planted on the sand dikes after construction is completed. As these plants become established, the sand dikes would be utilized by species generally associated with a dune type habitat.

4.19 Pine forest. A small amount of pine forest (approximately four acres) would be cleared during construction of the sand dike at the north end of Waties Island. Impacts associated with this clearing include a slight reduction in primary productivity and displacement of existing animal species. Some animal species would likely move into adjacent areas while others may continue to forage in the area during the construction process. As stated previously, sand dikes would be planted with appropriate native vegetation which would provide some habitat for animal species.

4.20 Endangered species. The only endangered species frequently observed in the area, the brown pelican, would not be adversely affected by the proposed project.

4.21 Mosquitoes. Since this project does not require the use of diked areas for disposal of dredged materials and all materials to be removed are of a sandy nature, the project would not cause any increase in mosquito breeding.

4.22 Archeological and historical sites. The National Register of Historic Places has been consulted and there are no existing or potential register properties which would be affected by the construction of the proposed project. As indicated in Section 2.70, it appears unlikely that significant archeological resources exist in any area which would be affected by construction. However, all areas to be affected by construction which have not been disturbed by previous dredging will be surveyed for archeological content. If the survey reveals no significant archeological resources, then it is considered that the project would not have a significant impact on this resource. If any significant archeological resources are found, a plan of salvage will be prepared and coordinated with the National Park Service and the Advisory Council on Historic Preservation. The actual salvage operation would be conducted in accordance with the coordinated plan of salvage before project construction. The only areas in which archeological resources could exist and be affected by project construction include the exposed ocean beaches bounding the inlet, any as yet undredged portions of the inner channel, and the surf zone where dredging of the entrance channel and jetty construction would occur. In view of the physical characteristics of these areas, it would appear that the real value of any archeological resources therein would not be realized until such resources were salvaged. Accordingly, if significant archeological resources are discovered during the survey, it is considered that the project impact on these resources would be favorable.

4.23 Recreation. The effects of the proposed action on the areas recreational resources would vary from temporary minor inconveniences to boaters in the area to enhancement of the areas boating and fishing opportunities. The jetties would provide a protected entrance to Little River Inlet which would benefit all boaters using the inlet for passage to and from the ocean. In addition, the jetties would provide

habitat for the development of a new jetty-related fishery which is currently not available in the Little River Inlet area. If a fishing walkway is provided on the south jetty it would assure that this fishery would be available to non-boaters as well as boaters. It is estimated that about 40,000 fishermen and 45,000 sightseers would use such a walkway annually by 1980, 50,000 fishermen and 60,000 sightseers by 2000, and 60,000 fishermen and 80,000 sightseers by 2030.

4.24           Aesthetics. The presence of the dredge, pipelines, and other assorted construction equipment will represent a temporary intrusion upon the view of boaters in the area. The physical presence of the sand dikes and jetties may be aesthetically displeasing to some individuals since they will be located in areas which are currently undeveloped.

4.25           Noise and air quality. Operating dredges are generally quiet and contribute less to ambient noise levels than normal motor and speedboat traffic. Air pollution derived from the dredge and other construction equipment should be negligible during both construction and maintenance of the project.

4.26           Economic impacts. The proposed project will have a favorable economic impact on the study area since it will provide direct and indirect benefits to the commercial charter boat industry, commercial fishermen, sport fishermen, recreational boaters, and marinas serving the area. Little River Inlet, because of the shifting sands at the entrance to the inlet, is unstable. Present controlling depth of the waterway is about two to three feet above mean low water. This depth is inadequate for operation of the existing and projected fleet of commercial and recreational boats which require about 12 feet in the ocean and 10 feet in the inner channels for safe navigation. Construction of the proposed project will result in tangible navigation benefits of \$1,636,800 per year derived from enhanced recreational boating and commercial charter boat operations, increased commercial seafood landings, reductions in vessel damage, and provision of an all-tide harbor of refuge during storms. In addition, the fishing walkway, if constructed, would provide an estimated annual benefit of \$112,000 based on an annual visitation of 40,000 fishermen and 45,000 sightseers. Re-development benefits would amount to \$70,000 and consist of labor income accruing to those who would be unemployed in such areas, except for the construction of the project.

4.27           The proposed project, by offering better access and safer conditions to all vessels, would result in some increase in business for marinas and other satellite services and businesses located in the Murrells Inlet area. The project might also stimulate the establishment of new businesses and satellite services in the area, especially in areas related to commercial charter and seafood industries.

4.28           Maintenance dredging. Maintenance dredging would be accomplished about every two to three years and would be required in the inner channel and deposition basin. Inner channel dredging would amount to about 9,000 cubic yards annually. All of this would will be used for beach nourishment. Approximately 300,000 cubic yards of material would be removed from the deposition basins annually and placed on adjacent beaches. The impacts of maintenance dredging would be similar to those of initial construction but would be of different order of magnitude.



4.29 Sand bypassing. The proposed jetties would extend out into the ocean well beyond the surf zone. Since the ocean surf is responsible for the movement of sand in the littoral zone along the ocean beaches, the jetties would constitute a barrier to both the up-coast and downcoast movement of sand. This movement of sand or littoral drift process affects the rate at which beaches accrete and erode. The proposed project, therefore, provides for the construction of features designed to maintain the present littoral drift regimen along the shores adjacent to Little River Inlet. Low weir sections would be constructed in each jetty to permit the normal movement of sand across the jetty. Deposition basins would be constructed inside each jetty to provide for the accumulation of all sand moving over the low weir sections. The sand that accumulates within each deposition basin would be periodically pumped out by a hydraulic dredge and deposited outside the jetties on either the upcoast or downcoast beaches as needed. These features are intended to insure that the project would have no effect on the rate at which beaches in the vicinity of Little River Inlet erode or accrete.

#### 5.0 Any Probable Adverse Effects Which Cannot Be Avoided

5.01 The principal adverse effects of constructing the proposed project are related to the dredging of channels and disposal of dredged materials. The dredging would temporarily increase turbidities in the immediate vicinity of the dredge and beach disposal areas during initial construction and periodic maintenance. This increase in turbidity could cause a decrease in primary productivity due to turbid waters reducing the euphotic zone. In addition, some benthic organisms may be destroyed by the dredge cutterhead. Disposal of all suitable material on adjacent beaches during initial and maintenance dredging operations would smother some beach inhabitants. Some macroinvertebrates would also be covered by placement of stone during jetty construction. Species inhabiting the high marsh and pine forest in areas which would be cleared for sand dike construction would be displaced by construction activities. The presence of the dredge, pipeline, and other construction equipment and the jetties and sand dikes may be aesthetically displeasing to some individuals.

#### 6.0 Alternatives to the Proposed Action

6.01 General. Several possible solutions to the problem of providing a stabilized channel of sufficient depth and width for regular use by commercial and recreational fishing vessels were considered. Experience has shown that it is not economically or physically feasible to maintain the channel by dredging alone. Therefore, it was decided that a proper solution must also include structural controls with provisions for sand bypassing. Structural controls considered included jetties, offshore breakwaters, and conventional and special facilities for sand bypassing. An optimum project was selected by maximizing benefits through comparison of cost and benefits for incremental project requirements related to variations in project depths. Five different plans were tested with physical models to determine the best location and arrangement of structural control appurtenances.

6.02 Non-structural alternatives. Construction and maintenance of the required channels were considered using a program of dredging in lieu of structural controls. In February 1975, private

dredging contractors were contacted by Charleston District and asked if they would consider dredging in Little River Inlet and Murrells Inlet with a pipeline dredge. All contractors responded that dredging in these inlets was too hazardous and not feasible for a pipeline dredge. The following reasons were submitted in support of their objections: (1) insurance is void once they go in open ocean waters; (2) a large dredge would require from 6 to 8 feet of water in which to work; (3) a small dredge would not require the water depths that a large dredge would but a small dredge's low pumping capacity would render its operation useless due to rapid shifting of sand in the inlet; and (4) the design of pipeline dredges renders them useless in areas of strong wave action.

6.03 In September 1975, a private consulting engineering firm was employed by Georgetown County to prepare plans and specifications to perform pipeline dredging at Murrells Inlet which is similar to Little River Inlet. A large number of private dredging firms were contacted by the private engineering firm. These dredging companies were requested to signify their interest in undertaking a dredging operation in Murrells Inlet. The responses to this inquiry were also all negative. Two out-of-state dredging firms sent representatives to look at the area before deciding that the work could not be done with their equipment.

6.04 Emergency dredging of the ocean bar was performed in March and April 1976 using the Corps of Engineers' sidecasting dredge, FRY. The channel dredged in May has already begun to shoal.

6.05 The technology does not presently exist in the private or government dredging fleets to adequately maintain Little River Inlet. The Corps of Engineers is not authorized to construct new dredges that would have capability of dredging the inlet, and the private sector appears not to be interested in undertaking the design of a prototype dredge capable of this operation without Federal funds. For the reasons stated in this and preceding paragraphs, dredging without structural controls is considered to be uneconomical and physically impractical.

6.06 The non-structural alternative was also considered more undesirable to the environmental quality of the inlet than plans with structural controls since the more frequent dredging required would be more disruptive to benthic populations. In addition, the non-structural alternative would not provide any sheltered water for small boats navigating the entrance channel because of the absence of a jetty system. Since it is not practical or economically feasible to maintain a dependable channel by any non-structural alternative, further growth in the commercial fishing and charter-boat operations and related businesses would be discouraged. It was therefore concluded that some type of structural control would be required.

6.07 Structural alternatives. Structural alternatives considered included provisions for interruption, trapping and bypassing sands moving along shore; sheltering fishing vessels from wave action; and

maintaining stable channel dimensions and alignments. Schemes considered include:

- (1) Two impermeable jetties;
- (2) Upcoast jetty with weir and impermeable downcoast jetty; and
- (3) Two jetties with weirs in each.

6.08 In the first plan, sands forming the fillet against the impermeable jetty would be exposed to ocean forces and would have to be bypassed using a permanently installed hydraulic plant, a conventional hydraulic dredge requiring offshore breakwater protection, or a submarine-type jet eductor system (not yet perfected). Schemes for trapping littoral drift by the use of weirs would have the advantage of providing wave protection to the conventional pipeline dredge. Littoral drift moving along shore would pass over a low weir section in the jetty and settle into a deposition basin located within the jetty confinement. Sand would be periodically bypassed to adjacent beaches by a conventional hydraulic dredge operating within the protected jetty system to remove entrapped sands from the deposition basin and transport these sands to downdrift or updrift beaches. Considering the previously described actions, the best project arrangement was found to be the construction of jetties extending from the barrier beaches on each side of a dredged inlet channel and the sand-bypassing scheme employing overflow weirs and deposition basins for each jetty.

6.09 Alternative depths. Various depths for the entrance and inner channel were considered during project formulation. Entrance channel depths that were considered ranged from eight feet to 14 feet mlw with inner channel depths being two feet less for each level of improvement. The additional two feet in the entrance channel is necessary to allow for the effects of pitch and roll in the ocean. The selection of inner channel depths was based on the loaded draft of the vessel plus an allowance of one-half foot for drag (the designed difference between the draft forward and aft when a vessel is down by the stern), one-half foot for squat (depression of water surface about the hull resulting from the bow and stern wave systems) and two-foot minimum bottom clearance. Using these criteria, boats with drafts up to 3.0 feet could safely negotiate a six-foot inner channel during all tidal stages and boats with up to 7.0 feet of draft could safely use the 10-foot channel which would be provided under the recommended plan of improvement.

6.10 The optimum navigation project was determined through maximization of benefits. Maximum benefits are achieved by incrementally adding higher levels of improvement until the incremental cost of the addition equals the incremental benefits received. Recreational boating and commercial fishing operations, which are now regulated by the tidal cycles, would realize increasing benefits due to greater channel depths until these depths reach a level that would be adequate at all tide stages for the deepest draft vessels expected to use the inlet. Annual benefits from reduction of vessel maintenance would also vary with channel project depth as do the jetty lengths which are based upon entrance channel length which is a function of depth. Cost and benefit analysis data for the various alternatives are presented in Table 14. As shown in this table, Plan C offers the optimum navigation facilities and therefore is the selected plan of improvement.

the proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

#### 10. Relatively Unconstrained Alternative Uses of Man's Environment, Proper Management and Enhancement of Natural Resources

The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long. The proposed alternative would require the construction of a new 100-foot wide channel, 1/2 mile long, and a 50-foot wide channel, 1/4 mile long, and a 25-foot wide channel, 1/4 mile long.

[illegible]

Environmental Protection Agency

In response to comment:

1. 36 Department of the Interior

1. Additional comments on addressing archeological resources and project impacts that have been inserted in Sections 2.70 and 4.22.

2. The suggested revisions have been incorporated in this EIS. See also Section 2.63.

3. See response to comment 1. Legislated responsibility for initiating surveys rests with the U. S. Department of the Interior. Prior to 1974, several laws, regulations, and presidential orders stated broad and general goals for protecting cultural resources, but did not provide specific steps for accomplishing all of these goals.

The Advisory Council on Historic Preservation outlined steps by which a Federal agency might comply with the few specific requirements of these laws and regulations, and also accomplish the vaguer, broader goals. Many of these steps were not required by law, but were suggested by the Advisory Council to encourage Federal agencies to adopt uniform procedures for protecting cultural resources.

On 24 May 1974, four months after the 36 CFR 800 regulations were published, Congress passed Public Law 93-291. This law outlined in unusually clear and specific terms the steps to be followed to protect cultural resources. In agreement with earlier public laws and executive orders, but in contrast to the suggestions by the Advisory Council in 36 CFR 800, Public Law 93-291 clearly assigns the responsibilities to the Secretary of the Interior for initiating surveys (Section 4c) and coordinating actions among cognizant agencies and individuals (Section 5). In Sections 4 and 5, the law states the responsibilities which "shall" be performed by the Secretary of the Interior. These include initiation of survey work and coordination efforts. The law does provide in Section 3a and 7a that Federal agencies constructing or financing a project "may" assist the Secretary by assuming certain tasks related to cultural resources.

In response to the permissive provisions of Sections 3a and 7a, the Corps of Engineers has agreed to assume most of the responsibilities for cultural resources on civil works projects and general investigation studies which were delegated to the USDI by Public Law 93-291 and earlier legislation. This voluntary assumption of responsibilities delegated to the USDI is in agreement with the broad sentiments expressed in the National Environmental Policy Act, Executive Order 11593, and the Historic Preservation Act of 1966, and is also responsive to suggestions of the Advisory Council pertaining to the adoption of uniform procedures as outlined in 36 CFR 305. The USDI's reliance on recommended procedure by the Advisory Council and declaration to acknowledge Public Law 93-291 is not a tenable position, especially when the latter is more specific and more authoritative.

Figure 1 shows the distribution of the 1976 estimates of the "percentage of the total north American population that is employed in the agricultural elevations" (hereafter referred to as  $Y_{it}$ ).

the elevation of the water in tidal elevations was determined by the tide gauge. It was considered the tide gauge to be reliable and that it was not likely that when and if some sear should occur and the water level be raised to a lesser degree the tidal changes would be about the same as the 2.1 feet.

It was also considered that a sear which would occur would make the design of the project more than the average 0.1-foot we have observed.

It was also noted that inlet projects similar to the Little River Inlet project have been documented data on before and after construction and that it should be used to predict accurately the effects of the project on the inlet. However, it has been proven that tidal heights and water levels have been accurate in the past and that a physical model of the inlet is a source of this information now available.

It was also noted that

It was also noted that

It was also noted that USDA, Columbia, South Carolina

It was also noted that in 1966 of the EIS, the sand dikes will be planted with vegetation and other salt tolerant plant species. A vegetative plan will be developed during the latter stages of project design, prior to the initiation of construction.

It was also noted that USDA, Raleigh, North Carolina

It was also noted that

It was also noted that Department of Health, Education, and Welfare

It was also noted that

It was also noted that Department of Housing and Urban Development

It was also noted that

It was also noted that Department of Defense, USDT

It was also noted that

It was also noted that Department of State Affairs

It was also noted that in the dictionary it littoral drift (lapping on each side of the beach) is approximately equal. If littoral drift is predominantly on one side of the beach, the littoral drift will migrate.



Historically, Little River Inlet has been rather stable in location, with the state line offering a rather definite reference point. Its locational stability together with its rather isolated lens of hinterland most suggests a closely balanced volume of littoral drift material coming from both directions. Analysis of available records for about the last five years suggests, during that period, a predominance of about 100,000 cubic yards a year moving westward. The geological evidence, however, suggests that at some point very near Little River Inlet, with slight secular shifts, the littoral drift from the two directions has been balanced over a long period of time. The persistence of the inlet indicates that it is effectively bypassing the gross littoral drift volume; that is, the sand impinging from both sides. Installation of a jetty would fix the location of the inlet thus preventing minor migrations of the inlet that are a part of the natural bypassing system, as by the gain and loss of material from a nearland shoal, or by the movement of sand across an offshore bar by means of channels traversing the bar and switching directions through the bar. The effects of this natural bypassing should be prevented by artificial bypassing means, as are contemplated in the improvement, in order to forestall erosion of the adjacent beach areas.

2. The Corps does not initiate Federal water resource projects. These projects originate with a request for assistance from local interests to a United States Senator or Representative, who submits the request to either the House or Senate Public Works Committee. If the Committee is convinced of the need for assistance, an authorization for an investigation will be included in an authorization bill for consideration by the Congress. When passed, the bill becomes a directive to the Corps for a study. If Congress also appropriates funds for the study, the Corps then conducts the study and submits a report to the Congress. If the report recommends action by the Federal government and if Congress approves the report, it will authorize the construction of a Federal project. Construction will be only if and when Congress appropriates funds for that particular project.

3. A study of the project's effects on the areas biological resources will be included in the monitoring program. A summary of the monitoring program presented in the GDM has been included in Table III.

4. Additional information has been included in Section 1.24 and 1.25 of the Final EIS.

#### National Indian Department of Human Resources

1. No response is required.

2. All riparian areas will not be required for project construction or maintenance; therefore, the project has no potential for contributing to the local mosquito population.

North Carolina Department of Natural and Economic Resources

No response is required.

South Carolina Wildlife and Marine Resources Department

1. Additional plant species have been included in the subject paragraph.
2. These species have been included in this final EIS.
3. The subject section has been revised as suggested.
4. The number of tidal marsh stations has been corrected.
5. The EIS has been revised as suggested.
6. Additional species have been included in the subject paragraph in the final EIS. Since no low marsh communities will be adversely affected by the proposed project it is not considered necessary to include a comprehensive listing of animal species utilizing this marsh.
7. Additional species have been included in this final EIS.
8. The subject paragraph has been revised as suggested.
9. The possibility of relocating the south sand dike so as to avoid potential disturbance of any high marsh acreage will be studied during preconstruction planning.

S. C. Department of Health and Environmental Control

No response is required.

S. C. Department of Archives and Administration

No response is required.

South Carolina Water Resources Commission

1. The EIS covers the impact of all construction associated with the sanitation project which does not include the park which may or may not be developed by the S. C. Department of Parks, Recreation, and Tourism. The benefits for the fishing walkway are shown as separate items in Appendix A. The B/C ratio shown in this Appendix is, as stated, for sanitation facilities only. The B/C ratio for recreation facilities has been included in Appendix A of this EIS.
2. The recreational development described in Section 1.11 is an integral part of the Little River Inlet project and is appropriately included in this EIS.
3. All facilities will comply with all federal laws and regulations.

4. Access to the proposed walkway would be provided by State operated electric powered vehicles as is noted in Section 1.17 of this EIS. The 90° pattern for parking stalls was adopted because it is more efficient in terms of overall capacity.
5. No response is required.
6. The data utilized in this paragraph is the most recent published data.
7. The suggested revisions have been incorporated in this EIS.
8. Since no specific reason is given for the conclusion that the project is undesirable from an environmental viewpoint, additional information and/or response cannot be included in this EIS. However, with reference to the statement that only limited secondary benefits would accrue to the general public, it should be noted that all boat owners and other recreationists that utilize any part of the project belong to the general public.

Cape Fear Council of Governments

No response is required.

Waccamaw Regional Planning and Development Council

1. In cases such as the Little River Inlet EIS, where a large number of plates are utilized, plates are placed at the end of the EIS to facilitate review of material in the text.
2. A legend has been included in Plate 5 in this final EIS.
3. Model studies being conducted by the U. S. Army Corps of Engineers, Waterways Experiment Station indicate that the project would have little if any effect on areawide hydrology and therefore should not affect the distribution of future waste loads.
4. The S. C. Department of Parks, Recreation, and Tourism has been negotiating with the owners of Waties Island in an effort to either purchase or lease the island for the purposes of developing a state park. If such plans should materialize, the Department has indicated that they would be willing to participate in the construction and operation of a fishing walkway on the south jetty.
5. The subject sentence has been clarified in this final EIS.
6. We are cognizant of the current status of the loggerhead sea turtle. Although construction schedules have not been finalized as yet, effort will be made to schedule construction during periods of lowest biological activity.

### List of References

1. American Fisheries Society. 1970. A list of common and scientific names of fishes from the United States and Canada, third edition. Spec. Pub. No. 6. Washington, D. C. 150 pp.
2. Bacci, G. 1954. Gradienti di salinità e distribuzione di molluschi nel lago di Patria. Boll. Zool. 21.
3. Boesch, D. F. 1976. A new look at the zonation of benthos along the estuarine gradient. In press in B. C. Coull (ed.), Ecology of marine benthos. Univ. South Carolina Press, Columbia.
4. Breder, Charles M., Jr. 1948. Field book of marine fishes of the Atlantic coast. G. P. Putnam's Sons, New York. 332 pp.
5. Burt, W. H., and R. P. Grossenheider. 1964. A field guide to the mammals. Houghton-Mifflin Co., Boston, Mass. 284 pp.
6. Calder, D. R. 1976. The zonation of hydroids along salinity gradients in South Carolina estuaries. In press in G. O. Mackie (ed.), Colelenterate ecology and behavior. Plenum Press, New York.
7. Calder, D. R., C. M. Bearden, and B. B. Boothe, Jr. 1976. Environmental inventory of a small neutral embayment: Murrells Inlet, South Carolina. South Carolina Mar. Res. Center Tech. Rep. No. 10. (in press).
8. Carr, A., and C. J. Goin. 1955. Guide to the reptiles, amphibians, and freshwater fishes of Florida. Univ. of Florida Press, Gainesville. 341 pp.
9. Chesapeake Biological Laboratory. 1970. Gross physical and biological effects of overboard spoil disposal in upper Chesapeake Bay. Final Report to the U. S. Bureau of Sport Fisheries and Wildlife (Contract 14-16-005-2096). Reference No. 70-3. Subsections included in this comprehensive report in order of presentation were as follows:  
Cronin L. E. Summary, conclusions, and recommendations. 15 pp.  
Biggs, R. B. Geology and Hydrology. Project A. Reference No. 69-23. 36 pp.  
Fiemer, D. A. Phytoplankton. Project B. Ref. No. 69-15. 15 pp.  
Pfitzenmeyer, H. T. Benthos. Project C. Ref. No. 69-130. 30 pp.  
Goodwyn, F., Jr. Zooplankton. Project D. Ref. No. 69-128. 9 pp.
10. Cooke, C. Wythe. 1936. Geology of the coastal plain of South Carolina. U. S. Geological Survey, Bulletin Number 867.
11. Conant, R. 1958. A field guide to reptiles and amphibians. Houghton Mifflin Co., Boston, Mass. 366 pp.

12. Craddock, G. R. and Ellerbo, C. M. General soil maps of South Carolina Counties. Soil association descriptions.
13. Coker, David M. 1972. A survey of the ichthyofauna of the surf zone in South Carolina. S. C. Wildlife and Marine Resources Department. Technical Report No. 4.
14. Cronin, J. 1966. Ecological salinity boundaries in poikilohaline waters. *Oikos* 7: 1-21.
15. Engineer Agency for Resources Inventories. 1973. U. S. Army Corps of Engineers environmental reconnaissance of the state of South Carolina. Washington, D. C. 51 pp.
16. Engelsoy, Reinhold J. 1976. Archaeological research and excavation on Watie's Island and Little River Neck, Horry County, South Carolina. Report prepared for S. C. Department of Parks, Recreation and Tourism.
17. Gosner, Kenneth L. 1971. Guide to identification of marine and estuarine invertebrates. Wiley-Interscience, a division of John Wiley and Sons, Inc., New York. 693 pp.
18. Hay, Edwin B. 1973. Environmental effects of hydraulic dredging in estuaries. Alabama Marine Resources Bulletin No. 9. 85 pp.
19. Miner, R. W. 1950. Field book of seashore life. G. P. Putnam's Sons, New York. 888 pp.
20. Morris, Percy M. 1951. A field guide to the shells of the Atlantic and Gulf coasts. Houghton Mifflin Co., Boston, Mass. 236 pp.
21. Palocz, Ralph S. 1954. The mammal guide. Doubleday and Company, Inc., Garden City, New York. 384 pp.
22. Pough, Richard H. 1951. Audubon water bird guide. Doubleday and Company, Inc., Garden City, New York. 352 pp.
23. North Carolina Department of Administration. 1975. Profile, North Carolina Counties.
24. North Carolina Bureau of Employment Security Research. 1973. North Carolina Labor Force Estimates 1973.
25. Rabinovich, R. W. 1955. Estuarine circulation patterns. *Proc. American Society of Civil Engineers* 81 (717): 1-11.
26. Silliman, A. E., B. E. Ables, and C. R. Bell. 1968. Manual of the vascular plants of the Carolinas. University of North Carolina Press, Chapel Hill. 1163 pp.

27. Riedl, R., and E. A. McMahan, 1974. High energy beaches. Pages 180-251 in H. T. Odum, B. J. Copeland and E. A. McMahan (eds.), Coastal ecological systems of the United States. The Conservation Foundation. Washington, D. C.
28. Robbins, C. S., B. Bruun, and H. S. Zinn. 1966. Birds of North America. Golden Press, New York. 340 pp.
29. Sanders, H. L., P. C. Mangelsdorf, Jr., and G. R. Hampson. 1965. Salinity and faunal distribution in the Pocasset River, Massachusetts. Limnol. Oceanogr. 10 (suppl.): R216-R229.
30. Sherk, J. A., Jr., and L. E. Cronin. 1970. The effects of suspended and deposited sediments on estuarine organisms. An annotated bibliography of selected references. Chesapeake Biological Laboratory, Reference No. 70-19. vi +73 pp.
31. South Carolina Department of Health and Environmental Control. 1974. Water Classification Standards System for the State of South Carolina. 11 pp.
32. South Carolina Employment Security Commission. 1975. South Carolina's manpower in industry, Research and Statistics Section, Columbia.
33. South Carolina Water Resources Commission. 1970. South Carolina tidelands report. 178 pp.
34. S. C. Wildlife and Marine Resources Department. 1976. Little River Inlet environmental studies report. Final report to the U. S. Army, Corps of Engineers (Contract DACW60-76-C-0017).
35. Stickney, Robert. 1973. Effect of hydraulic dredging on estuarine animals studied. World Dredging and Marine Construction. P. 34-37.
36. Thompson, J. P. 1973. Ecological effects of offshore dredging and beach nourishment: a review. U. S. Army Corps of Engineers, Coastal Engineering Research Center Misc. Paper 1-73, Washington, D. C.
37. U. S. Department of Commerce, Bureau of Census. 1971. 1970 Census of population. U. S. Govt. Printing Office, Washington, D. C.
38. U. S. Department of Commerce, National Oceanic and Atmospheric Administration. 1974. Tide tables, high and low water predictions, 1975: east coast of North and South America. U. S. Govt. Printing Office, Washington, D. C. 288 pp.

39. U. S. Department of the Interior. 1975. Endangered and threatened wildlife and plants. Federal Register, Vol. 40, No. 188.
40. U. S. Department of the Interior. 1976. National Register of Historic Places. Federal Register, Vol. 41, No. 28.
41. U. S. Water Resources Council. 1974. 1972 OBERS projections-economic activity in the U. S. Volumes 1-7.

## GLOSSARY

- algae - any of a group of chiefly marine or freshwater aquatic plants with no true leaves, stems, or roots ranging in size from microscopic single-cell organisms or colonies to large macroscopic seaweeds.
- Amphipoda - large order of malacostracan Crustacea; includes the sideswimmers, sand hoppers, etc.; body compressed; first thoracic segment fused with head; no true carapace; mostly scavengers; most spp. marine, burrowing or moving about on the bottom and debris.
- anaerobic - refers to life or processes that occur in the absence of oxygen.
- Annelida - phylum consisting of elongated, segmented worms; includes earthworms, leeches, and many kinds of marine forms.
- aquifer - an underground bed or stratum of earth, gravel or porous stone that contains water.
- Arthropoda - largest phylum; characterized by a segmented body, segmented appendages, chitinous exoskeleton, and an extensive hemocoel; includes crustaceans, insects, spiders and their relatives, centipedes, millipedes, etc.; in all types of habitats.
- association - in an ecological sense, a subunit of community organization identified by its major organisms.
- benthic region - the bottom of a body of water. This region supports the benthos, a type of life that not only lives upon, but contributes to the character of the bottom.
- benthos - the plant and animal life whose habitat is the bottom of a sea, lake or river.
- biota - all the species of plants and animals occurring within a certain area.
- biotic - of/life.
- bivalve - any member of the molluscan Class Pelecypoda. Having a shell of two parts which are joined by hinge, as in pelecypods.
- bloom - to flower; of algae, to appear or occur suddenly or in large quantity or degree.
- Bryozoa - ectoprocta; phylum which includes the "moss animalcules"; small tufted or branched marine and freshwater organisms a few mm. high; attached to substrates.



GLOSSARY  
(Cont'd)

canopy - the upper layer of leaves, twigs, and branches of forest trees, or of other woody plants.

carnivore - a flesh eater. The highest trophic level(s) at the top of most food chains.

coliform - any one of a number of organisms common to the intestinal tract of man and animals whose presence in waste water is an indicator of pollution and of potentially dangerous bacterial contamination.

colonize - to establish a colony in or on.

community - collectively, all of the organisms inhabiting a common environment and interacting with each other.

detritus - in the ecological sense, any fine particulate debris of organic or inorganic origin.

diatom - a uni-cellular form of algae with walls impregnated with silica.

dissolved oxygen - the oxygen dissolved in water or sewage. Adequately dissolved oxygen is necessary for the life of fish and other aquatic organisms and for the prevention of offensive odors. Low dissolved oxygen concentrations generally are due to discharge of excessive organic solids having high BOD, the result of inadequate waste treatment.

diurnal - activity by daylight; opposite of nocturnal. Occuring every day.

diversity - refers to the number of different kinds of species in an area.

dominant - a species or group of species which largely control the energy flow and strongly affect the environment within a community or association.

ecotone - transition or interdigitated area between two adjacent communities in the merging zone or adjacent forest and grassland.

environment - sum of all physical, chemical, and biological factors to which an organism is subjected. One of the major habitat types, such as desert, terrestrial, rain forest, desert, lake, etc.

epifauna - that fauna living on the surface of the bottom deposits in the water.

erosion - the process of wearing away by the action of water, wind, or other natural forces.

estuary - where the fresh water meets salt water. For example, bays, mouths of rivers, salt marshes and lagoons. Estuaries are delicate ecosystems that serve as nurseries, spawning and feeding grounds for many marine life and provide shelter and food for birds and wildlife.

GLOSSARY  
(Cont'd)

fauna - the animals, the animal life of any particular area or of a particular period of time. A list of animal species and descriptions of a particular area or time.

filter feeder - an animal that obtains its food (usually small particles) by filtering it from water; e.g. Daphnia, clams, mollusks.

flora - the plants peculiar to a country, area, specified environment, or period.

Fora infera - one of the orders of the Class Sarcodina; main bulk of the cell is enclosed within a simple or chambered and/or coiled shell or test composed of secreted calcium carbonate (usually), silicon dioxide, or bits of foreign material cemented together with an organic secretion.

formation - one sedimentary bed or consecutive series of beds sufficiently homogeneous or distinctive to be a unit.

fossiliferous - containing fossils.

habitat - the place where a particular plant or animal lives usually used in a much more restricted sense than ecology. It refers to a smaller area; e.g. spring brook, trout pool, weedy pond, and sandy beach.

halocline - boundary between water layers of differing salinities.

hydroperiod - rainy season.

in situ - in place.

infauna - fauna consisting of burrowers in the bottom deposits

intertidal zone - that portion of the sea bottom between high and low tide lines; depending on tidal amplitude and slope of the bottom, the intertidal zone may be narrow or very wide.

invertebrate - collectively, all animals without a vertebral column.

Isopoda - order of malacostracan Crustacea; includes pill bugs, sow bugs, and scud bugs; body unsegmented; first thoracic segment fused with head; antennae short, some or all segments two-jointed; found in both fresh and salt water.

larva - period term for any independent, active, immature stage of an animal which is morphologically quite unlike the adult; includes prolonged metamorphosis in most cases.

GLOSSARY  
(Cont'd)

**littoral** - that shallow portion of the bottom extending from the shoreline to a depth of 200 m.; the term is also used to include both the bottom and the water above the bottom at the depths indicated.

**microscopic** - Indistinguishable without the use of a microscope.

**Mollusca** - Mollusk; any member of the Phylum Mollusca; Phylum including soft-bodied animals usually partly or wholly enclosed within a calcium carbonate shell and having a muscular "foot" for locomotion.

**nekton** - collectively, the macroscopic animals suspended in the water of ponds, lakes, rivers, and seas; they move about independently of currents and include such forms as fishes and whales.

**Nematoda** - Phylum which includes all the true roundworms; body slender, cylindrical, often tapered near ends, and covered with a cuticle; 100 microns to 1 m. long; marine, freshwater, terrestrial, and parasites of plants and animals.

**nursery area** - an area where animals congregate for giving birth or where the early life history stages develop. e.g. estuaries for shrimp

**pelagic** - of or pertaining to the open waters of the sea and lakes, especially where the water is more than 20 m. deep.

**photic zone** - the region of aquatic environments in which the intensity of light is sufficient for photosynthesis.

**photosynthesis** - synthesis of carbohydrates from carbon dioxide and water with chlorophyll as a mediator using light as energy with oxygen as a by-product.

**physiography** - a description of nature or natural phenomena in general.

**phytoplankton** - small, mostly microscopic, plants floating in the water column.

**pioneer** - any early occupant of an open or disturbed area of ground.

**plankton** - collectively, all those organisms suspended in the water of an aquatic habitat which are not independent of currents and other water movements; most such organisms are microscopic and commonly include bacteria, algae, protozoans, rotifers, larvae, and small crustaceans.

**population** - a group of organisms of the same species.

**producer** - any organisms able to synthesize organic compounds from simple inorganic substances, e.g. green plants.

cellulose - a complex carbohydrate, as stored by animals and plants, and in some fungi.

chromatids - the molecules having a nucleus, chromosomes, and other structures in certain protozoans, and algae, and some fungi.

climatic - pertaining to climate, partly along and partly under the surface, extending out, shoots above and roots below.

clinging - growing permanently attached to a substrate, such as a barnacle or sponge.

community - series of communities which follow one another in slow but definite sequence, ending in a climax typical of a particular climate and geographic area; such series may be completed in a hundred years or up to thousands of years.

creeper - attached to a substrate; not motile. Without a stalk.

substratum - the ground or any other solid object to which an animal may be attached, on which it moves about, or with which it is otherwise associated.

succession - the replacement of one community by another, the definition includes the (controversial or hypothetical) possibility of "retrograde" succession.


terrace - a raised embankment with the top leveled. A level ordinarily narrow plain usu. with steep front bordering a river, lake, or sea.


tunicata - a subphylum in the Phylum Chordata; includes the tunicates, ascidians, salps, and sea squirts; highly modified marine chordates having a more or less cylindrical or globular shape; body wall covered with a secreted cuticular tunic; sessile, free-swimming, or suspended at surface; solitary or colonial.

turbidity - condition of water resulting from suspended matter, water is turbid when its load of suspended material is excessive.


vascular - consisting of or containing vessels adapted for transmission or circulation of fluid.


zeolite - characterized by or pertaining to conditions of scanty water supply.






ARMY ENGINEER DISTRICT, CHARLESTON	
CORPS OF ENGINEERS	
CHARLESTON, SOUTH CAROLINA	
NAVIGATION PROJECT	
GENERAL PLAN	
LITTLE RIVER INLET	
MOUNTAIN COUNTY, SOUTH CAROLINA & BRUNSWICK COUNTY, NORTH CAROLINA	
DATE: 24 OCT 19	FILE NO. 10043













UPCOAST JETTY PROFILE

JETTY STONE

ITEM	WEIGHT (TON)	SIZE (IN)	QTY
ARMOR STONE	100	48	100
PROTECTION	100	48	100
FOUNDATION BLANKET	100	48	100


\* ASSUMED SPECIFIC WEIGHT 160 LBS PER CU YD (1.35 TON)




TYPICAL HEAD SECTION

10/2


SYMBOL	DESCRIPTION	BY	DATE



LONG PROFILE



TYPICAL WEIR SECTION



TYPICAL SAND DUNE SECTION

ARMY ENGINEER DISTRICT, CHARLESTON ENGINEERING DISTRICT CHARLESTON, SOUTH CAROLINA	
NAVIGATION PROJECT UPCOAST JETTY PROFILE & JETTY SECTIONS LITTLE RIVER INLET	
NOBBY COUNTY, SOUTH CAROLINA SCALE AS SHOWN DATE: 14 SEP 1918	PLATE 3 FILE NO. 0048

*single*





Plate 4

1 of 2



TYPICAL SECTION — NOURISHMENT AREAS

U.S. FARM BUREAU DISTRICT CHARLESTON  
LOOPS 2 (BEEHIVES)  
CHARLESTON SOUTH CAROLINA

NAVIGATION PROJECT

DOWNCOAST JETTY PROFILE

LITTLE RIVER INLET


MURRY COUNTY SOUTH CAROLINA & BROWDER COUNTY NORTH CAROLINA

SCALE AS SHOWN



DATE 24 SEP 1970

PLATE 4

FBI NO 0000




SYMBOL	DESCRIPTION	BY	SA




*20K*

U.S. ARMY ENGINEER DISTRICT, CHARLOTTE		
CHIEF OF ENGINEERS		
CHARLESTON, SOUTH CAROLINA		
<b>NAVIGATION PROJECT</b>		
<b>POTENTIAL</b>		
<b>RECREATION PLAN</b>		
<b>LITTLE RIVER INLET</b>		
WORTH, COUNTY, SOUTH CAROLINA	WORTH, COUNTY, SOUTH CAROLINA	WORTH, COUNTY, SOUTH CAROLINA
SCALE: AS SHOWN	GENERAL DESIGN	PLATE 5
DATE: 24 SEPT 57	MEMORANDUM	FILE NO. 10049









Source: S. C. Wildlife and Marine Resources Department.


holding compliance statistics in the little book that I have.






note 9

146



U.S. NAVY ENGINEERING DIVISION  
CHARLESTON, SOUTH CAROLINA  
LITTLE RIVER NAVIGATION PROJECT  
INTERTIDAL OYSTER SURVEY  
MAY 1976


246




10/10/60

10/10/60


10/10/60





# LITTLE RIVER NAVIGATION PROJECT WETLANDS MAP

- |                       |  |
|-----------------------|--|
| 1. MARSH              | 11. OPEN SAND (beaches, dunes, highland) |
| 2. MARSH              | 12. FORMER OPEN MARSH DISPOSAL AREA      |
| 3. DEEPER MARSH       | 13. WETLANDS SAMPLING STATIONS           |
| 4. SAND ISLAND        | 14. WETLANDS SAMPLING TRANSECTS          |
| 5. OPEN DISPOSAL AREA |  |
| 6. OPEN WATER         |  |
| 7. OPEN SAND          |  |
| 8. MUD FLATS          |  |
| 9. MARSH              |  |



1/1/77

1/1/77






TABLE 1  
SOIL TEST RESULTS - LITTLE RIVER INLET

BOR. NO.	SAMP. NO.	DEPTH		SOIL CLASS.	MECH. ANAL.			
		TOP	BOTT.		#1	#10	#40	#200
CR-1	1	0.0	1.5	SP	-	-	-	-
"	2	4.5	6.0	SP	100	100	99	99
"	4	26.0	37.5	SC	100	97	80	13
"	5	39.0	40.5	CH	-	-	-	-
CR-2	2	15.0	16.5	SP	100	100	98	99
CR-3	1	0.0	1.5	SP - SM	-	-	-	-
"	2	4.5	6.0	SP - SM	-	-	-	-
"	4	13.5	15.0	SP - SM	-	-	-	-
CR-4	1	0.0	1.5	SP - SM	100	99	98	99
"	2	4.5	6.0	SP - SM	-	-	-	-
"	3	9.0	10.5	SP - SM	100	99	84	99
CR-5	3	9.0	10.5	SP	99	99	99	99
"	4	15.0	16.5	SP - SM	-	-	-	-
"	6	24.0	25.5	SP - SM	-	-	-	-
CR-6	2	4.5	6.0	SP - SM	-	-	-	-
"	3	9.5	10.5	SP	99	99	98	99
"	4	15.0	16.5	SP - SM	100	100	98	99
CR-7	1	0.0	1.5	SP - SM	-	-	-	-
"	3	9.0	10.5	SP - SM	-	-	-	-
"	4	15.0	16.5	SP - SM	-	-	-	-
CR-8	1	0.0	1.5	SP - SM	-	-	-	-
"	4	15.0	16.5	SP - SM	-	-	-	-
CR-9	1	0.0	1.5	SP	100	100	92	99
"	2	4.5	6.0	SP - SM	-	-	-	-
CR-10	1	0.0	1.5	SP - SM	-	-	-	-
"	2	4.5	6.0	SP	100	99	99	99
"	4	15.0	16.5	SP	99	99	91	99
CR-11	1	0.0	1.5	SP - SM	100	99	99	99
"	2	4.5	6.0	SP	-	-	-	-
"	3	9.0	10.5	SP - SM	99	99	96	99
"	4	15.0	16.5	SP - SM	-	-	-	-
CR-12	2	4.5	6.0	SP - SM	-	-	-	-
"	3	9.0	10.5	SP - SM	-	-	-	-
"	5	19.5	21.0	SP - SM	-	-	-	-
CR-13	1	0.0	1.5	SP - SM	-	-	-	-
"	2	4.5	6.0	SP	99	99	98	99
"	4	15.0	16.5	SP - SM	99	99	91	99
"	5	19.0	21.0	SP - SM	-	-	-	-
"	6	24.0	25.5	CH	-	-	-	-
"	8	34.5	36.0	SM	-	-	-	-
"	9	39.0	40.5	CH	100	100	99	99

NOTE: - means less than 0.075 mm sieve size. SP = sand, SM = silt, CH = clay, CL = clay, LL = liquid limit, PL = plastic limit, PI = plasticity index, U = undisturbed, D = disturbed, C = compression, E = expansion, S = shrinkage, T = tensile, V = volume, W = weight, M = moisture, F = field, L = laboratory, R = results, P = procedure, M = method, T = test, E = equipment, S = sample, D = data, C = calculation, U = unit, V = value, W = weight, M = moisture, F = field, L = laboratory, R = results, P = procedure, M = method, T = test, E = equipment, S = sample, D = data, C = calculation, U = unit, V = value.

Table 2 Chemical analysis of sediment samples from Little River Inlet. Values are expressed as percent by weight (dry basis).

	LRI-2	LRI-1	LRI-3	LRI-5	LRI-7	LRI-9
Volatile Solids (Max. 6.0)	1.06	0.43	0.68	1.11	1.10	2.00
T.V.S. Formula EC	1.60	1.36	1.42	2.45	1.96	1.89
Total Organic Carbon	< 0.10	< 0.10	< 0.10	0.40	0.20	0.21
C.O.D., (Max. 5.0)	0.29	0.40	0.10	1.15	0.65	0.58
Nitrogen, Kjeldahl (Max. 0.10)	0.042	0.050	0.046	0.066	0.048	0.045
Oil and Grease (Max. 0.15)	0.025	0.022	0.020	0.028	0.049	0.000
Lead (Max. 0.005)	0.0005	< 0.0005	< 0.0005	0.0011	0.0013	0.0000
Zinc (Max. 0.005)	0.0011	0.0005	0.0006	0.0013	0.0007	0.0000
Mercury (Max. 0.0001)	< 0.00002	< 0.00002	< 0.00002	< 0.00002	< 0.00002	< 0.00002
Total P as PO <sub>4</sub>	0.07	0.04	0.04	0.06	0.07	0.05
Iron	0.355	0.075	0.165	0.460	0.220	0.260
Cadmium	< 0.00005	< 0.00005	< 0.00005	0.00008	0.00006	0.00000
Arsenic	0.00012	0.00009	0.00005	0.00013	0.00005	0.00000
Chromium	0.00100	0.00040	0.00060	0.00140	0.00090	0.00000
Nickel	0.00050	< 0.00050	< 0.00050	0.00080	< 0.00050	0.00000
Copper	0.00056	0.00034	0.00038	0.00124	0.00042	0.00000
Beryllium	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Selenium	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Vanadium	0.0008	< 0.0005	< 0.0005	0.0017	0.0010	0.00000

Table 3. Data collected during routine studies in the waters of the study.

Station	Date	Time	Temp. (C)	Salinity (‰)	Diss. (mg/l)	Turbidity (NTU)	Solids (mg/l)		Nutrients (µg/l)	
							Suspended	Settleable	NO <sub>3</sub> -N	PO <sub>4</sub> -P
LRI-1	20-IV-76	Surface	21.3	33.25	7.3	2.7	-	-	11.3	3.3
		Bottom	23.5	33.96	6.3	13.0	-	-	2.7	1.5
LRI-1	20-IV-76	Surface	22.5	33.14	7.8	2.0	-	-	2.0	0.8
		Bottom	22.0	33.79	7.8	3.3	-	-	2.8	1.0
LRI-3	21-IV-76	Surface	22.3	32.75	7.8	3.2	-	-	-	-
		Bottom	22.6	33.25	7.8	3.7	-	-	1.6	0.9
LRI-3	21-IV-76	Surface	21.2	33.71	7.9	3.1	54.0	61.2	10.1	0.7
		Bottom	23.9	33.74	7.7	3.2	-	-	6.2	0.8
LRI-7	21-IV-76	Surface	22.7	32.97	7.6	3.1	-	-	-	-
		Bottom	22.4	33.13	7.7	2.7	-	-	22.1	1.0
LRI-7	20-IV-76	Surface	22.2	29.59	7.2	4.3	50.8	50.8	23.1	1.4
		Bottom	21.7	31.42	7.3	5.0	-	-	6.1	1.3
LRI-9	21-IV-76	Surface	22.7	32.00	7.6	3.8	-	-	2.1	1.7
		Bottom	22.3	33.02	7.4	3.4	-	-	7.4	1.0
LRI-9	20-IV-76	Surface	24.4	25.56	6.9	5.4	64.4	20.4	31.8	2.5
		Bottom	23.5	26.21	7.2	5.1	99.8	12.8	15.4	2.4
LRI-9	21-IV-76	Surface	23.2	31.00	7.4	4.4	73.6	2.4	-	-
		Bottom	22.8	32.81	7.3	5.3	-	-	-	-

Source: S. C. Wildlife and Marine Resources Department

# Table 1

Percentages of invertebrates collected on water column and on land near shore, and their estimated densities. Percentages of invertebrates were based on two 100 m<sup>2</sup> samples of water column Stations, one at High Tide, one at Mid Tide, and one at Low Tide.

Percentages of invertebrates collected on water column and on land near shore, and their estimated densities.

Invertebrate	High Tide		
	Water Column	Land	Water Column
Amphipods	355	20	20
Polychaetes	140	15	15
Crustaceans	70	10	10
Isopods	65	5	5
Hydroids	20	10	10
Other	10	5	5
Amphipods	5	1	1
Polychaetes	10	10	10
Crustaceans	10	10	10
Isopods	5	5	5
Hydroids	5	5	5
Other	5	5	5
Amphipods	65%	61%	61%
Polychaetes	1	10	10
Crustaceans	0.00	0.77	1.00
Isopods	0.00	1.86	2.00

## Table 2

Invertebrate	High Tide		
	Water Column	Land	Water Column
Amphipods	205	40%	40%
Polychaetes	10	21	21
Crustaceans	5	20%	20%
Isopods	13	10	10
Hydroids	5	5	5
Other	5	5	5
Amphipods	20%	20%	20%
Polychaetes	3	10	10
Crustaceans	0.12	1.00	1.00
Isopods	1.1	1.00	1.00

Percentages of invertebrates collected on water column and on land near shore, and their estimated densities.

Table 5. Species of macroinvertebrates collected in the entrance channel, and their estimated densities in numbers  $m^{-2}$ . Estimates were based on two 0.13  $m^2$  samples at each of three stations:

A = amphipod, D = decapod, B = bivalve, P = polychaete, G = gastropod, E = echinoderm, I = isopod

Species	LRE-1	LRE-2	LRE-3
<i>Spiophanes bombyx</i> (P)		354	
<i>Parahaustorius longimerus</i> (A)			177
<i>Neohaustorius schmitzi</i> (A)			158
<i>Magelona</i> sp. (P)	131	8	4
<i>Tellina</i> sp. (B)	46	73	
<i>Clymenella torquata</i> (P)	54	19	
<i>Homipholis elongata</i> (E)		58	
<i>Glycera dibranchiata</i> (P)	15	35	
<i>Paraprionospio pinnata</i> (P)	31	19	
Nemertina (undet.)	19	15	
<i>Heteromastus filiformis</i> (P)		35	
Polychaeta (undet.)	12	23	
<i>Sigambra bassji</i> (P)	8	23	
<i>Turbonilla interrupta</i> (G)	27		
<i>Aglaophanus verrilli</i> (P)	12	12	
<i>Pectinaria gouldii</i> (P)	19	4	
<i>Baginoca solitaria</i> (G)	12	8	
<i>Nereis succinea</i> (P)	4	15	
<i>Batea catharinensis</i> (A)	4	15	
<i>Corophium</i> sp. (A)	4	15	
<i>Eteone</i> sp. (P)		15	
<i>Diopatra cuprea</i> (P)		12	

Table 5. (continued)

Species	LRE-1	LRE-2	LRE-3
<u>Sabellaria vulgaris</u> (P)		12	
<u>Anadara ovalis</u> (B)		12	
<u>Notomastus hemipodus</u> (P)		8	
<u>Nephtys bucera</u> (P)	4	4	
<u>Lycastopsis</u> sp. (P)	8		
<u>Eteone heteropoda</u> (P)		8	
<u>Spio</u> sp. (P)		8	
<u>Busycen carica</u> (G)		8	
<u>Brachidontes exustus</u> (B)		8	
<u>Mulinia lateralis</u> (B)		8	
<u>Edotea montosa</u> (I)		8	
<u>Microprotopus shoemakeri</u> (A)	8		
<u>Pionixa retinens</u> (D)	8		
<u>Leptosynapta inhaerens</u> (E)	8		
<u>Arenicola marina</u> (P)	4		
<u>Baploscoplos fragilis</u> (P)		4	
<u>Owenia fusiformis</u> (P)	4		
<u>Sthenelais boa</u> (P)		4	
<u>Spio setosa</u> (P)	4		
<u>Polinices duplicatus</u> (G)		4	
<u>Mitrella lunata</u> (G)	4		
<u>Terebra dilocata</u> (G)		4	
<u>Nucula proxima</u> (B)	4		
<u>Anadara</u> sp. (B)		4	
<u>Donax variabilis</u> (B)			4
Pelecypoda A (undet.)			4
Pelecypoda B (undet.)	4		

Table 2. (continued)

Species	IRE-1	IRE-2	IRE-3
<i>Ardea herodias</i> (H)			4
<i>Ardea herodias</i> (H)			4
<i>Ardea herodias</i> (H)			4
<i>Ardea herodias</i> (H)		4	
<i>Ardea herodias</i> (H)	4		
<i>Ardea herodias</i> (H)		4	
<i>Ardea herodias</i> (H)	4		
<i>Ardea herodias</i> (H)		4	
<i>Ardea herodias</i> (H)			4
No. Individuals	466	874	359
No. Species	28	37	8
Species Richness	4.39	5.32	1.19
Species Diversity (H')	3.86	3.73	1.46

Source: S. C. Wildlife and Marine  
Resources Department

Table 6. Benthic invertebrates from dredge collections at three stations in the Entrance Channel.

Species	LRE-1	LRE-2	LRE-3
Phylum Cnidaria			
<u>Rhopilema verrilli</u> (polyp)			+
Phylum Annelida			
<u>Sabellaria vulgaris</u>		+	
Phylum Mollusca			
<u>Brachidontes exustus</u>			+
<u>Bryozoa canaliculata</u>		+	
<u>Bryozoa calica</u>	+	+	
Phylum Arthropoda			
<u>Balanus amphitrite</u>		+	
<u>Balanus</u> sp. (cyprids)			+
<u>Portunus gibbesi</u>	+	+	
<u>Portunus spinimanus</u>	+		
Phylum Hemichordata			
<u>Balanoglossus aurantiacus</u>	+		
Number of species	4	5	3

Source: S. C. Wildlife and Marine  
Resources Department



Table 7. Species of macroinvertebrates collected in the inner channel, and their estimated densities in numbers  $m^{-2}$ . Estimates were based on two 0.13  $m^2$  samples at each of nine stations.

A = amphipod, P = polychaete, B = bivalve, D = decapod, E = echinoderm, L = larva, Ba = barnacle, F = Flatworm

Species	LRI-1	LRI-2	LRI-3	LRI-4	LRI-5	LRI-6	LRI-7	LRI-8	LRI-9
<i>Neodanagobius schlegelii</i> (A)		262	782	358					
<i>Spio-phros hemphys</i> (P)			12		42	139	127	97	213
<i>Heterostichus filiger</i> (P)					12	123	59	19	246
<i>Neteliseria chnei</i> (D)					8	54	42	27	169
<i>Parachanna longimanus</i> (A)	62		131	39					
<i>Lepidostichus styriacus</i> (A)	154	35		12					
Polychaeta (undet.)					12	62		11	31
<i>Brachidontes exilis</i> (B)			27		4		4	69	
<i>Leopaeopsis styl</i> (D)						8	12	4	58
<i>Spio setosa</i> (P)							4	4	73
<i>Podarke chelona</i> (P)								12	62
<i>Oligera diaphanellata</i> (P)						15	8	12	35
<i>Streblospio benedicti</i> (P)							31	15	15
<i>Metanephria metanephria</i> (D)					4		12	19	19
<i>Nemertina</i> (undet.)					12	15		4	19
<i>Natona</i> (amphipod) (P)					4	23			
<i>Eugenia longimanus</i> (D)		35							
<i>Anodonta</i> (undet.)					4	23			4
<i>Clypeosyllis regina</i> (P)						8			15
<i>Mollusca</i> (indet.) (A)									31
<i>Lebistostoma</i> (indet.) (P)							8	4	15
<i>Polysiphonia</i> (undet.)							12		11

Table 7. (continued)

Species	LR1-1	LR1-2	LR1-3	LR1-4	LR1-5	LR1-6
<i>Hemipholis elongata</i> (F)						1
<i>Eteone lactea</i> (P)				4		15
<i>Nuculana</i> sp. (B)					15	4
<i>Pectinaria gouldii</i> (P)					8	
<i>Scalworn</i> (undet.)					6	
<i>Apophatete</i> sp. (P)						4
<i>Tellina</i> sp. (B)			8	4	4	
<i>Astelidium</i> sp. (P)						
<i>Phyllodoce</i> sp. (P)						1
<i>Solen viridis</i> (B)						
<i>Magelona</i> sp. (P)			4	8		
<i>Anagides ordlia</i> (B)						8
<i>Myxid</i> (undet.)				12		
<i>Nephtys buccata</i> (P)					8	
<i>Artefida</i> sp. (P)					8	
<i>Sabellaria vulgaris</i> (P)						
<i>Nucula proxima</i> (P)						8
<i>Cyathus furcatus</i> (P)						8
<i>Chironomus</i> sp. (C)			8			
<i>Idotea costata</i> (C)						
<i>Caprellus ellipticus</i> (P)			4			
<i>Neomartina</i> (undet.)						
<i>Glycymeris americana</i> (P)					4	
<i>Diopatra cuprea</i> (C)						
<i>Eteone heteropoda</i> (P)						
<i>Phyllodoce</i> sp. (P)						

AD-A149 773 LITTLE RIVER INLET NAVIGATION PROJECT BRUNSWICK COUNTY 2/2  
NORTH CAROLINA AND. (U) CORPS OF ENGINEERS CHARLESTON  
SC CHARLESTON DISTRICT JUN 77

LITTLE RIVER INLET NAVIGATION PROJECT BRUNSWICK COUNTY  
NORTH CAROLINA AND. (U) CORPS OF ENGINEERS CHARLESTON  
SC CHARLESTON DISTRICT JUN 77

212


UNCLASSIFIED SC CHARLESTON DISTRICT JUN 77 F/G 13/2 NL

F/G 13/2

NL

END

Environ Monit Assess (2008) 142:111–120



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS 1963-A

Table 1. (continued)

Species	LRI-1	LRI-2	LRI-3	LRI-4	LRI-5	LRI-6	LRI-7	LRI-8	LRI-9
<u>Sigambra bassi</u> (P)							4		
<u>Sabella microphthalmia</u> (P)									
<u>Spio</u> sp. (P)					4				
<u>Mulinia lateralis</u> (B)					4				
<u>Abra dioica</u> (B)					4				
<u>Balanus improvisus</u> (Ba)					4				
<u>Unciola serrata</u> (A)					4				
<u>Paracaprella tenuis</u> (A)					4				
Amphipod (undet.)							4		
<u>Clibanarius vittatus</u> (D)									4
<u>Pagurus</u> sp. (D)					4				
No. Individuals	216	332	976	433	158	517	365	336	1182
No. Species	2	3	8	6	21	15	20	19	27
Species Richness	0.19	0.34	1.02	0.82	3.95	2.24	3.22	3.09	3.67
Species Diversity (H')	0.86	0.95	1.04	1.00	3.89	3.11	3.31	3.45	3.58

Source: S. C. Wildlife and Marine  
Resources Department

Table 8. Benthic invertebrates from oyster dredge collections at nine stations in the Inner Channel.

Species	LRI-1	LRI-2	LRI-3	LRI-4	LRI-5	LRI-6	LRI-7	LRI-8	LRI-9
Phylum Porifera									
<u>Microciona prolifera</u>		+							
<u>Cliona celata</u>				+	+			+	
Sponge (undet.)		+							
Phylum Cnidaria									
<u>Rhopilema verrilli</u> (polyp)			+	+					
<u>Bougainvillia rugosa</u>				+	+		+		+
<u>Garveia franciscana</u>								+	
<u>Garveia humilis</u>								+	
<u>Amphinema dinema</u>					+				+
<u>Campanulina</u> sp.						+	+		
<u>Obelia dichotoma</u>				+	+	+	+	+	+
<u>Astrangia danae</u>					+				
Anemone (undet.)								+	+
Phylum Platyhelminthes									
<u>Stylochus ellipticus</u>					+	+	+	+	+
Phylum Rhynchocoela									
Nemertine (undet.)					+				
Phylum Entoprocta									
<u>Barentsia gracilis</u>									
Phylum Bryozoa									
<u>Alcyonidium hauffi</u>					+				

Table 8. (continued)

Species	LRI-1	LRI-2	LRI-3	LRI-4	LRI-5	LRI-6	LRI-7	LRI-8	LRI-9
<u>Anguinella palmata</u>				+	+				
<u>Bowerbankia gracilis</u>					+	+	+	+	
<u>Membranipora arborescens</u>					+				
<u>Membranipora tenuis</u>					+	+		+	+
<u>Conopeum tenuissimum</u>					+		+	+	+
<u>Electra monostachys</u>				+	+		+	+	+

## Phylum Annelida

<u>Notomastus hemipodus</u>								+	
<u>Nereis succinea</u>				+	+		+	+	+
<u>Sabellaria vulgaris</u>					+			+	+
<u>Hydroides dianthus</u>					+			+	+
Syllidae (undet.)								+	
<u>Ampharete</u> sp.								+	

## Phylum Mollusca

<u>Crepidula plana</u>									+
<u>Urosalpinx cinerea</u>						+			
Nudibranch (undet.)		+			+				+
<u>Anadara ovalis</u>								+	
<u>Brachidontes exustus</u>			+		+	+	+	+	+
<u>Lithophaga bisulcata</u>					+				
<u>Modiolus modiolus squamosus</u>					+				
<u>Martesia cuneiformis</u>					+		+		
<u>Crassostrea virginica</u>					+			+	+
<u>Mercenaria mercenaria</u>					+			+	
Bivalve (undet.)								+	

Table 8. (continued)

Species	LRI-1	LRI-2	LRI-3	LRI-4	LRI-5	LRI-6	LRI-7	LRI-8	LRI-9
Phylum Arthropoda									
<u>Balanus amphitrite</u>		+							
<u>Balanus improvisus</u>			+	+	+	+	+	+	+
<u>Cleantis planicauda</u>			+						
<u>Melita nitida</u>									+
<u>Erichthonius brasiliensis</u>					+				
<u>Paracaprella tenuis</u>					+			+	
<u>Clibanarius vittatus</u>			+						
<u>Pagurus longicarpus</u>		+							
<u>Callinectes sapidus</u>							+		+
<u>Hexapanopus angustifrons</u>		+			+				
<u>Eurypanopus depressus</u>							+		
Phylum Echinodermata									
<u>Asterias forbesi</u> (juv.)								+	
Phylum Chordata									
<u>Molgula manhattensis</u>				+	+			+	+
No. Species	0	6	5	9	29	8	13	25	20

Source: S. C. Wildlife and Marine  
Resources Department



Table 9. Species of macroinvertebrates collected in adjacent waterways, and their estimated densities in numbers  $m^{-2}$ . Estimates were based on two 0.13  $m^2$  samples at each of eight stations.

P = polychaete, B = bivalve, A = amphipod, D = decapod, E = echinoderm,  
G = gastropod, T = tunicate, C = cumacean.

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
<i>Spioptanus boeckii</i> (P)		42	58	123	139	81	54	424
<i>Nereis succinea</i> (P)	23	23					246	316
<i>Podiceps obsoletus</i> (P)		39					331	8
<i>Notomastus hemipodus</i> (P)	23	35			15		85	62
Polychaeta (undet.)	54	23	8	15	12		77	46
<i>Tellina</i> sp. (B)	23	19		4	108	35		
<i>Chironella turgida</i> (P)		23		27			100	15
<i>Corophium lacustris</i> (A)	62			12			69	
Nemertina (undet.)	15		8	8	4	8	8	46
<i>Melita nitida</i> (A)	85							
<i>Mercenaria mercenaria</i> (B)	23	19		4			15	15
<i>Autolytus fasciatus</i> (P)		4						69
<i>Nephtys incerta</i> (P)			42		19	12		
<i>Amphicharterius</i> sp. (A)			19		23	31		
<i>Streblospio benedicti</i> (P)		15		12				39
<i>Paraprionospio pinnata</i> (P)		4		46				
<i>Paraprionospio pinnata</i> (P)				39	8			
<i>Glycerodrilus olivaceus</i> (P)	23			19				
<i>Chironomus tentaculatus</i> (B)	31	4						
<i>Glycera americana</i> (E)				8				23
Amphipod (undet.)							8	15
<i>Polydora lignea</i> (P)							15	8

Table 9. (continued)

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
<u>Neopanope savi</u> (D)		4						15
<u>Spio setosa</u> (P)							15	
<u>Pelecypoda</u> (undet.)		15						
<u>Microprotopus raneyi</u> (A)							15	
<u>Asterias forbesi</u> (E)								15
<u>Hemipholis elongata</u> (E)								15
<u>Pectinaria gouldii</u> (P)				4			8	
<u>Abra lioica</u> (B)				4				8
<u>Glycera</u> sp. (P)		4					4	
<u>Haploscoloplos fragilis</u> (P)	8							
<u>Polydora ligni</u> (P)					4	4		
<u>Pista</u> sp. (P)							8	
<u>Diodora cayenensis</u> (G)							8	
<u>Brachidontes exustus</u> (B)		8						
<u>Spisula</u> sp. (B)							8	
<u>Mulinia lateralis</u> (B)							8	
<u>Chione cancellata</u> (B)								8
<u>Batea catharinensis</u> (A)							8	
<u>Alpheus normani</u> (D)							8	
<u>Pagurus</u> sp. (D)								8
<u>Portunus</u> sp. (D)								8
<u>Molgula manhattensis</u> (T)							8	
<u>Heteromastus filiformis</u> (P)				4				
<u>Onuphis</u> sp. (P)		4						
<u>Diopatra cuprea</u> (P)					4			
<u>Ampharete</u> sp. (P)				4				

Table 9. (continued)

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
Gastropod (undet.)				4				
<u>Nucula proxima</u> (B)				4				
<u>Nuculana</u> sp. (B)			4					
<u>Cyclaspis varians</u> (C)				4				
<u>Oxyurostylus smithi</u> (C)					4			
<u>Ampelisca vadorum</u> (A)				4				
<u>Corophium</u> sp. (A)		4						
<u>Trichorhoxus epistomus</u> (A)						4		
<u>Protohaustorius deichmannae</u> (A)					4			
<u>Lystriella clymenellae</u> (A)				4				
<u>Monoculoides</u> sp. (A)		4						
<u>Pinnixa chaetopterana</u> (D)					4			
No. Individuals	370	293	139	353	348	175	1106	1163
No. Species	11	19	6	21	13	7	22	20
Species Richness	1.69	3.17	1.01	3.41	2.05	1.16	3.00	2.69
Species Diversity (H')	3.18	3.79	2.06	3.35	2.47	2.14	3.21	2.94

Source: S. C. Wildlife and Marine  
Resources Department

Table 10. Benthic invertebrates from oyster dredge collections at eight stations in adjacent waterways.

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
Phylum Porifera								
<u>Cliona celata</u>							+	+
<u>Cliona truitti</u>							+	+
Phylum Cnidaria								
<u>Ectopleura dumortieri</u>				+				+
<u>Turritopsis nutricula</u>							+	+
Hydractiniidae (undet.)							+	
<u>Bougainvillia rugosa</u>		+						
<u>Garveia franciscana</u>		+						
<u>Garveia humilis</u>								+
<u>Amphinema dinema</u>								+
Pandeidae (undet.)		+					+	
<u>Eudendrium</u> sp.							+	+
<u>Clytia cylindrica</u>							+	+
<u>Clytia kincaidi</u>								+
<u>Obelia dichotoma</u>	+	+		+			+	+
<u>Campanulina</u> sp.			+	+				
<u>Campanopsis</u> (?) sp.							+	+
<u>Schizotricha tenella</u>							+	+
<u>Renilla reniformis</u>						+		
<u>Haliplanella luciae</u>							+	
<u>Astrangia danae</u>							+	
Phylum Platyhelminthes								
<u>Stylochus ellipticus</u>	+	+		+			+	+

Table 10. (continued)

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
Phylum Rhynchocoela								
Nemertine (undet.)							+	
Phylum Entoprocta								
<u>Pedicellina cernua</u>							+	+
Phylum Bryozoa								
<u>Anguinella palmata</u>							+	+
<u>Bowerbankia gracilis</u>							+	+
<u>Aeverrillia setigera</u>							+	
<u>Membranipora tenuis</u>	+	+	+	+			+	+
<u>Conopeum tenuissimum</u>	+	+						
<u>Electra monostachys</u>		+		+				
<u>Bugula neritina</u>				+				
<u>Schizoporella errata</u>							+	
<u>Parasmittina nitida</u>							+	
Phylum Annelida								
<u>Clymenella torquata</u>				+				
<u>Nereis succinea</u>	+	+		+			+	+
<u>Sabellaria vulgaris</u>		+		+			+	+
<u>Hydroides dianthus</u>							+	+
<u>Polydora sp.</u>	+							
Phylum Mollusca								
<u>Diodora cayenensis</u>								+
<u>Urosalpinx cinerea</u>							+	+
<u>Eupleura caudata</u>							+	+

Table 10. (continued)

Species	LRA-1	LRA-2	LRA-3	LRA-4	LRA-5	LRA-6	LRA-7	LRA-8
<u>Busycon carica</u>							+	+
<u>Brachidontes exustus</u>	+	+	+	+				+
<u>Anomia simplex</u>								+
<u>Crassostrea virginica</u>	+	+					+	+
<u>Chione cancellata</u>							+	+
<u>Marlesia cuneiformis</u>							+	+
Phylum Arthropoda								
<u>Balanus amphitrite</u>				+				
<u>Balanus improvisus</u>	+	+	+	+			+	+
<u>Erichthonius brasiliensis</u>	+		+					
<u>Paracaprella tenuis</u>							+	+
<u>Alpheus normanni</u>							+	+
<u>Callinectes sapidus</u>			+					+
<u>Panopeus herbstii</u>	+							+
Phylum Echinodermata								
<u>Asterias forbesi</u>							+	+
<u>Ophiothrix angulata</u>							+	
<u>Mellita quinquesperforata</u>					+			
Phylum Chordata								
<u>Molgula manhattensis</u>							+	
No. Species	11	13	6	13	1	1	36	35

Source: S. C. Wildlife and Marine  
Resources Department

Table 11 List of observed marsh and marsh-bordering plants in the Little River  
Inlet study area.

Common Name	Scientific Name	Abbreviation	Location
Smooth cordgrass	<u>Spartina alterniflora</u> short form medium form	SSA MSA	low marsh, high marsh
Marsh-hay cordgrass	<u>Spartina patens</u>	Sp	high marsh, shrub border
Sea lavender	<u>Limonium sp.</u>	L	high marsh, shrub border
Glasswort	<u>Salicornia virginica</u>	Sv	high marsh
Salt-marsh aster	<u>Aster sp.</u>	A	high marsh
Sea ox-eye	<u>Borreria frutescens</u>	Bf	high marsh, shrub border
Salt-grass	<u>Distichlis spicata</u>	Ds	high marsh, shrub border
Salt-marsh fimbriatilis	<u>Fimbristylis spadicea</u>	Fs	high marsh, shrub border
Seaside goldenrod	<u>Solidago sempervirens</u>	Ss	high marsh, shrub border
Coastal dropseed	<u>Sporobolus virginicus</u>	SV	high marsh
Black needlerush	<u>Juncus roemerianus</u>	Jr	high marsh, shrub border
American three-square	<u>Scirpus americanus</u>	Sa	high marsh
Salt-marsh bulrush	<u>Scirpus robustus</u>	Sr	high marsh
Narrow-leaved cattail	<u>Typha angustifolia</u>	Ta	high marsh
Sea-blite	<u>Suaeda linearis</u>	Sl	high marsh (shell mounds)
Swathgrass	<u>Panicum virgatum</u>	Pv	shrub border
Poison ivy	<u>Rhus radicans</u>	Rr	shrub border
High tide bush	<u>Iva frutescens</u>	If	shrub border
Sea myrtle	<u>Baccharis hamatifolia</u>	Bh	shrub border, adjacent upland
Wax myrtle	<u>Myrica cerifera</u>	Mc	shrub border, adjacent upland
Coastal cedar	<u>Juniperus virginiana</u>	Jv	adjacent upland
Slash pine	<u>Pinus elliotii</u>	Pe	adjacent upland
Loblolly pine	<u>Pinus taeda</u>	Pt	adjacent upland
Yaupon	<u>Ilex vomitoria</u>	Iv	adjacent upland
Live oak	<u>Quercus virginiana</u>	Qv	adjacent upland
Greenbriar	<u>Smilax sp.</u>	S	adjacent upland
Pokeweed	<u>Phytolacca americana</u>	Pa	adjacent upland
Broomsedge	<u>Andropogon sp.</u>	A	adjacent upland, shrub border
Finger grass	<u>Chloris sp.</u>	C	adjacent sand flat
Beach elder	<u>Iva imbricata</u>	Ii	adjacent sandflat
Sea oats	<u>Uniola paniculata</u>	Up	adjacent dune ridge
Camphorweed	<u>Heterotheca subaxillaris</u>	Hs	adjacent sandflat, spoil area
Dock	<u>Rumex cf. hastatulus</u>	Rh	adjacent sandflat, spoil area

Source: S. C. Wildlife and Marine  
Resources Department

TABLE 12. Results of field observations of 19 marsh locations in Little River Inlet study area.

STATION NO.	GENERAL LOCATION	DOMINANT VEGETATION	ASSOCIATED VEGETATION	APPROXIMATE ELEVATION (FT. above MSL)	COMMENTS
1	Bird Island	<i>Spartina alterniflora</i>		4.7	Monospecific stand
1a	Bird Island	<i>Spartina patens</i>	SSA, L, Bf, Sv, Ds, F, Ss, Ss, Bh	5.1	Isolated old spoil mound
2	Bonaparte Creek	<i>Spartina alterniflora</i>		4.6	Monospecific stand
3	Goat Island	<i>Spartina alterniflora</i>	Higher elevations - Sv Bf, L, Sp, Fs	4.3	Island edge of island - Sp, v., Sp, If, Pv, Ss, Bh, Bf, L, Ss, Jr
4	Goat Island	<i>Spartina alterniflora</i> (MSA & SSA)	Marsh edge - SSA, Ds, Sp, Bf, If, Pv, Bh, Jr	3.5	Edge of island - Pt, Mc, S and other maritime forest species
5	Goat Island	<i>Spartina patens</i>	If, Bf, L, Bh, Mc, Pv, Jr	5.5	Lower elevations - MSA, Sv, Ds, Bf, L, A
5a	Goat Island	<i>Spartina alterniflora</i>	Higher elevations - Ds, MSA, Bf, L, Sp, If	3.7	
6	Waties Island	<i>Silene virginica</i>	MSA, Ds, L, Bf	5.3	Higher elevations (spoil mound) - Sp, If, Bf, Ds, SSA, A, Pv, Fs, Ss, Sp, v.
7	Waties Island	<i>Spartina patens</i> (higher levels) Mixed community (lower levels)	Bf, If, Ds, Sv, A, L, Bf, Ds, Sv, SSA, A, L	5.5	<i>Spartina patens</i> replaced by <i>Spartina alterniflora</i> at lower elevations
8	Waties Island	<i>Spartina patens</i>	Fs, Ds, Bf, L, Mc, Sr, Iv	5.8	
9	Mink Island	<i>Spartina alterniflora</i>		5.2	Monospecific stand
10	Mink Island	Mixed community - Mc, Iv, Iv, Bh, If	Typical high marsh species	7.4	Former open marsh disposal area
11	Milliken Cove	<i>Spartina alterniflora</i>	St, If, Bf, Sp and other high marsh species	4.5	
12	Colkins Neck AIRM	<i>Spartina alterniflora</i>	Ta, Bf, If, Bh and other high marsh species	5.0	
13	Little River Neck Little River	<i>Spartina alterniflora</i>	Ss, Sr, Ta, Jr, Sv, L, Sp, If, Bf, Bh, Sl	4.5	Edge of mainland - Mc, Bh, Pt, Jv, Qv, Iv; <i>Scirpus americanus</i> abundant along marsh-upland border
14	The Battery Island	<i>Spartina alterniflora</i>		3.4	Monospecific stand
15	Dunn Sound Creek	<i>Spartina alterniflora</i>		4.4	Monospecific stand
16	Dunn Sound Creek	<i>Spartina alterniflora</i>		4.2	Monospecific stand
17	Dunn Sound Creek	<i>Spartina alterniflora</i>		3.2	Monospecific stand

Source: S. C. Wildlife and Marine  
Resources Department



TABLE 11  
COSTS OF THE ARGENTINE, 1911-1912

Year	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
Population	100,000	105,000	110,000	115,000	120,000	125,000	130,000	135,000	140,000	145,000	150,000	155,000	160,000	165,000	170,000	175,000	180,000	185,000	190,000	195,000	200,000	205,000	210,000	215,000	220,000	225,000	230,000	235,000	240,000	245,000	250,000	255,000	260,000	265,000	270,000	275,000	280,000	285,000	290,000	295,000	300,000	305,000	310,000	315,000	320,000	325,000	330,000	335,000	340,000	345,000	350,000	355,000	360,000	365,000	370,000	375,000	380,000	385,000	390,000	395,000	400,000	405,000	410,000	415,000	420,000	425,000	430,000	435,000	440,000	445,000	450,000	455,000	460,000	465,000	470,000	475,000	480,000	485,000	490,000	495,000	500,000	505,000	510,000	515,000	520,000	525,000	530,000	535,000	540,000	545,000	550,000	555,000	560,000	565,000	570,000	575,000	580,000	585,000	590,000	595,000	600,000	605,000	610,000	615,000	620,000	625,000	630,000	635,000	640,000	645,000	650,000	655,000	660,000	665,000	670,000	675,000	680,000	685,000	690,000	695,000	700,000	705,000	710,000	715,000	720,000	725,000	730,000	735,000	740,000	745,000	750,000	755,000	760,000	765,000	770,000	775,000	780,000	785,000	790,000	795,000	800,000	805,000	810,000	815,000	820,000	825,000	830,000	835,000	840,000	845,000	850,000	855,000	860,000	865,000	870,000	875,000	880,000	885,000	890,000	895,000	900,000	905,000	910,000	915,000	920,000	925,000	930,000	935,000	940,000	945,000	950,000	955,000	960,000	965,000	970,000	975,000	980,000	985,000	990,000	995,000	1,000,000	1,005,000	1,010,000	1,015,000	1,020,000	1,025,000	1,030,000	1,035,000	1,040,000	1,045,000	1,050,000	1,055,000	1,060,000	1,065,000	1,070,000	1,075,000	1,080,000	1,085,000	1,090,000	1,095,000	1,100,000	1,105,000	1,110,000	1,115,000	1,120,000	1,125,000	1,130,000	1,135,000	1,140,000	1,145,000	1,150,000	1,155,000	1,160,000	1,165,000	1,170,000	1,175,000	1,180,000	1,185,000	1,190,000	1,195,000	1,200,000	1,205,000	1,210,000	1,215,000	1,220,000	1,225,000	1,230,000	1,235,000	1,240,000	1,245,000	1,250,000	1,255,000	1,260,000	1,265,000	1,270,000	1,275,000	1,280,000	1,285,000	1,290,000	1,295,000	1,300,000	1,305,000	1,310,000	1,315,000	1,320,000	1,325,000	1,330,000	1,335,000	1,340,000	1,345,000	1,350,000	1,355,000	1,360,000	1,365,000	1,370,000	1,375,000	1,380,000	1,385,000	1,390,000	1,395,000	1,400,000	1,405,000	1,410,000	1,415,000	1,420,000	1,425,000	1,430,000	1,435,000	1,440,000	1,445,000	1,450,000	1,455,000	1,460,000	1,465,000	1,470,000	1,475,000	1,480,000	1,485,000	1,490,000	1,495,000	1,500,000	1,505,000	1,510,000	1,515,000	1,520,000	1,525,000	1,530,000	1,535,000	1,540,000	1,545,000	1,550,000	1,555,000	1,560,000	1,565,000	1,570,000	1,575,000	1,580,000	1,585,000	1,590,000	1,595,000	1,600,000	1,605,000	1,610,000	1,615,000	1,620,000	1,625,000	1,630,000	1,635,000	1,640,000	1,645,000	1,650,000	1,655,000	1,660,000	1,665,000	1,670,000	1,675,000	1,680,000	1,685,000	1,690,000	1,695,000	1,700,000	1,705,000	1,710,000	1,715,000	1,720,000	1,725,000	1,730,000	1,735,000	1,740,000	1,745,000	1,750,000	1,755,000	1,760,000	1,765,000	1,770,000	1,775,000	1,780,000	1,785,000	1,790,000	1,795,000	1,800,000	1,805,000	1,810,000	1,815,000	1,820,000	1,825,000	1,830,000	1,835,000	1,840,000	1,845,000	1,850,000	1,855,000	1,860,000	1,865,000	1,870,000	1,875,000	1,880,000	1,885,000	1,890,000	1,895,000	1,900,000	1,905,000	1,910,000	1,915,000	1,920,000	1,925,000	1,930,000	1,935,000	1,940,000	1,945,000	1,950,000	1,955,000	1,960,000	1,965,000	1,970,000	1,975,000	1,980,000	1,985,000	1,990,000	1,995,000	2,000,000	2,005,000	2,010,000	2,015,000	2,020,000	2,025,000	2,030,000	2,035,000	2,040,000	2,045,000	2,050,000	2,055,000	2,060,000	2,065,000	2,070,000	2,075,000	2,080,000	2,085,000	2,090,000	2,095,000	2,100,000	2,105,000	2,110,000	2,115,000	2,120,000	2,125,000	2,130,000	2,135,000	2,140,000	2,145,000	2,150,000	2,155,000	2,160,000	2,165,000	2,170,000	2,175,000	2,180,000	2,185,000	2,190,000	2,195,000	2,200,000	2,205,000	2,210,000	2,215,000	2,220,000	2,225,000	2,230,000	2,235,000	2,240,000	2,245,000	2,250,000	2,255,000	2,260,000	2,265,000	2,270,000	2,275,000	2,280,000	2,285,000	2,290,000	2,295,000	2,300,000	2,305,000	2,310,000	2,315,000	2,320,000	2,325,000	2,330,000	2,335,000	2,340,000	2,345,000	2,350,000	2,355,000	2,360,000	2,365,000	2,370,000	2,375,000	2,380,000	2,385,000	2,390,000	2,395,000	2,400,000	2,405,000	2,410,000	2,415,000	2,420,000	2,425,000	2,430,000	2,435,000	2,440,000	2,445,000	2,450,000	2,455,000	2,460,000	2,465,000	2,470,000	2,475,000	2,480,000	2,485,000	2,490,000	2,495,000	2,500,000	2,505,000	2,510,000	2,515,000	2,520,000	2,525,000	2,530,000	2,535,000	2,540,000	2,545,000	2,550,000	2,555,000	2,560,000	2,565,000	2,570,000	2,575,000	2,580,000	2,585,000	2,590,000	2,595,000	2,600,000	2,605,000	2,610,000	2,615,000	2,620,000	2,625,000	2,630,000	2,635,000	2,640,000	2,645,000	2,650,000	2,655,000	2,660,000	2,665,000	2,670,000	2,675,000	2,680,000	2,685,000	2,690,000	2,695,000	2,700,000	2,705,000	2,710,000	2,715,000	2,720,000	2,725,000	2,730,000	2,735,000	2,740,000	2,745,000	2,750,000	2,755,000	2,760,000	2,765,000	2,770,000	2,775,000	2,780,000	2,785,000	2,790,000	2,795,000	2,800,000	2,805,000	2,810,000	2,815,000	2,820,000	2,825,000	2,830,000	2,835,000	2,840,000	2,845,000	2,850,000	2,855,000	2,860,000	2,865,000	2,870,000	2,875,000	2,880,000	2,885,000	2,890,000	2,895,000	2,900,000	2,905,000	2,910,000	2,915,000	2,920,000	2,925,000	2,930,000	2,935,000	2,940,000	2,945,000	2,950,000	2,955,000	2,960,000	2,965,000	2,970,000	2,975,000	2,980,000	2,985,000	2,990,000	2,995,000	3,000,000	3,005,000	3,010,000	3,015,000	3,020,000	3,025,000	3,030,000	3,035,000	3,040,000	3,045,000	3,050,000	3,055,000	3,060,000	3,065,000	3,070,000	3,075,000	3,080,000	3,085,000	3,090,000	3,095,000	3,100,000	3,105,000	3,110,000	3,115,000	3,120,000	3,125,000	3,130,000	3,135,000	3,140,000	3,145,000	3,150,000	3,155,000	3,160,000	3,165,000	3,170,000	3,175,000	3,180,000	3,185,000	3,190,000	3,195,000	3,200,000	3,205,000	3,210,000	3,215,000	3,220,000	3,225,000	3,230,000	3,235,000	3,240,000	3,245,000	3,250,000	3,255,000	3,260,000	3,265,000	3,270,000	3,275,000	3,280,000	3,285,000	3,290,000	3,295,000	3,300,000	3,305,000	3,310,000	3,315,000	3,320,000	3,325,000	3,330,000	3,335,000	3,340,000	3,345,000	3,350,000	3,355,000	3,360,000	3,365,000	3,370,000	3,375,000	3,380,000	3,385,000	3,390,000	3,395,000	3,400,000	3,405,000	3,410,000	3,415,000	3,420,000	3,425,000	3,430,000	3,435,000	3,440,000	3,445,000	3,450,000	3,455,000	3,460,000	3,465,000	3,470,000	3,475,000	3,480,000	3,485,000	3,490,000	3,495,000	3,500,000	3,505,000	3,510,000	3,515,000	3,520,000	3,525,000	3,530,000	3,535,000	3,540,000	3,545,000	3,550,000	3,555,000	3,560,000	3,565,000	3,570,000	3,575,000	3,580,000	3,585,000	3,590,000	3,595,000	3,600,000	3,605,000	3,610,000	3,615,000	3,620,000	3,625,000	3,630,000	3,635,000	3,640,000	3,645,000	3,650,000	3,655,000	3,660,000	3,665,000	3,670,000	3,675,000	3,680,000	3,685,000	3,690,000	3,695,000	3,700,000	3,705,000	3,710,000	3,715,000	3,720,000	3,725,000	3,730,000	3,735,000	3,740,000	3,745,000	3,750,000	3,755,000	3,760,000	3,765,000	3,770,000	3,775,000	3,780,000	3,785,000	3,790,000	3,795,000	3,800,000	3,805,000	3,810,000	3,815,000	3,820,000	3,825,000	3,830,000	3,835,000	3,840,000	3,845,000	3,850,000	3,855,000	3,860,000	3,865,000	3,870,000	3,875,000	3,880,000	3,885,000	3,890,000	3,895,000	3,900,000	3,905,000	3,910,000	3,915,000	3,920,000	3,925,000	3,930,000	3,935,000	3,940,000	3,945,000	3,950,000	3,955,000	3,960,000	3,965,000	3,970,000	3,975,000	3,980,000	3,985,000	3,990,000	3,995,000	4,000,000	4,005,000	4,010,000	4,015,000	4,020,000	4,025,000	4,030,000	4,035,000	4,040,000	4,045,000	4,050,000	4,055,000	4,060,000	4,065,000	4,070,000	4,075,000	4,080,000	4,085,000	4,090,000	4,095,000	4,100,000	4,105,000	4,110,000	4,115,000	4,120,000	4,125,000	4,130,000	4,135,000	4,140,000	4,145,000	4,150,000	4,155,000	4,160,000	4,165,000	4,170,000	4,175,000	4,180,000	4,185,000	4,190,000	4,195,000	4,200,000	4,205,000	4,210,000	4,215,000	4,220,000	4,225,000	4,230,000	4,235,000	4,240,000	4,245,000	4,250,000	4,255,000	4,260,000	4,265,000	4,270,000	4,275,000	4,280,000	4,285,000	4,290,000	4,295,000	4,300,000	4,305,000	4,310,000	4,315,000	4,320,000	4,325,000	4,330,000	4,335,000	4,340,000	4,345,000	4,350,000	4,355,000	4,360,000	4,365,000	4,370,000	4,375,000	4,380,000

1. The Bales (Georgetown, Norway and Marion counties, U. S. Dept. of Commerce (Letter sheets) from Landings Annual Summaries, U. S. Dept. of Commerce in cooperation with the S. C. Wildlife and Marine Resources Department and Brunswick, N. C., Landings, U. S. Dept. of Commerce (Letter sheets))

Table 14

CONSIDERED LEVELS OF IMPROVEMENT  
FOR NAVIGATION FACILITIES

ITEM	Plans of Improvement			
	A	B	C <sup>1/</sup>	D
PERTINENT DATA				
Entrance channel depth	8	10	12	14
Inner channel depth	6	8	10	12
Initial dredging (C.Y.)	950,000	1,120,000	1,290,000	1,510,000
Deposition basin				
Upcoast	450,000	450,000	450,000	450,000
Downcoast	230,000	230,000	230,000	230,000
Entrance channel	220,000	330,000	440,000	580,000
Inner channel	50,000	110,000	170,000	250,000
Annual maintenance				
dredging (C.Y.)	303,000	306,000	309,000	313,000
North Jetty length (ft)	3,790	3,790	3,790	3,790
South Jetty length (ft)	3,570	3,570	3,570	3,570
PROJECT FIRST COSTS	\$11,667,000	\$11,810,000	\$11,959,000	\$12,222,000
AVERAGE ANNUAL COSTS	\$1,330,200	\$1,343,800	\$1,358,700	\$1,382,300
Maintenance costs	551,000	555,000	560,000	566,000
Interest & amortization	779,200	788,000	798,700	816,300
BENEFITS				
Party boating	\$258,300	\$489,200	\$534,400	\$534,400
Charter boating	100,100	231,800	236,400	236,400
Recreational boating	297,200	321,000	351,600	351,600
Commercial fishing	321,300	423,700	485,300	492,500
Elimination of vessel damage	3,400	4,200	5,600	5,700
Harbor of refuge	18,400	18,400	18,400	18,400
Reduction in vessel operation costs	3,200	4,200	5,100	5,300
TOTAL ANNUAL BENEFITS (Navigation Facilities)	\$1,001,900	\$1,492,500	\$1,636,800	\$1,644,300
Excess of benefits over costs	0	148,700	278,100	262,000
Benefit-to-cost ratios	0.8	1.1	1.2	1.2

<sup>1/</sup> Recommended plan of improvement

# APPENDIX A

ECONOMIC DATA, EXTRACTED FROM U. S. ARMY, CORPS OF ENGINEERS GENERAL DESIGN MEMORANDUM, LITTLE RIVER INLET, SOUTH CAROLINA. COMPLETE DOCUMENT IS AVAILABLE AT U. S. ARMY ENGINEER DISTRICT, CHARLESTON, SOUTH CAROLINA

## SUMMARY OF ESTIMATED ANNUAL BENEFITS

<u>Item</u>	
NAVIGATION FACILITIES	
Party boating	\$ 534,400
Charter boating	236,400
Recreational boating	351,600
Commercial fishing	485,300
Elimination of vessel damage	5,600
Harbor of refuge	18,400
Reduction in vessel operating costs	5,100
TOTAL ANNUAL BENEFITS (Navigation Project)	<u>\$1,636,800</u>
RECREATION FISHING WALKWAY	112,000
REDEVELOPMENT	<u>74,600</u>
TOTAL PROJECT ANNUAL BENEFITS	<u>\$1,823,400</u>

## APPORTIONMENT OF FIRST COSTS

NAVIGATION FACILITIES	
Federal	\$9,999,700
Non-Federal	<u>1,959,300</u>
TOTAL	<u>\$11,959,000</u>
RECREATION FISHING WALKWAY	
Federal	\$ 510,000
Non-Federal	<u>510,000</u>
TOTAL	<u>\$ 1,020,000</u>
TOTAL PROJECT FIRST COST	<u>\$12,979,000</u>

## APPORTIONMENT OF AVERAGE ANNUAL COSTS

NAVIGATION FACILITIES	
Federal	\$1,227,800
Non-Federal	<u>130,900</u>
TOTAL	<u>\$1,358,700</u>
RECREATION FISHING WALKWAY	
Federal	\$ 32,950
Non-Federal	<u>58,950</u>
TOTAL	<u>\$ 91,900</u>


Benefit-Cost Ratio (Navigation Facilities)	1.2:1
Benefit-Cost Ratio (Recreation Fishing Walkway)	1.2:1

APPENDIX B

GRAIN SIZE ANALYSIS


DEPARTMENT OF THE ARMY, SOUTH ATLANTIC DIVISION LABORATORY  
CORPS OF ENGINEERS, 111 SOUTH COBB DRIVE, MARETTA, GA. 30061

WORK ORDER NO. 9824  
Req. No. SACEG-76-45



ENG FORM 2087  
1 MAY 63

\* Chemical Analysis on SAD Form 158-R.




ENG FORM 2087  
(MAY 75)

\* Chemical Analysis on SAD Form 158-R.

DEPARTMENT OF THE ARMY  
CORPS OF ENGINEERS

WASH DC 20315-5000  
ENGINEERING LABORATORY  
11 SOUTH FERRY DRIVE WASHINGTON DC 20047

WORK ORDER NO 9824  
REQ NO SAGEC-76-45



Project		Little River, S. C.	
Lab. No.		3S-609	
Area		---	
Boring No.		-- Sample No. 02-76006, LR1-3	
Date		4 June 1976	

GRADATION CURVES			
Sample No.	Depth	Classification	Notes
02-76006, LR1-3		gray poorly graded sand w/trace gravel size shell (SP)	

ENG 2087 Chemical Analysis on SAND FOR 158-R.





FIG. 2007



DEPARTMENT OF THE ARMY, SOUTH ATLANTIC DIVISION LABORATORY  
CORPS OF ENGINEERS, 611 SOUTH COBB DRIVE, MARETTA, GA. 30061

WORK ORDER NO. 3-24  
REQ. NO. SAGC-76-45




Sample No. 02-76010, LRI-7	Elev or Depth --	Classification Gray poorly graded gravel size shell fragments w/trace sand	Nat w % --	LL --	PL --	PI --
Project Little River, S.C. Lab. No. 3S-611 *						
Area --						
Boring No -- Sample No. 02-76010, LRI-7						
Date 4 June 1976						
GRADATION CURVES						

ENG FORM 2087

\* Chemical Analysis on SAD Form 158-R.

DEPARTMENT OF THE ARMY, SOUTH ATLANTIC DIVISION LABORATORY  
CORPS OF ENGINEERS, 611 SOUTH COBB DRIVE, MARLETTA, GA. 30061

WORK ORDER NO. 9824  
Req. No. SACEG-76-45



ENG FORM 2087  
1 MAY 63

\* Chemical Analysis on SAD Form 158-R.

APPENDIX C

Letters of Comment

## TABLE OF CONTENTS

	<u>Page No.</u>
U. S. Environmental Protection Agency	C-1
U. S. Department of Interior	C-1
U. S. Department of Commerce	C-3
Forest Service, USDA	C-4
Soil Conservation Service, USDA	C-5
Department of Health, Education and Welfare	C-6
Department of Housing and Urban Development	C-6
Federal Highway Administration, USDT	C-7
North Carolina Office of Marine Affairs	C-8
North Carolina Department of Human Resources	C-9
North Carolina Department of Natural and Economic Resources	C-10
South Carolina Wildlife and Marine Resources Department	C-10
South Carolina Department of Health and Environmental Control	C-12
South Carolina Department of Archives and History	C-12
South Carolina Water Resources Commission	C-13
Cape Fear Council of Governments	C-14
Waccamaw Regional Planning and Development Council	C-15

15 DEC 1976

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IV  
1425 PENTAGON AVENUE, N.E.  
ATLANTA, GEORGIA 30333



United States Department of the Interior

OFFICE OF THE SECRETARY

Southeast Region / 148 Cain St., N.E. / Atlanta, Ga 30303

ER-76/931

DEC 6 1976

Colonel Harry S. Wilson, Jr.  
District Engineer  
U.S. Army Corps of Engineers  
P. O. Box 913  
Charleston, South Carolina 29402

Dear Colonel Wilson:

This is in response to your October 12, 1976, letter. We have reviewed the draft environmental statement and design memorandum (D. 1) for Little River Inlet, navigation project in Brunswick County, North Carolina and Horry County, South Carolina for effects on fisheries, recreation, cultural resources, mineral resources, scientific resources, and fish and wildlife resources.

General Comments:

The statement does not adequately identify cultural resources nor does it adequately assess the project's potential impacts on these resources. Design memorandum no. 1 and the revised draft impact statement contain no information that assures cultural resources which exist in the project's vicinity area have received adequate consideration in the statement. The statement is primarily a project description and does not contain any information which the project has been designed to avoid, minimize, or compensate for. However, the statement does contain adequate steps taken by the Corps of Engineers to fulfill its responsibilities to identify and protect cultural resources which may or will be affected by implementation of the project. Consideration of cultural resources, as required by 33 CFR, part 326, should provide adequate data for presentation in the final statement.

Minor quantities of sand and gravel are produced in Brunswick and Horry Counties, with a small amount of clay also being produced in Horry County. No records show evidence of mineral production or significant resources in the immediate vicinity of the proposed project site. Implementation of this proposal should result in no significantly adverse impact on the mineral resources of the area.

October 19, 1976

Colonel Harry S. Wilson, Jr., USA  
District Engineer  
U.S. Army Corps of Engineers, Charleston District  
P. O. Box 913  
Charleston, S.C. 29402

Dear Colonel Wilson:

The Environmental Protection Agency has reviewed the Draft Environmental Impact Statement for the Little River Inlet Navigation Project in Brunswick County, North Carolina and Horry County, South Carolina and we have no objections to the proposed project. We will continue to monitor/assess for the environmental impact of the project as well as reasonable alternatives.

During our review, we have categorized the project LO (Lack of Information) and the Impact Statement I (Adequate). We will immediately receiving one copy of the Final Statement when available, and if we may be of further assistance, please let us know.

Sincerely yours,  
*John E. Hogan, III*  
John E. Hogan, III  
Chief, EIS Branch

Specific Comments

⑧ Page 2, line 25-27

In the first paragraph of the marsh, this paragraph fails to mention the fact that the marsh serves as a spawning and nursery area for a variety of sport and commercial finfish. A list of some of the important species of the project area include mullet, striped bass, channel bass, sea trout, spotted Atlantic croaker, and blue crabs.

⑨ Page 2, line 28-30

The statement should be expanded to provide information on the extent and nature of adverse cultural resources in the area affected. If the statement is not sufficient to assure adequate examination of the area has occurred, it is the responsibility of the Corps of Engineers to conduct a survey sufficient to identify all resources. All resources must be evaluated for significance.

⑩ Page 2, line 31-33

The statement should be expanded to provide specific information on the magnitude of the adverse cultural resources in the area affected. It should also mention the fact that the Corps of Engineers is responsible for the disposal of dredge spoil disposal areas on beaches.

⑪ The statement should be expanded to provide the author to be typed by the proposed project manager and should state whether any appreciable adverse cultural resources are present.

⑫ Page 2, line 34-36

The statement should be expanded to provide information on the southside dike may require the filling of the marsh area with fill and one acre of high marsh at the mouth of the dike. The fish and wildlife Service has stated that there is a less biologically damaging dike system which has been proposed. Relocation of the south sand dike and the marsh area will be one after high marsh and wooded upland areas.

⑬ Page 2, line 37-39

This section should be expanded to discuss impacts on cultural resources which are not on the National Register as well as those which may be eligible for nomination to the Register.

The statement "Construction would be coordinated with the State Historic Preservation Officer and State Archaeologist to minimize potential damage to sites of historical or archaeological interest in the area" is interpreted to mean that cultural resources will only be considered after planning has been completed and construction initiated. This action would circumvent federal agency responsibilities in identification and protection of cultural resources which must be done in the planning as well as in construction stages. We recommend this sentence be omitted from the final statement and replaced with an adequate discussion of potential impacts recognized as a result of adequate resource identification and evaluation. Steps planned to mitigate potential impacts should be discussed.

⑭ Page 2, section 8.0

This section should be expanded to include discussion of impacts on cultural resources. Protection is a primary responsibility in federal agency planning. Discussion should clearly indicate efforts made to protect significant resources. Alteration or salvage of significant resources are clearly adverse impacts and should be undertaken only after a determination is made, in consultation with the State Historic Preservation Officer and the Advisory Council on Historic Preservation, that there is no other alternative.

⑮ Page 4, section 8.0

This section should be expanded to include cultural resources.

Thank you for the opportunity to review and comment on the draft statement and design memorandum.

Sincerely yours,

*June Whelan*

(Miss) June Whelan  
Special Assistant to the Secretary  
Southeast Region



UNITED STATES DEPARTMENT OF COMMERCE  
The Assistant Secretary for Science and Technology  
Washington, DC 20230

December 6, 1976

Col. Harry S. Wilson, Jr.  
Corps of Engineers  
Department of the Army  
P. O. Box 917  
Charleston, South Carolina 29402

Dear Colonel Wilson:

This is in reference to your revised draft environmental impact statement entitled, "Little River Inlet, Navigation Project, Brunswick County, North Carolina and Horry County, South Carolina". The enclosed comments from the National Oceanic and Atmospheric Administration are forwarded for your consideration.

Thank you for giving us an opportunity to provide these comments, which we hope will be of assistance to you. We would appreciate receiving eight copies of the final statement.

Sincerely,

*John P. Miller*  
John P. Miller  
Deputy Assistant Secretary  
for Environmental Affairs

Enclosures      Memo from National Ocean Survey



U.S. DEPARTMENT OF COMMERCE  
National Oceanic and Atmospheric Administration  
NATIONAL OCEAN SURVEY  
Rockville, Md. 20852

C52/JLP

NOV 30 1976

DEC 2 1976

TO: William Aron

Director

Office of Ecology and Environmental Conservation

FROM:

Gordon Liff

Deputy Director

National Ocean Survey

SUBJECT: DEIS #7510.33 - Little River Inlet Navigation Project, N.C.

The subject statement and General Design Memorandum (GDM) have been reviewed within the areas of NOS responsibility and expertise, and in terms of the impact of the proposed action on NOS activities and projects.

The following comments are offered for your consideration.

In compliance with a Cooperative Agreement between the U.S. Army Corps of Engineers (CE), Charleston District, and the National Ocean Survey (NOS), NOS installed ADC (Analog to Digital) tide gages at 13 CE installations throughout the Little River system in an effort to obtain tidal datums in the area.

① In paragraph 2.18 of the DEIS, CE states that at a point one mile above the mouth of the Little River Inlet (NOS assumes that CE means 1.0 mile inland) the mean tide range is 5.0 feet and the spring range is 5.9 feet. The NOS measurements for this general area indicate a mean tide range of 4.5 feet to 4.7 feet and a spring range of 5.2 feet to 5.4 feet depending upon the exact location of interest. Final datums computed from NOS measurements taken at the town of Little River indicate a mean tide range of 4.4 feet and a spring range of 5.0 feet.

② NOS has not completed a rigorous study and analysis of the circulation in the Little River system. The statements made in paragraph 4.02 in the DEIS and paragraph 51 of the GDM could be investigated further. NOS agrees that CE's expectation of an initial 10 percent decrease in the tidal prism in the Little River Inlet is probably a fair estimate.

CE then predicts that this 10 percent reduction in the tidal prism will decrease after channel stabilization to a mere 0.1 foot shift downward in both the mean high water and the mean low water datums. This is interpreted to mean CE expects no change in the tidal prism after channel stabilization. Whether this prediction is based on CE's hydraulic model of the inlet, or if there is other supporting evidence that was not included, is unclear.

(3) NOS agrees that there will be a certain amount of scouring in the proposed outer channel due to an increased ebb flow in that area. However, the extent of deposition and subsequent change in tidal prism which will occur in the proposed inner channel due to the possible decrease in ebb flow velocities in these areas, have not been addressed.

(4) Finally, NOS inquires about the availability of results from past navigation improvement projects, similar to the one proposed, to support CE's prediction of no significant change in tidal heights occurring as a result of project construction in the Little River system.

UNITED STATES DEPARTMENT OF AGRICULTURE  
FOREST SERVICE  
1720 Peachtree Road, N. W.  
Atlanta, Georgia 30309

November 26, 1976  
8400



Colonel Harry S. Wilson, Jr.  
Department of the Army  
Charleston District  
Corps of Engineers  
P.O. Box 919  
Charleston, South Carolina 29402

Dear Colonel Wilson:

The United States Forest Service, State and Private Forestry review of the revised draft environmental impact statement covering the Little River Inlet Navigation Project in Brunswick County, North Carolina, and Horry County, South Carolina, reveals no significant project impacts on forest lands or resources in the area. Consequently, we have no comments on the proposal.

Thank you for the opportunity to review and comment on the revised draft EIS.

Sincerely,

ROBERT K. DODSON  
Area Environmental Coordinator

Copy: State Forester: North Carolina  
South Carolina



UNITED STATES DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

201 Stonewall Drive, Columbia, South Carolina 29210

October 27, 1976

Colonel Harry S. Wilson, Jr.  
District Engineer  
District Engineer, Corps of Engineers  
Department of the Army  
P. O. Box 319  
Charleston, South Carolina 29402

Dear Colonel Wilson:

Thank you for reference to your recent request for comments on the draft environmental impact statement and draft General Design Memorandum for the Little River Inlet Navigation Project, South Carolina.

We are not finding a vegetative plan relative to the construction involved in this project. It appears to us that much of the proposed sand dike shall be vegetated. In certain areas the dike appears to be primarily in an area of the frontal dune system. Adapted vegetation is a critical element in dune stabilization.

It is recommended that a study be made of the proposed sand dike as well as other areas of planned disturbance and a supporting vegetative plan prepared.

Sincerely,

*James E. Shuler*

James E. Shuler  
Assistant State Conservationist

UNITED STATES DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

P. O. Box 27397, Raleigh, North Carolina 27611  
Telephone 919 755-4210

October 29, 1976

Colonel Harry S. Wilson, Jr.  
District Engineer, Corps of Engineers  
Department of the Army  
P. O. Box 319  
Charleston, South Carolina 29402

Dear Colonel Wilson:

We received three copies of the revised draft environmental impact statement for the Little River Inlet Navigation Project, South Carolina. The statement is located about entirely within South Carolina with the exception of the sand dike on Bird Island across the state line in North Carolina.

The cover letter transmitting copies of the statement did not identify our North Carolina organization. We assume the copies are primarily for information. George E. Hovey, South Carolina State Conservationist, Soil Conservation Service, has received the report and is preparing a response. We have no comment on the statement.

Sincerely,

*James I. Hicks*

James I. Hicks  
State Conservationist

cc: Council on Environmental Quality, 722 Jackson Place, N.W., Washington, D. C. (5 copies)  
USDA Coordinator of Environmental Activities, Office of the Secretary, U.S. Department of Agriculture, Washington, D.C. 20250  
R. M. Davis, Administrator, SCS, Washington, D.C.  
S. G. Lane, Director, State Soil & Water Conservation Commission, Raleigh, N.C.  
G. E. Hovey  
J. V. Martin



DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

REGION IV  
Regional Environmental Standards Officer  
1301 Peachtree Street, N.E.  
Atlanta, Georgia 30309

November 23, 1976

HEM-705-10-76

Harry S. Wilson, Jr.  
Colonel, Corps of Engineers  
District Engineer  
Department of the Army  
Charleston District Corps of Engineers  
P.O. Box 919  
Charleston, South Carolina 29402

Subject: Little River Inlet  
Navigation Project  
Barnwell County, North Carolina  
and Horry County, South Carolina

Dear Mr. Wilson:

We have reviewed the subject draft Environmental Impact Statement (Revised). Based upon the data contained in the draft, it is our opinion that the proposed action will have only a minor impact upon the human environment within the scope of this Department's review. The impact statement has been adequately addressed for our comments.

Sincerely yours,  
*Philip P. Sayre*  
Philip P. Sayre  
Regional Environmental Officer  
DHM - Region IV



DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

AREA OFFICE  
415 NORTH DORCHESTER STREET  
GREENSBORO, NORTH CAROLINA 27401

January 7, 1977

REGION IV  
Regional Environmental Standards Officer  
1301 Peachtree Street, N.E.  
Atlanta, Georgia 30309

4-455

U. S. Army Engineer District  
Corps of Engineers  
Charleston, South Carolina

Dear Sirs:

Subject: Draft Environmental Impact Statement (Revised)  
Little River Inlet  
Navigation Project  
Barnwell County, N. C.  
Horry County, S. C.

Thank you for the opportunity of reviewing the proposal. We have no substantive comments to make at this time.

Sincerely,  
*Philip P. Sayre*  
Philip P. Sayre  
Area Director

cc: Regional Environmental Standards Officer



U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
2001 Assembly Street, Suite 203  
Columbia, South Carolina 29201

October 22, 1976

Colonel Harry S. Wilson, Jr.  
Charleston District, Corps of Engineers  
Post Office Box 919  
Charleston, South Carolina 29402

Dear Colonel Wilson:

Reference is made to your letter dated October 12, 1976 transmitting the draft environmental impact statement for the Little River Inlet Navigation Project, South Carolina.

We have reviewed the statement and find that the proposal does not conflict with present or planned highway facilities within FWA mission areas.

Sincerely yours,

*W. H. Rice, Jr.*  
W. H. Rice, Jr.  
District Engineer

For B. G. Cloyd  
Division Administrator



North Carolina Department  
of Administration

OFFICE OF  
INTERGOVERNMENTAL  
RELATIONS  
EDWIN DECADE  
DIRECTOR

JAMES E. HOUNSCLOUGH, JR. GOVERNOR • ROUTE A 1EN1Z, SECRETARY

November 29, 1976

Colonel Harry S. Wilson, Jr.  
Charleston District, Corps of Engineers  
Department of the Army  
Post Office Box 919  
Charleston, South Carolina 29402

Dear Colonel Wilson:

Re: SCH File #159-76; Draft (Provised) FIS-  
Little River Inlet Navigation Project;  
Berkeley County, NC & Horry County,  
South Carolina

SCH File #159-76; General Design Memo-  
randum - Little River Inlet, NC & SC

The State Clearinghouse has received and reviewed the above referenced projects. As a result of this review, the State Clearinghouse has received comments from the office of Marine Affairs and Department of Human Resources. Comments from both Departments are attached.

We appreciate the opportunity comment on the above referenced projects. If we may be of further assistance in this matter, please let us know.

Sincerely,

*Chrys Baggett*

Chrys Baggett (Mrs)  
Clearinghouse Supervisor

CB:mw  
cc: Region "O"

Attachments



North Carolina State Clearinghouse Comments

SCH # 158-76

Date: November 29, 1976

- ① The Department of Human Resources submits the following comment: We have no objections to this project construction is in accordance with submitted plans.

SCH # 159-76

Date: November 29, 1976

- ② The Department of Human Resources submits the following comment: We have no objections to this project provided plans are included for the control of mosquitoes that are created in those areas in which the spoil is dyked. The dyked spoil islands have created severe mosquito problems in many areas of the state and appropriate plans must be devised for the control of mosquitoes in these specific areas.

C-9

North Carolina Department  
of Administration

OFFICE OF  
INTERGOVERNMENTAL  
RELATIONS  
DIVISION  
PLANS

JAMES E. HODGKINS, JR., GOVERNOR • BRUCE A. LENTZ, SECRETARY

January 4, 1977

MEMORANDUM

TO: Colonel Harry S. Wilson, Jr.

FROM: Chrys Baggett (Mrs) *CB*

SUBJECT: Little River Inlet Navigation Project, SCH #158-76  
and SCH #159-76, General Design Memorandum

Attached are additional comments which were submitted following our clearance letter on your

\_\_\_\_ Notification To Clearinghouse Of Intent To Apply  
For Assistance

\_\_\_\_ Application for funding

\_\_\_\_ XXX Environmental Impact Statement

\_\_\_\_ Environmental Review

If you have questions regarding these comments please contact me at (919) 829-2591.

CB/mw  
cc: Region "O"



James A. Timmerman, Jr., Ph.D.  
Executive Director  
Edwin B. Joseph, Ph.D.  
Director  
Marine Resources Center

**December 8, 1976**

Elmer C. Whitten, Jr.  
State Clearinghouse  
Division of Administration  
1205 Pendleton Street  
Columbia, South Carolina 29201

**Re: 08-2002-7; Little River Inlet  
Navigation Project**

Dear Mr. Whitten:

The attached letter from Charles Bearden to Duncan Newkirk represents the Department's preliminary comments on this project. Any additional comments will be forwarded to your office next week.

Thank you for your help on this project. We will advise you of the final comments on this project by Friday, December 17.

**Sincerely,**

James A. Zimmerman, Jr.  
JAMES A. ZIMMERMAN, JR.  
Barrister at Law, District of Columbia

JATjr:lsb  
enclosure  
cc: John Carothers, Corps of Engineers

P. O. Box 12559 □ Charleston, South Carolina 29412 □ Telephone (803) 795-4350


January 5, 1977

16: Cary: 6, 11, 14

0.75 cm

**SOURCE:** Little River Inlet Navigation Project, SOI #19-76 and  
General Design Memorandum, SOI #19-76

But the public role of Animal Care, the Wildlife Protection, and the Fish and Game Service, is not to exercise direct protection in such a manner as to deprive the water and air quality in the estuary of the natural character, stability, and amenity that the Federal Government has a responsibility to maintain. The development program has a goal that the CEIS has already addressed, and subject of interest to them. Therefore, the CEIS should not be a condition to offering.



James A. Tormey, Jr., Ph.D.  
Executive Director  
Eugene B. Cress, Ph.D.  
Director  
Marvin R. Gorman, C.E.S.

November 8, 1976

8-11-63

三、

We have completed our review of the revised draft environmental impact statement for the U. S. Army Corps of Engineers' Little River Inlet Navigation Project and hereby recommend that the project be approved.

[illegible]

1. The following specific comments refer to various sections of the draft environmental impact statement:

- (1) P. 2, Para. 1.65. Sund dikes. The report indicates that upon completion the sund dikes will be planted with sea oats or other tolerant plants to aid in erosion controls. A list of suitable plants would be desirable.
- (2) P. 17, Para 2.34. Moisture shrub thickets. Two mammals, raccoon and deer, should be included in the list of animals that may be present in shrub thickets.
- (3) P. 19, Para 2.40. Flotation. Amphipods and isopods should not be considered as benthic members of their own community. Since they are characteristic part of the benthon community (i.e., Gammarid amphipods) or part of the benthic community (i.e., Copepodid amphipods and Cylindrus isopods which are both known to be semi-invertebrates). Also, the bearded shrimp, such as

[illegible]

Mr. Duncan Newkirk  
November 8, 1975  
Page 2

the white spring, brown spring, and yellow spring, are

(4) (u) P. 24, Para. 2.54. L. 24. " ...13 tidal gauge stations..." and P. 42, Para. 2.54. L. 24. " ...19 tidal gauge stations..."

(5) P. 25, Para. 2.57. Since this paragraph cannot describe the importance of fish and fish products, it also cannot be used to support the importance of fish and fish products, and fish and fish products, and fish and fish products, and fish and fish products.

[illegible]

(7) P. 27, Para. 2-52. Discrepancies are shown in the Little River Plant, where there was such as March 6, 1958, and March 10, 1958, to the other plants, which were not included.

(8) P. 36, para. 2.19. Fourth, regarding the use of the word "work" on the initial stages, this phraseology is not consistent with the construction of the card deck. Most of these cards are designed to move into adjacent areas, as indicated by the arrows, and are not moved by deposition of the sandy material. This is a significant difference that should be noted.

(3) General current on alignment of main line is 1000 amperes. The effect of the higher current will be mitigated by slightly altering the proposed alignment. As currently proposed, about three acres of marsh and high marsh will be destroyed by construction of the proposed alignment. The proposed alignment will be located to and south of existing causeway on Wal-es Islands, near the habitat and some wooded upland habitats would be affected. Some existing high marsh near destruction. It would only be removed the extent if it is technically feasible and will not affect the proposed project.

We appreciate having the opportunity to comment on this presentation.

*Charles*

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84



# **SOUTH CAROLINA DEPARTMENT OF HEALTH AND ENVIRONMENTAL CONTROL**

E. KENNETH ARCECK, M.D., MPH, COMMISSIONER  
J. MARION SIMS BUILDING — 700 BULL STREET  
COLUMBIA, SOUTH CAROLINA 29201

October 25, 1976

Colonel Harry S. Wilson  
District Engineer  
Department of the Army  
Charleston District, Corps of Engineers  
Post Office Box 919  
Charleston, South Carolina 29402

Dear Colonel Wilson:

Your office has reviewed the Draft Environmental Impact Statement for the Little River Inlet Navigation Project, and we do not anticipate any significant adverse environmental impacts on the Little River Inlet Navigation Project.

We appreciate the opportunity to comment on this proposed project and we are of any assistance, please contact us.

Sincerely,

*James G. Zack, Jr.*  
James G. Zack, Jr.  
Environmental Analysis Section  
Programs Development Division  
Bureau of Wastewater & Storm  
Quality Control

cc: Mr. James G. Zack, Jr.

BOARD MEMBERS  
L. J. BROWN, JR., Chairman  
W. H. WILSON, Vice Chairman  
J. D. BROWN, Secretary  
W. A. BROWN, Jr.  
L. J. BROWN, Jr.  
J. D. BROWN, Jr.  
W. A. BROWN, Jr.



South Carolina Department of Archives and History  
1430 Senate Street  
Columbia, S. C.

P. O. Box 1000  
Columbia, S. C. 29201  
803 — 746 1816

November 5, 1976

Colonel Harry S. Wilson  
District Engineer  
Department of the Army  
Charleston District, Corps of Engineers  
Post Office Box 919  
Charleston, South Carolina 29402

Dear Colonel Wilson:

We are in receipt of the Revised Draft Environmental Impact Statement for the Little River Inlet Navigation Project, and we do not anticipate any significant adverse environmental impacts on the Little River Inlet Navigation Project. In review of the draft, it appears that an adequate assessment of historic and archeological values has been incorporated and appropriate provisions made (4.22) to minimize potential damage to these values.

Sincerely,

*Charles E. Lee*  
Charles E. Lee  
State Historic Preservation Officer

CEL/sa



State of South Carolina

Office of the Governor

November 24, 1976

Division of Administration  
Columbia, South Carolina 29201

Mr. Elmer C. Whitten, Jr.  
State Office Building  
Division of Administration  
Edward A. Brown Building  
Columbia, South Carolina 29201

Re: Revised Draft EIS for the Little  
River Outlet Navigation Project

Dear Mr. Whitten:

The staff of the South Carolina Water Resources Commission has received the revised draft environmental impact statement for the Little River Outlet Navigation Project and the preliminary design memorandum (PDM) for the same project. Overall it appears that the Corps of Engineers has presented a well prepared proposal, although we wish to offer several minor comments and suggestions.

The staff of the South Carolina Water Resources Commission has received the revised draft environmental impact statement for the Little River Outlet Navigation Project and the preliminary design memorandum (PDM) for the same project. Overall it appears that the Corps of Engineers has presented a well prepared proposal, although we wish to offer several minor comments and suggestions.

If you have any further assistance, please contact me.

*Elmer C. Whitten, Jr.*  
Governor

Enclosure  
11/24/76

State of South Carolina  
Water Resources Commission

Elmer C. Whitten, Jr.  
Executive Director

November 24, 1976

Re: Revised Draft EIS for the Little  
River Outlet Navigation Project

Dear Mr. Whitten:

The staff of the South Carolina Water Resources Commission has received the revised draft environmental impact statement for the Little River Outlet Navigation Project and the preliminary design memorandum (PDM) for the same project. Overall it appears that the Corps of Engineers has presented a well prepared proposal, although we wish to offer several minor comments and suggestions.

- ① Section 1.1.10 Recreation Facilities. The impact of the proposed navigation project by the Corps and the proposed recreation park by P&H are totally unrelated and should be separated. The benefits for the fishing walkway should be excluded unless the Corps of Engineers plans to build the walkway exclusive of P&H interests.
- ② Section 1.1.11 The recommended plan of improvement for recreation should require a separate environmental impact statement.
- ③ Section 1.1.13 Comfort Station. Relative to the responsibilities of the National Flood Insurance Program, what measures will be taken during the construction of this facility?
- ④ Section 1.1.17 Parking. It appears that 4 miles of travel by walkway will be required from the parking area to the jetty. We also recommend changing the design of the parking stalls from the proposed 994 pattern to 450 or 450 stalls. Attention less efficient in terms of overall capacity, while parking facility for proven maneuverability into the stalls, with accessibility for handicapped facilities, and may be required to be more aesthetically appealing.
- ⑤ Section 1.1.25 The wooden decking over the weir section could be replaced by prefabricated concrete slabs. Although more expensive initially, the wooden decking will require more maintenance and their strength will reduce through the deterioration process, even daily treatment with safety boards.

# CAPE HARR COUNCIL OF GOVERNMENTS

PO BOX 100  
 P.O. Box 100  
 WASHINGTON, N.C. 27884

South Carolina Department of Transportation  
 1000 North Main Street  
 Columbia, South Carolina 29201

November 22, 1976

Page 2 of 2

Director  
 U.S. Army Engineer District  
 P.O. Box 419  
 Charleston, South Carolina 29402

Dear Sir:

Enclosed for the U.S. Army Engineer District are two copies of a letterhead memorandum (LHM) dated and captioned as above.

The Cape Harr Council of Governments has a project in progress to develop a regional goals and objectives study. This study will be completed in 1977 and will provide information for the development of regional programs. The adverse information is being furnished for your information.

This letter conveys the official position of the Cape Harr Council of Governments.

Very truly yours,  
 [Signature]  
 Executive Director

APP/ab  
 cc: Chrys Baggett, Clearinghouse Supervisor

Enclosed for the U.S. Army Engineer District are two copies of a letterhead memorandum (LHM) dated and captioned as above.

- ② Sections 4.74 through 4.80 Why have updated data not been utilized?
- ③ Section 4.81 Recommendation. Recent contact with the S.C. Highway Commission has indicated that the "Grand Strand Expressway" from Charleston, S.C. to the title shown, S.C. was a conceptual design and has not been funded yet. Route S.C. 9 is shown as a design in the construction of land access since existing widening has taken place and additional widening will be continuing.

Section 4.80 The Possible Impact of the Proposed Action on the Environment. This project is generally undesirable from an environmental viewpoint; however, it is not necessarily devastating. It is hoped that the benefits will accrue to a limited number of individuals and that the project will not cause any limited environmental damage to the area public.


The Cape Harr Council of Governments appreciates the opportunity to comment on the proposed action and the navigation project and offers any assistance to the Corps of Engineers that will aid in its implementation.

Very truly yours,

Chair P. Gueas, Jr.  
 Executive Director

ENCLOSURE

WACCAMAW REGIONAL  
PLANNING AND DEVELOPMENT COUNCIL



November 10, 1976

Colonel Harry S. Wilson, Jr.  
1015 Elm Street  
Post Office Box 919  
Farmington, South Carolina 29402  
Dear Colonel Wilson:

The staff of Waccamaw Regional Planning and Development Council has prepared a draft Environmental Impact Statement for the Little River Bridge, located on Highway 17, near the town of Little River, South Carolina. Enclosed are general and specific comments on the draft statement regarding the content of said document; they are for your information.

- ① 1. Should all the plates contained in this report be grouped together in the back portion or should they follow pages referring to such plates?
- ② 2. Why does plate 5 lack a legend?
- ③ 3. Will this project affect America's hydrology, e.g., increased erosion and sedimentation which may affect future waste disposal, particularly Plant No. 1, Grand Strand 201?
- ④ 4. Section 1.10, p. 31: Has the South Carolina Department of Parks, Recreation and Tourism committed itself on the question of purchase of Morris Island for development as a park, as well as the construction of a fishing walkway? If so, has PRT budgeted operating expenses and will they operate the park?
- ⑤ 5. Section 1.22, p. 51: Does "one percent of the construction cost" refer to the construction cost of the jetties or the entire project? This ambiguity should be clarified by inserting the proper estimated dollar amount.
- ⑥ 6. Sections 2.24, 2.28 and 2.52, pp. 14, 15 and 24: In light of the proposed new federal regulations naming the Atlantic loggerhead sea turtle a "threatened" species and the apparent position of concern by the South Carolina Wildlife and Marine Resources Department, will this project require any necessary reworking of the project to avoid any adverse impact on the nesting of this species of sea turtle?

Colonel Harry S. Wilson, Jr.  
November 10, 1976  
Page 2

Thank you for providing Waccamaw Regional Planning and Development Council with the opportunity to read and comment on the draft Environmental Impact Statement.

Respectfully,

*James L. Corbin*  
James L. Corbin  
Chief of Staff, Waccamaw Regional Planning and Development Council

JLC:pc

APPENDIX D

Reference List for Section 404 Evaluation

Reference List for Section 404 Evaluation

33 CFR 209.145

209.145 e. Factors to be considered in the evaluation of Federal projects involving the disposal of dredged materials in navigable or ocean waters.

(1) Disposal of dredged materials in navigable waters. The proposed project would involve the disposal of dredged materials in navigable waters at a specified disposal site (paragraphs 1.18, 1.22, and 4.0 of the EIS). This proposed disposal has been evaluated by the application of guidelines developed by the Administrator, EPA, in conjunction with the Secretary of the Army pursuant to section 404(b) of the Federal Water Pollution Control Act. The 404(b) evaluation is presented below in paragraphs 230.4 and 230.5.

(2) Disposal of dredged material in ocean waters. Not applicable since no aspect of this project comes under the purview of P.L. 92-532.

(3) Effects on wetlands. The only wetlands which would be impacted by disposal are beach areas above mean low water. Since these areas currently have a severe erosion problem, the overall impact of using these wetland areas for disposal is in the nature of restoration and would be beneficial.

(4) Fish and wildlife. The EIS and GDM have been coordinated with all responsible Federal and State agencies in accordance with the Fish and Wildlife Coordination Act. All reports and suggestions submitted by these agencies were considered during project formulation (Appendix C of the EIS and paragraph 50 and Exhibits 1-17 of the GDM).

(5) Historic, scenic, recreational, and conservation values. Due consideration has been given to the effect which the disposal of dredged material may have on the enhancement, preservation, or development of such areas. It has been determined that the project offers no potential for adversely affecting: (1) any properties on the National Register of Historic Places; (2) endangered species; (3) rivers named in Section 3 of the Wild and Scenic Rivers Act; and (4) any other areas named in Acts of Congress or Presidential Proclamations as National Rivers, National Wilderness Areas, National Seashores, National Lakeshores, National Parks, National Monuments, and such laws as may be established under Federal law for similar and related purposes, such as marine and estuarine sanctuaries (paragraphs 4.20, 4.22, and 4.23 of the EIS).

(6) Disposal of dredged material in coastal zones and marine sanctuaries. Not applicable since the State of South Carolina does not have a coastal zone management plan approved by the Secretary of Commerce and the project area is not within a marine sanctuary established by the Secretary of Commerce.

1. Final discharge permit. The discharge of dredge material in this paragraph five feet below the water for this project (Section 9.0 and Appendix C of the EIS and paragraphs 34, 35, 50, and 69 and Exhibits 1-17 of the GDM).

4. Public notice. See public notice number 444 coordination with the Department of the Environment.

#### ROW Guidelines, Discharge of Dredged or Fill Material in Navigable Waters

##### 4.01.4-1

#### Excavated and fill material for beach nourishment

a. Excavated material. Approximately 3,000,000 cubic yards of material will be excavated during actual period of construction. All of this material will be used for and after construction, beach nourishment projects. Material to be placed will involve the periodic removal of approximately 300,000 cubic yards of material annually. All material will be used for nourishment of adjacent beaches.

b. Large quarry-stone. The material placed and discussed above, large quarry-stone will be placed in the jetties. The upcoast jetty would be 3,490 feet long and the downcoast jetty 3,490 feet long. The maximum width of the jetty would be 15 feet and the maximum bottom width of the jetty would provide substrate and cover for a variety of bottom animals and would support a jetty related sport fishery which is presently available in the area (paragraph 4.13 of the EIS).

c. Immediate area of fill. In the immediate area of fill would be destroyed. There would be no significant or permanent impairment of the water column as a result of the proposed work (see paragraph 1.04-1.08, 1.10-1.13, 4.0 and 4.01 of the EIS and paragraphs 65, 66, 103-109 and 142 of the GDM).

d. Geological- biological interactive effects. Since the materials to be used are either from the immediate area or consist of large quarry-stone, they qualify for exclusion from the evaluative procedures specified in paragraphs (1)(2) and (3). (see paragraph 4.15 and Appendix B of the EIS).

e. Comparison of excavated and fill material with the disposal site. The excavated material is of the same consistency and constituency as the area into which it will be placed and the quarrystone is compatible with the sediments upon which it will be placed (paragraphs 53-62 and Appendix C of the GDM and Appendix B of the EIS).

230.4-2 Water quality considerations. Construction and operation and maintenance of the Little River Jetty construction project would not result in contravention of any State, interstate, or local water quality



10

Number of hauls	<i>P. setiferus</i> (%)	<i>P. setiferus</i> + <i>P. setiferus</i> + <i>P. setiferus</i> (%)
1	10	5
2	30	10
3	50	15
4	70	18
5	85	20
6	95	22
7	100	23
8	100	24
9	100	25
10	100	26

10



10

drift patterns so that the project would not cause erosion of any beaches in the area (paragraph 4.13, 4.23, and 4.29 of the EIS).

There would be no eutrophication, degradation of aesthetic values or impediment of recreation uses due to release of nutrients from dredged or fill material (paragraph 4.01 of the EIS).

(6) Threatened and endangered species. The proposed project would not jeopardize the continued existence of threatened or endangered species or destroy or modify the habitat of those species determined critical in accordance with the Endangered Species Act (paragraph 4.20 of the EIS).

(7) Benthic life. Any benthic life in the disposal area would be smothered by deposition of dredged materials. This loss would not significantly affect the area's long-term productivity since animals in these areas characteristically undergo rapid population turnovers and would be replaced by recruitment from adjacent areas (paragraph 4.15 of the EIS). The jetties would provide substrate and cover for a variety of plant and animal life (paragraph 4.13 of the EIS).

(8) Wetlands. Utilizing excess dredged materials for beach nourishment above mean low water is the most beneficial disposal alternative. Disposal in these wetlands would not have an unacceptable adverse impact on aquatic resources. The proposed fill and the activity associated with it will not cause a permanent unacceptable disruption to the beneficial water quality uses of the affected aquatic ecosystem (paragraphs 4.15 and 4.18).

(9) Submersed vegetation. No areas of submersed vegetation would be destroyed or adversely affected by the proposed action.

(10) Size of the disposal area. The size of the proposed disposal areas is the smallest practicable to perform the design functions of this project.

(11) Contaminated fill material restrictions. There will be no deposition, discharge, leaching, or erosion of contaminated material associated with this project (paragraph 4.01 and Appendix B of the EIS).

(12) Mixing zone determination. Not applicable.



**END**

**FILMED**

**3-85**

**DTIC**

